

PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY.

W.P ITEM NO. D1166 NB/NB/2401 JOB NO. 10225L MMBE&MA/SDBE&F/01/2024-2025

TENDER DOCUMENT

CLIENT STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES P.O.BOX 58187 – 00200 NAIROBI

PROJECT MANAGER

WORKS SECRETARY

S.D.P.W

P.O.BOX 30743-00100

NAIROBI

QUANTITY SURVEYOR

CHIEF QUANTITY SURVEYOR

S.D.P.W

P.O.BOX 30743-00100

NAIROBI

STRUCTURAL ENGINEER

CHIEF ENGINEER (STRUCTURAL)

S.D.P.W

P.O.BOX 30743-00100

NAIROBI

INTERIOR DESIGNER

CHIEF DESIGNER

S.D.P.W

P.O.BOX 30743-00100

NAIROBI

ARCHITECT

CHIEF ARCHITECT

S.D.P.W

P.O.BOX 30743-00100

NAIROBI

ELECTRICAL ENGINEER

CHIEF ENGINEER (ELECTRICAL)

S.D.P.W

P.O.BOX 30743-00100

NAIROBI

MECHANICAL ENGINEER

CHIEF ENGINEER (MECHANICAL-B.S)

S.D.P.W

P.O.BOX 30743-00100

NAIROBI

OCTOBER 2024

PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY

TENDER DOCUMENTS

Consisting

A	Contents page		(i)
В	Signature and	Special notes page	(ii)
C	Standard Tend	der Documents for Procurement of Works:	
	Section I:	Instructions to Tenderers	1
	Section II:	Tender Data Sheet (TDS)	18
	Section III:	Evaluation and Qualification Criteria	22
	Section IV:	Tendering Forms	28
	Section V:	Bills of Quantities	60
	Section VI:	Specifications	73
	Section VII:	Drawings	73
	Section VIII:	General Conditions of Contract (GCC)	74
	Section IX:	Special Conditions of Contract (SCC)	130
	Section X:	Contract Forms	132
D	Particular Pre	liminaries	PP /1
E	General Prelin	minaries	GP/1
F	Preambles and	d pricing notes	PN/4
G	Builders Worl	ks	BW/21
Н	Electrical Wo	rks	E/1
J	Mechanical W	Vorks	MW/1
K	Provisional Su	ums	PS/1
L	Grand Summa	ary	GS/1

PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY

Prepared by: - Quantities and Contract Department, State Department for Public Works, Ministry of Lands, Public Works, Hous P. O. Box 30743-00100,	sing & Urban Development,
NAIROBI.	
by the undersigned refers to these Tende WORKS, HOUSING & URBAN DEVEL	rks entered into this day of
THE CONTRACTOR	THE PRINCIPAL SECRETARY, STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES
Date :	Date:

SPECIAL NOTES

The Contractor is required to check the numbers of the pages of these Bills of Quantities and should he find any missing or duplicate or figures indistinct he must inform the Principal Secretary for State Department for Public Works, Head Office, Ngong Road, Nairobi at once and have the same rectified.

Should the Contractor be in doubt about the precise meaning of any item or figure for any reason whatsoever, he must inform the Principal Secretary, State Department for Public Works, Head Office in order that the correct meaning may be decided before the date for submission of tenders.

No liability will be admitted nor claim allowed in respect of errors in the Contractor's Tender due to mistakes in the specifications, which should have been rectified in the manner, described above.

SIGNATURE PAGE AND NOTES

TABLE OF CONTENTS

INVI	TATION TO TENDER	V
PART	Γ 1: TENDERING PROCEDURES	1
SECT	FION I - INSTRUCTIONS TO TENDERERS	1
A. G	ENERAL PROVISIONS	1
1.0	Scope of tender	
2.0	Fraud and corruption.	
3.0	Eligible tenderers	
4.0	Eligible goods, equipment, and services	
5.0	Tenderer's responsibilities	
В. С	ONTENTS OF TENDER DOCUMENTS	4
6.0	Sections of Tender Document	4
7.0	Clarification of Tender Document, Site Visit, Pre-tender Meeting	4
8.0	Amendment of Tender Documents	5
10.0	Language of Tender	5
11.0	Documents Comprising the Tender	
12.0	Form of Tender and Schedules	
13.0	Alternative Tenders	
14.0	Tender Prices and Discounts	
15.0	Currencies of Tender and Payment	
16.0	Documents Comprising the Technical Proposal	
17.0	Documents Establishing the Eligibility and Qualifications of The Tenderer	
18.0	Period of Validity of Tenders	
19.0	Tender Security	
20.0	Format and Signing of Tender	9
D. SU	UBMISSION AND OPENING OF TENDERS	11
21.0	Sealing and Marking of Tenders	11
22.0	Deadline for Submission of Tenders	
23.0	Late Tenders	
24.0	Withdrawal, Substitution, and Modification of Tenders	11
25.0	Tender Opening	12
E. EV	VALUATION AND COMPARISON OF TENDERS	
26.0	Confidentiality	12
27.0	Clarification of Tenders	
29.0	Determination of Responsiveness	13
30.0	Non-material Non-conformities	13
31.0	Arithmetical Errors	
33.0	Margin of Preference and Reservations	14
34.0	Nominated Subcontractors	14
35.0	Evaluation of Tenders	15
36.0	Comparison of tenders	15
37.0	Abnormally low tenders and abnormally high tenders	
	Abnormally Low Tenders	
	Abnormally high tenders	
38.0	Unbalanced and/or front-loaded tenders	
39.0	Qualifications of the tenderer.	
40.0	Lowest evaluated tender	
41.0	Procuring entity's right to accept any tender, and to reject any orall tenders.	16

F. AV	VARD OF CONTRACT	17
42.0	Award criteria	17
43.0	Notice of intention to enter into a contract	
44.0	Standstill Period.	
44.0	Standstill Period	
45.0	Debriefing By The Procuring Entity	
46.0	Letter of Award	
47.0	Signing of Contract	17
48.0	Performance Security	
49.0	Publication of Procurement Contract	
50.0	Procurement related Complaint	18
SECT	TION II - TENDER DATA SHEET (TDS)	18
SECT	TION III - EVALUATION AND QUALIFICATION CRITERIA	22
1.	General Provisions	22
2.	Preliminary examination for Determination of Responsiveness	22
3.	Tender Evaluation	22
4.	Multiple Contracts	22
5.	AlternativeTenders	23
6.	Margin of Preference	
7.	Post qualification and Contract Award	
8.	QUALIFICATION FORM	
SECT	TION IV -TENDERING FORMS	28
1.	FOREIGN TENDERERS 40% RULE	
2.	Form EQU: EQUIPMENT	
3.	FORM PER - 1:	
4.	FORM PER - 2:	
5.	TENDERERS QUALIFICATION WITHOUT PRE-QUALIFICATION	
отні	ER FORMS	43
1.	FORM OF TENDER	43
	a) TENDERER'S ELIGIBILITY- CONFIDENTIALBUSINESS QUESTIONNAIRE	
	b) CERTIFICATE OF INDEPENDENTTENDERDETERMINATION	
	c) SELF-DECLARATION FORM - SELF DECLARATION OFTHETENDERER	
	d) APPENDIX 1 - FRAUD AND CORRUPTION	
2.	FORM OF TENDER SECURITY - DEMANDBANKGUARANTEE	
3.	FORM OF TENDER SECURITY (TENDER BOND)	
4.	FORM OF TENDER-SECURING DECLARATION.	
5.	APPENDIX TO TENDER	
	TION V – BILLS OF QUANTITIES	
1.	PREAMBLES	
2.	Bill No. 1 – Preliminary Items	
3.	Bill No. 2: Work Items	
4.	Bill No. 3: Schedule of Daywork Rates - Labour	
5.	Bill No. 3: Schedule of Daywork Rates - Materials	
6.	Bill No. 3: Schedule of Daywork Rates - Contractor's Equipment	
7.	Bill No. 3: Daywork Summary	
8.	Bill No. 4: Provisional Sums.	
9.	GRAND SUMMARY	72

SECTION VI - SPECIFICATIONS	73
SECTION VII - DRAWINGS	73
SECTION VIII - GENERAL CONDITIONS OF CONTRACT (GCC)	74
1. General Provisions	74
2. The Procuring Entity	80
3. The Engineer	81
4. The Contractor	83
5. Nominated Subcontractors	91
6. Staff and Labor.	92
7. Plant, Materials and Workmanship	95
8. Commencement, Delays and Suspension	97
9. Tests on Completion	100
10. Procuring Entity's Taking Over	100
11. Defects Liability	102
12. Measurement and Evaluation	104
13. Variations and Adjustments	105
14. Contract Price and Payment	109
15. Termination by Procuring Entity	
16. Suspension and Termination by Contractor	
17. Risk and Responsibility	
18. Insurance	
19. Force Majeure	
20. Settlement of Claims and Disputes	126
Section IX - Special Conditions of Contract	130
SECTION X - CONTRACT FORMS	132
FORM No. 1 - NOTIFICATION OF INTENTIONTOAWARD	133
FORM No. 2 - NOTIFICATION OF AWARD - LETTEROFACCEPTANCE	135
FORM No. 3 – CONTRACT AGREEMENT	136
FORM No. 4 - PERFORMANCE SECURITY [Option 1 - Unconditional Demand Bank Guarantee]	137
FORM No. 5- PERFORMANCE SECURITY [Option 2 – Performance Bond]	138
FORM No. 6 – ADVANCE PAYMENT SECURITY	140
FORM No. 7 – RETENTION MONEY SECURITY	141



TENDER DOCUMENTS FOR PROCUREMENT OF WORKS (BUILDING AND ASSOCIATED CIVIL ENGINEERING WORKS)

1)	NAME AND CONTACT ADDRESSES OF PROCURING ENTITY
	Name: STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES Address: P.O.BOX 58187 – 00200
	Email address: ps@blueeconomy.go.ke
2)	Invitation to Tender (ITT) No:

3) Tender Name: PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI

COUNTY.

INVITATION TO TENDER

PROCURING ENTITY: STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES

CONTRACT NAME AND DESCRIPTION: PROPOSED PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY.

- 1. The PRINCIPAL SECRETARY—STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES invites sealed tenders for the construction of the PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY.
- 2. Tendering will be conducted under open national competitive method using a standardized tender document. Tendering is open to all qualified and interested Tenderers.
- 3. Qualified and interested tenderers may obtain further information and inspect the Tender Documents during office hours 0900 to 1700 hours at the address given below.
- **4.** A complete set of tender documents may be obtained electronically from the Website(s) *www.mibema.go.ke or public procurement information portal (tenders.go.ke)*. Tender documents obtained electronically will be free of charge.
- 5. Tender documents may be viewed and downloaded for free from the website www.mibema.go.ke. Tenderers who download the tender document must forward their particulars immediately to ps@blueeconomy.go.ke and P.O.BOX 58187 00200 to facilitate any further clarification or addendum.
- **6.** Tenders shall be quoted be in Kenya Shillings and shall include all taxes. Tenders shall remain valid for 126 days from the date of opening of tenders.
- 7. All Tenders must be accompanied by a tender Security of Kenya Shillings 850,000.00
- **8.** The Tenderer shall chronologically serialize all pages of the tender documents submitted.
- 9. Completed tenders must be delivered to the address below on or before (as indicated in tender advertisement). Electronic Tenders will not be permitted.
- 10. Tenders will be opened immediately after the deadline date and time specified above or any dead line date and time specified later. Tenders will be publicly opened in the presence of the Tenderers' designated representatives who choose to attend at the address below.
- 11. Late tenders will be rejected.
- **12.** The addresses referred to above are:

A. Address for obtaining further information and for purchasing tender documents

- (1) STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES.
- (2) MAJI HOUSE, 3RD FLOOR, NAIROBI COUNTY
- (3) P.O.BOX 58187 00200
- (4) Email: ps@blueeconomy.go.ke.

B. Address for Submission of Tender	B.	Address	for	Submission	of Tenders
--	----	---------	-----	------------	------------

- (1) STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES.
- (2) MAJI HOUSE, 3RD FLOOR, NAIROBI COUNTY
- (3) P.O.BOX 58187 00200

C. Address for Opening of Tenders.

- (1) STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES.
- (2) MAJI HOUSE, 3RD FLOOR, NAIROBI COUNTY

Name		
	(Official of the Procuring Entity issuing the invitation)	
Designation		
Signature		
Data		



SECTION I - INSTRUCTIONS TO TENDERERS

A GENERAL PROVISIONS

1.0 Scope of tender

1.1 The Procuring Entity as defined in the Appendix to Conditions of Contract invites tenders for Works Contract as described in the tender documents. The name, identification, and number of lots (contracts) of this Tender Document are specified in the TDS.

12 Throughout this tendering document:

- a) The term "in writing" means communicated in written form (e.g. by mail, e-mail, fax, including if specified in the TDS, distributed or received through the electronic-procurement system used by the Procuring Entity) with proof of receipt;
- b) if the context so requires, "singular" means "plural" and vice versa;
- c) "Day" means calendar day, unless otherwise specified as "Business Day". A Business Day is any day that is an official working day of the Procuring Entity. It excludes official public holidays.

20 Fraud and corruption

- 21 The Procuring Entity requires compliance with the provisions of the Public Procurement and Asset Disposal Act, 2015, Section 62 "Declaration not to engage in corruption". The tender submitted by a person shall include a declaration that the person shall not engage in any corrupt or fraudulent practice and a declaration that the person or his or her sub-contractors are not debarred from participating in public procurement proceedings.
- The Procuring Entity requires compliance with the provisions of the Competition Act 2010, regarding collusive practices in contracting. Any tenderer found to have engaged in collusive conduct shall be disqualified and criminal and/or civil sanctions may be imposed. To this effect, Tenders shall be required to complete and sign the "Certificate of Independent Tender Determination" annexed to the Form of Tender.
- 23 Tenderers shall permit and shall cause their agents (whether declared or not), subcontractors, sub-consultants, service providers, suppliers, and their personnel, to permit the Procuring Entity to inspect all accounts, records and other documents relating to any initial selection process, pre-qualification process, tender submission, proposal submission, and contract performance (in the case of award), and to have them audited by auditors appointed by the Procuring Entity.
- 24 Unfair Competitive Advantage Fairness and transparency in the tender process require that the firms or their Affiliates competing for a specific assignment do not derive a competitive advantage from having provided consulting services related to this tender. To that end, the Procuring Entity shall indicate in the **Data Sheet** and make available to all the firms together with this tender document all in formation that would in that respect give such firm any unfair competitive advantage over competing firms.

3.0 Eligible tenderers

- 3.1 A Tenderer may be a firm that is a private entity, a state-owned enterprise or institution subject to ITT 3.8, or an individual or any combination of such entities in the form of a joint venture (JV) under an existing agree mentor with the intent to enter in to such an agreement supported by a letter of intent. In the case of a joint venture, all members shall be jointly and severally liable for the execution of the entire Contract in accordance with the Contract terms. The JV shall nominate a Representative who shall have the authority to conduct all business for and on behalf of any and all the members of the JV during the tendering process and, in the event the JV is awarded the Contract, during contract execution. Members of a joint venture may not also make an individual tender, be a subcontractor in a separate tender or be part of another joint venture for the purposes of the same Tender. The maximum number of JV members shall be specified in the **TDS**.
- 32 Public Officers of the Procuring Entity, their Spouses, Child, Parent, Brothers or Sister. Child, Parent, Brother or Sister of a Spouse, their business associates or agents and firms/organizations in which they have a substantial or controlling interest shall not be eligible to tender or be awarded a contract. Public Officers are also not allowed to participate in any procurement proceedings.
- 33 A Tenderer shall not have a conflict of interest. Any tenderer found to have a conflict of interest shall be disqualified. A tenderer may be considered to have a conflict of interest for the purpose of this tendering process, if the tenderer:

- a) Directly or indirectly controls, is controlled by or is under common control with an other tenderer;
- b) Receives or has received any director indirect subsidy from another tenderer;
- c) Has the same legal representative as an other tenderer;
- d) Has a relationship with an other tenderer, directly or through common third parties, that puts it in a position to influence the tender of an other tenderer, or influence the decisions of the Procuring Entity regarding this tendering process;
- e) Any of its affiliates participated as a consultant in the preparation of the design or technical specifications of the goods or works that are the subject of the tender;
- f) Any of its affiliates has been hired (or is proposed to be hired) by the Procuring Entity as a consultant for Contract implementation;
- g) Would be providing goods, works, or non-consulting services resulting from or directly related to consulting services for the preparation or implementation of the contract specified in this Tender Document;
- h) Has a close business or personal relationship with senior management or professional staff of the Procuring Entity who has the ability to influence the bidding process and:
 - i) Are directly or indirectly involved in the preparation of the Tender document or specifications of the Contract, and/or the Tender evaluation process of such contract; or
 - ii) May be involved in the implementation or supervision of such Contract unless the conflicts temming from such relationship has been resolved in a manner acceptable to the Procuring Entity throughout the tendering process and execution of the Contract.
- 3.4 A tenderer shall not be involved in corrupt, coercive, obstructive or fraudulent practice. A tenderer that is proven to have been involved in any of these practices shall be automatically disqualified
- A Tenderer (either individually or as a JV member) shall not participate in more than one Tender, except for permitted alternative tenders. This includes participation as a subcontractor in other Tenders. Such participation shall result in the disqualification of all Tenders in which the firm is involved. Members of a joint venture may not also make an individual tender, be a sub-contractor in a separate tender or be part of another joint venture for the purposes of the same Tender. A firm that is not a tenderer or a JV member may participate as a subcontractor in more than one tender.
- 3.6 A Tenderer may have the nationality of any country, subject to the restrictions pursuant to ITT3.9. ATenderer shall be deemed to have the nationality of a country if the Tenderer is constituted, incorporated or registered in and operates in conformity with the provisions of the laws of that country, as evidenced by its articles of incorporation (or equivalent documents of constitution or association) and its registration documents, as the case may be. This criterion also shall apply to the determination of the nationality of proposed sub-contractors or sub-consultants for any part of the Contract including related Services.
- 3.7 A Tenderer that has been debarred from participating in public procurement shall be ineligible to tender or be awarded a contract. The list of debarred firms and individuals is available from the website of PPRA www.ppra.go.ke.
- 3.8 A Tenderer that is a state-owned enterprise or a public institution in Kenya may be eligible to tender and be awarded Contract(s) only if it is determined by the Procuring Entity to meet the following conditions, i.e. if it is:
 - i) A legal public entity of Government and/or public administration,
 - ii) financially autonomous and not receiving any significant subsidies or budget support from any public entity or Government, and;
 - (iii) Operating under commercial law and vested with legal rights and liabilities similar to any commercial enterprise to enable it compete with firms in the private sector on an equal basis.
- 3.9 Firms and individuals shall be ineligible if their countries of origin are:
 - (a) As a matter of law or official regulations, Kenya prohibits commercial relations with that country;
 - (b) By an act of compliance with a decision of the United Nations Security Council taken under Chapter VII of the Charter of the United Nations, Kenya prohibits any import of goods or contracting of works or services from that country, or any payments to any country, person, or entity in that country.

A tenderer shall provide such documentary evidence of eligibility satisfactory to the Procuring Entity, as the Procuring Entity shall reasonably request.

- 3.10 Foreign tenderers are required to source at least forty (40%) percent of their contract inputs (in supplies, local sub-contracts and labor) from citizen suppliers and contractors. To this end, a foreign tenderer shall provide in its tender documentary evidence that this requirement is met. Foreign tenderers not meeting this criterion will be automatically disqualified. Information required to enable the Procuring Entity determine if this condition is met shall be provided for this purpose in "SECTION III EVALUATION AND QUALIFICATION CRITERIA, Item 9".
- 3.11 Pursuant to the eligibility requirements of ITT 3.10, a tender is considered a foreign tenderer, if it is registered in Kenya and has less than 51 percent ownership by nationals of Kenya and if it does not subcontract to foreign firms or individuals more than 10 percent of the contract price, excluding provisional sums. JVs are considered as foreign tenderers if the individual member firms registered in Kenya have less 51 percent ownership by nationals of Kenya. The JV shall not subcontract to foreign firms more than 10 percent of the contract price, excluding provisional sums.
- 3.12 The National Construction Authority Act of Kenya requires that all local and foreign contractors be registered with the National Construction Authority and be issued with a Registration Certificate before they can undertake any construction works in Kenya. Registration shall not be a condition for tender, but it shall be a condition of contract award and signature. A selected tenderer shall be given opportunity to register before such award and signature of contract. Application for registration with National Construction Authority may be accessed from the website www.nca.go.ke.
- 3.13 The Competition Act of Kenya requires that firms wishing to tender as Joint Venture undertakings which may prevent, distort or lessen competition in provision of services are prohibited unless they are exempt in accordance with the provisions of Section 25 of the Competition Act, 2010. JVs will be required to seek for exemption from the Competition Authority. Exemption shall not be a condition for tender, but it shall be a condition of contract award and signature. A JV tenderer shall be given opportunity to seek such exemption as a condition of award and signature of contract. Application for exemption from the Competition Authority of Kenya may be accessed from the website www.cak.go.ke.
- 3.14 A Kenyan tenderer shall be eligible to tender if it provides evidence of having fulfilled his/her tax obligations by producing valid tax compliance certificate or tax exemption certificate issued by the Kenya Revenue Authority.

40 Eligible goods, equipment, and services

- Goods, equipment and services to be supplied under the Contract may have their origin in any country that is not ineligible under ITT 3.9. At the Procuring Entity's request, Tenderers may be required to provide evidence of the origin of Goods, equipment and services.
- 42 Any goods, works and production processes with characteristics that have been declared by the relevant national environmental protection agency or by other competent authority as harmful to human beings and to the environment shall not be eligible for procurement.

5.0 Tenderer's responsibilities

- 5.1 The tenderer shall bear all costs associated with the preparation and submission of his/her tender, and the Procuring Entity will in no case be responsible or liable for those costs.
- 52 The tenderer, at the tenderer's own responsibility and risk, is encouraged to visit and examine and inspect the Site of the Works and its surroundings and obtain all information that may be necessary for preparing the tender and entering into a contract for construction of the Works. The costs of visiting the Site shall beat the tenderer's own expense.
- 53 The Tenderer and any of its personnel or agents will be granted permission by the Procuring Entity to enter upon its premises and lands for the purpose of such visit. The Tenderer shall indemnify the Procuring Entity again stall liability arising from death or personal injury, loss of or damage to property, and any other losses and expenses incurred as a result of the examination and inspection.

54 The tenderer shall provide in the Form of Tender and Qualification Information, a preliminary description of the proposed work method and schedule, including charts, as necessary or required.

B. CONTENTS OF TENDER DOCUMENTS

60 Sections of Tender Document

61 The tender document consists of Parts 1, 2, and 3, which includes all the sections specified below, and which should be read in conjunction with any Addenda issued in accordance with ITT 10.

PART 1: Tendering Procedures

Section I – Instructions to Tenderers Section II – Tender Data Sheet (TDS) Section III- Evaluation and Qualification Criteria Section IV – Tendering Forms

PART 2: Works' Requirements

Section V - Bills of Quantities Section VI - Specifications Section VII - Drawings

PART 3: Conditions of Contract and Contract Forms

Section VIII - General Conditions (GCC) Section IX - Special Conditions of Contract Section X- Contract Forms

- The Invitation to Tender Notice issued by the Procuring Entity is not part of the Contract documents.

 Unless obtained directly from the Procuring Entity, the Procuring Entity is not responsible for the completeness of the Tender document, responses to requests for clarification, the minutes of a pre-arranged site visit and those of the pre-Tender meeting (if any), or Addenda to the Tender document in accordance with ITT 10. Incase of any contradiction, documents obtained directly from the Procuring Entity shall prevail.
- 63 The Tenderer is expected to examine all instructions, forms, terms, and specifications in the Tender Document and to furnish with its Tender all information and documentation as is required by the Tender document.

7.0 Clarification of Tender Document, Site Visit, Pre-tender Meeting

- A Tenderer requiring any clarification of the Tender Document shall contact the Procuring Entity in writing at the Procuring Entity's address specified in the **TDS** or raise its enquiries during the pre-Tender meeting if provided for in accordance with ITT 7.2. The Procuring Entity will respond in writing to any request for clarification, provided that such request is received no later than the period specified in the **TDS** prior to the deadline for submission of tenders. The Procuring Entity shall forward copies of its response to all tenderers who have acquired the Tender documents in accordance with ITT 7.4, including a description of the inquiry but without identifying its source. If so specified in the **TDS**, the Procuring Entity shall also promptly publish its response at the web page identified in the **TDS**. Should the clarification result in changes to the essential elements of the Tender Documents, the Procuring Entity shall amend the Tender Documents following the procedure under ITT 8 and ITT 22.2.
- The Tenderer, at the Tenderer's own responsibility and risk, is encouraged to visit and examine and inspect the site(s) of the required contracts and obtain all information that may be necessary for preparing a tender. The costs of visiting the Site shall be at the Tenderer's own expense. The Procuring Entity shall specify in the **TDS** if a pre-arranged Site visit and or a pre-tender meeting will be held, when and where. The Tenderer's designated representative is invited to attend a pre-arranged site visit and a pre-tender meeting, as the case may be. The purpose of the site visit and the pre-tender meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.
- 73 The Tenderer is requested to submit any questions in writing, to reach the Procuring Entity not later than the period specified in the **TDS** before the meeting.

- 7.4 Minutes of a pre-arranged site visit and those of the pre-tender meeting, if applicable, including the text of the questions asked by Tenderers and the responses given, together with any responses prepared after the meeting, will be transmitted promptly to all Tenderers who have acquired the Tender Documents. Minutes shall not identify the source of the questions asked.
- The Procuring Entity shall also promptly publish anonymized (*no names*) Minutes of the pre-arranged site visit and those of the pre-tender meeting at the web page identified in the **TDS**. Any modification to the Tender Documents that may become necessary as a result of the pre-arranged site visit and those of the pre-tender meeting shall be made by the Procuring Entity exclusively through the issue of an Addendum pursuant to ITT 8 and not through the minutes of the pre-Tender meeting. Non-attendance at the pre-arranged site visit and the pre-tender meeting will not be a cause for disqualification of a Tenderer.

80 Amendment of Tender Documents

- **&1** At any time prior to the deadline for submission of Tenders, the Procuring Entity may amend the Tender Documents by issuing addenda.
- Any addendum issued shall be part of the Tender Documents and shall be communicated in writing to all who have obtained the Tender Documents from the Procuring Entity. The Procuring Entity shall also promptly publish the addendum on the Procuring Entity's website in accordance with ITT 7.5.
- To give Tenderers reasonable time in which to take an addendum into account in preparing their Tenders, the Procuring Entity should extend the dead line for the submission of Tenders, pursuant to ITT 22.2.

C. PREPARATION OF TENDERS

9.0 Cost of Tendering

The Tenderer shall bear all costs associated with the preparation and submission of its Tender, and the Procuring Entity shall not be responsible or liable for those costs, regardless of the conduct or outcome of the tendering process.

10.0 Language of Tender

The Tender, as well as all correspondence and documents relating to the tender exchanged by the tenderer and the Procuring Entity, shall be written in the English Language. Supporting documents and printed literature that are part of the Tender may be in another language provided they are accompanied by an accurate and notarized translation of the relevant passages into the English Language, in which case, for purposes of interpretation of the Tender, such translation shall govern.

11.0 Documents Comprising the Tender

- 11.1 The Tender shall comprise the following:
 - a) Form of Tender prepared in accordance with ITT 12;
 - b) Schedules including priced Bill of Quantities, completed in accordance with ITT 12 and ITT 14;
 - c) Tender Security or Tender-Securing Declaration, in accordance with ITT 19.1;
 - d) Alternative Tender, if permissible, in accordance with ITT 13;
 - e) *Authorization*: written confirmation authorizing the signatory of the Tender to commit the Tenderer, in accordance with ITT 20.3;
 - f) *Qualifications:* documentary evidence in accordance with ITT 17 establishing the Tenderer's qualifications to per form the Contract if its Tender is accepted;
 - g) Conformity: a technical proposal in accordance with ITT 16;
 - h) Any other document required in the **TDS**.
- In addition to the requirements under ITT 11.1, Tenders submitted by a JV shall include a copy of the Joint Venture Agreement entered into by all members. Alternatively, a letter of intent to execute a Joint Venture Agreement in the event of a successful Tender shall be signed by all members and submitted with the Tender, together with a copy of the proposed JV Agreement. Change of membership and conditions of the JV prior to contract signature will render the tender liable for disqualification.

12.0 Form of Tender and Schedules

- 12.1 The Form of Tender and Schedules, including the Bill of Quantities, shall be prepared using the relevant forms furnished in Section IV, Tendering Forms. The forms must be completed with out any alterations to the text, and no substitutes shall be accepted except as provided under ITT 20.3. All blank spaces shall be filled in with the information requested. The Tenderer shall chronologically serialize all pages of the tender documents submitted.
- 12.2 The Tenderer shall furnish in the Form of Tender information on commissions and gratuities, if any, paid or to be paid to agents or any other party relating to this Tender.

13. Alternative Tenders

- 13.1 Unless otherwise specified in the TDS, alternative Tenders shall not be considered.
- When alternative times for completion are explicitly invited, a statement to that effect will be included in the **TDS**, and the method of evaluating different alternative times for completion will be described in Section III, Evaluation and Qualification Criteria.
- 133 Except as provided under ITT 13.4 below, Tenderers wishing to offer technical alternatives to the requirements of the Tender Documents must first price the Procuring Entity's design as described in the Tender Documents and shall further provide all information necessary for a complete evaluation of the alternative by the Procuring Entity, including drawings, design calculations, technical specifications, breakdown of prices, and proposed construction methodology and other relevant details. Only the technical alternatives, if any, of the Tenderer with the Winning Tender conforming to the basic technical requirements shall be considered by the Procuring Entity.
- When specified in the **TDS**, Tenderers are permitted to submit alternative technical solutions for specified parts of the Works, and such parts will be identified in the **TDS**, as will the method for their evaluating, and described in Section VII, Works' Requirements.

140 Tender Prices and Discounts

- 14.1 The prices and discounts (including any price reduction) quoted by the Tenderer in the Form of Tender and in the Billof Quantities shall conform to the requirements specified below.
- The Tenderer shall fill in rates and prices for all items of the Works described in the Bill of Quantities. Items against which no rate or price is entered by the Tenderer shall be deemed covered by the rates for other items in the Bill of Quantities and will not be paid for separately by the Procuring Entity. An item not listed in the priced Bill of Quantities shall be assumed to be not included in the Tender, and provided that the Tender is determined substantially responsive notwithstanding this omission, the average price of the item quoted by substantially responsive Tenderers will be added to the Tender price and the equivalent total cost of the Tender so determined will be used for price comparison.
- The price to be quoted in the Form of Tender, in accordance with ITT 12.1, shall be the total price of the Tender, including any discounts offered.
- 144 The Tenderer shall quote any discounts and the methodology for their application in the Form of Tender, in accordance with ITT 12.1.
- It will be specified in the **TDS** if the rates and prices quoted by the Tenderer are or are not subject to adjustment during the performance of the Contract in accordance with the provisions of the Conditions of Contract, except incases where the contract is subject to fluctuations and adjustments, not fixed price. In such a case, the Tenderer shall furnish the indices and weightings for the price adjustment formulae in the Schedule of Adjustment Data and the Procuring Entity may require the Tenderer to justify its proposed indices and weightings.
- Where tenders are being invited for individual lots (contracts) or for any combination of lots (packages), tenderers wishing to offer discounts for the award of more than one Contract shall specify in their Tender the price reductions applicable to each package, or alternatively, to individual Contracts within the package. Discounts shall be submitted in accordance with ITT 14.4, provided the Tenders for all lots (contracts) are opened at the sametime.

All duties, taxes, and other levies payable by the Contractor under the Contract, or for any other cause, as of the date 30 days prior to the deadline for submission of Tenders, shall be included in the rates and prices and the total Tender Price submitted by the Tenderer.

15.0 Currencies of Tender and Payment

- 15.1 The currency (ies) of the Tender and the currency (ies) of payments shall be the same.
- 152 Tenderers shall quote entirely in Kenya Shillings. The unit rates and the prices shall be quoted by the Tenderer in the Bill of Quantities, entirely in Kenya shillings.
 - a) A Tenderer expecting to incur expenditures in other currencies for inputs to the Works supplied from outside Kenya (referred to as "the foreign currency requirements") shall (if so allowed in the **TDS**) indicate in the Appendix to Tender the percentage(s) of the Tender Price (excluding Provisional Sums), needed by the Tenderer for the payment of such foreign currency requirements, limited to no more than two foreign currencies.
 - b) The rates of exchange to be used by the Tenderer in arriving at the local currency equivalent and the percentage(s) mentioned in (a) above shall be specified by the Tenderer in the Appendix to Tender and shall be based on the exchange rate provided by the Central Bank of Kenya on the date 30 days prior to the actual date of tender opening. Such exchange rate shall apply for all foreign payments under the Contract.
- Tenderers may be required by the Procuring Entity to justify, to the Procuring Entity's satisfaction, their local and foreign currency requirements, and to substantiate that the amounts included in the unit rates and prices and shown in the Schedule of Adjustment Data in the Appendix to Tender are reasonable, in which case a detailed break down of the foreign currency requirements shall be provided by Tenderers.

16.0 Documents Comprising the Technical Proposal

The Tenderer shall furnish a technical proposal including a statement of work methods, equipment, personnel, schedule and any other information as stipulated in Section IV, Tender Forms, and in sufficient detail to demonstrate the adequacy of the Tenderer's proposal to meet the work's requirements and the completion time.

17.0 Documents Establishing the Eligibility and Qualifications of the Tenderer

- 17.1 Tenderers shall complete the Form of Tender, included in Section IV, Tender Forms, to establish Tenderer's eligibility in accordance with ITT 4.
- In accordance with Section III, Evaluation and Qualification Criteria, to establish its qualifications to perform the Contract the Tenderer shall provide the information requested in the corresponding information sheets included in Section IV, Tender Forms.
- 173 If a margin of preference applies as specified in accordance with ITT 33.1, national tenderers, individually or in joint ventures, applying for eligibility for national preference shall supply all information required to satisfy the criteria for eligibility specified in accordance with ITT 33.1.
- 17.4 Tenderers shall be asked to provide, as part of the data for qualification, such information, including details of ownership, as shall be required to determine whether, according to the classification established by the Procuring Entity, a particular contractor or group of contractors qualifies for a margin of preference. Further the information will enable the Procuring Entity identify any actual or potential conflict of interest in relation to the procurement and/or contract management processes, or a possibility of collusion between tenderers, and thereby help to prevent any corrupt influence in relation to the procurement process or contract management.
- 175 The purpose of the information described in ITT 17.4 above overrides any claims to confidentiality which a tenderer may have. There can be no circumstances in which it would be justified for a tenderer to keep information relating to its ownership and control confidential where it is tendering to undertake public sector work and receive public sector funds. Thus, confidentiality will not be accepted by the Procuring Entity as a justification for a Tenderer's failure to disclose, or failure to provide required information on its ownership and control.
- 17.6 The Tenderer shall provide further documentary proof, information or authorizations that the Procuring Entity may request in relation to owner ship and control which in formation on any changes to the information which was provided by the tenderer under ITT 6.4. The obligations to require this information shall continue for the duration of the procurement process and contract performance and after completion of the contract, if any change to the information previously provided may reveal a conflict of interest in relation to the award or management of the contract.

- 17.7 All information provided by the tenderer pursuant to these requirements must be complete, current and accurate as at the date of provision to the Procuring Entity. In submitting the information required pursuant to these requirements, the Tenderer shall warrant that the information submitted is complete, current and accurate as at the date of submission to the Procuring Entity.
- 178 If a tenderer fails to submit the information required by these requirements, its tender will be rejected. Similarly, if the Procuring Entity is unable, after taking reasonable steps, to verify to a reasonable degree the information submitted by a tenderer pursuant to these requirements, then the tender will be rejected.
- 179 If information submitted by a tenderer pursuant to these requirements, or obtained by the Procuring Entity (whether through its own enquiries, through notification by the public or otherwise), shows any conflict of interest which could materially and improperly benefit the tenderer in relation to the procurement or contract management process, then:
 - i) If the procurement process is still ongoing, the tenderer will be dis qualified from the procurement process,
 - ii) if the contract has been awarded to that tenderer, the contract award will be set as idepending the outcome of (iii),
 - iii) the tenderer will be referred to the relevant law enforcement authorities for investigation of whether the tenderer or any other person shave committed any criminal offence.
- 17.10 If a tenderer submits information pursuant to these requirements that is incomplete, inaccurate or out-of-date, or attempts to obstruct the verification process, then the consequences ITT 17.8 will ensue unless the tenderer can show to the reasonable satisfaction of the Procuring Entity that any such act was not material, or was due to genuine error which was not attributable to the intentional act, negligence or recklessness of the tender.

18.0 Period of Validity of Tenders

- 18.1. Tenders shall remain valid for the Tender Validity period specified in the **TDS**. The Tender Validity period starts from the date fixed for the Tender submission deadline (as prescribed by the Procuring Entity in accordance with ITT 22). At ender valid for a shorter period shall be rejected by the Procuring Entity as non-responsive.
- 18.2 In exceptional circumstances, prior to the expiration of the Tender validity period, the Procuring Entity may request Tenderers to extend the period of validity of their Tenders. The request and the responses shall be made in writing. If a Tender Security is requested in accordance with ITT 19, it shall also be extended for thirty (30) days beyond the deadline of the extended validity period. A Tenderer may refuse the request without forfeiting its Tender security. A Tenderer granting the request shall not be required or permitted to modify its Tender.

19.0 Tender Security

- 19.1 The Tenderer shall furnish as part of its Tender, either a Tender-Securing Declaration or a Tender Security as specified in the **TDS**, in original form and, in the case of a Tender Security, in the amount and currency **specified** in the **TDS**. A Tender-Securing Declaration shall use the form included in Section IV, Tender Forms.
- 192 If a Tender Security is specified pursuant to ITT 19.1, the Tender Security shall be a demand guarantee in any of the following forms at the Tenderer's option:
 - I) cash;
 - ii) a bank guarantee;
 - iii) a guarantee by an insurance company registered and licensed by the Insurance Regulatory Authority listed by the Authority;
 - (iv) a guarantee issued by a financial institution approved and licensed by the Central Bank of Kenya, from a reputable source, and an eligible country.
- 193 If an unconditional bank guarantee is issued by a bank located outside Kenya, the issuing bank shall have a correspondent bank located in Kenya to make it enforceable. The Tender Security shall be valid for thirty (30) days beyond the original validity period of the Tender, or beyond any period of extension if requested under ITT 18.2.

- 194 If a Tender Security or Tender-Securing Declaration is specified pursuant to ITT 19.1, any Tender not accompanied by a substantially responsive Tender Security or Tender-Securing Declaration shall be rejected by the Procuring Entity as non-responsive.
- If a Tender Security is specified pursuant to ITT 19.1, the Tender Security of unsuccessful Tenderers shall be returned as promptly as possible upon the successful Tenderer's signing the Contract and furnishing the Performance Security and any other documents required in the TDS. The Procuring Entity shall also promptly return the tender security to the tenderers where the procurement proceedings are terminated, all tenders were determined non-responsive or a bidder declines to extend tender validity period.
- The Tender Security of the successful Tenderer shall be returned as promptly as possible once the successful Tenderer has signed the Contract and furnished the required Performance Security, and any other documents required in the TDS.
- 19.7 The Tender Security may be forfeited or the Tender-Securing Declaration executed:
 - a) if a Tenderer withdraws its Tender during the period of Tender validity specified by the Tenderer on the Form of Tender, or any extension there to provided by the Tenderer; or
 - b) if the successful Tenderer fails to:
 - i) sign the Contract in accordance with ITT47; or
 - ii) furnish a Performance Security and if required in the TDS, and any other documents required in the TDS.
- Where tender securing declaration is executed, the Procuring Entity shall recommend to the PPRA to debar the Tenderer from participating in public procurement as provided in the law.
- The Tender Security or the Tender-Securing Declaration of a JV shall be in the name of the JV that submits the Tender. If the JV has not been legally constituted into a legally enforceable JV at the time of tendering, the Tender Security or the Tender-Securing Declaration shall be in the names of all future members as named in the letter of intent referred to in ITT 4.1 and ITT 11.2.
- **19.10** A tenderer shall not issue a tender security to guarantee itself.

20.0 Format and Signing of Tender

- The Tenderer shall prepare one original of the documents comprising the Tender as described in ITT 11 and clearly mark it "ORIGINAL." Alternative Tenders, if permitted in accordance with ITT 13, shall be clearly marked "ALTERNATIVE." In addition, the Tenderer shall submit copies of the Tender, in the number specified in the **TDS** and clearly mark them "COPY." In the event of any discrepancy between the original and the copies, the original shall prevail.
- 202 Tenderers shall mark as "CONFIDENTIAL" all information in their Tenders which is confidential to their business. This may include proprietary information, trade secrets, or commercial or financially sensitive information.
- The original and all copies of the Tender shall be typed or writtenvin indelible ink and shall be signed by a person duly authorized to sign on behalf of the Tenderer. This authorization shall consist of a written confirmation as specified in the **TDS** and shall be attached to the Tender. The name and position held by each person signing the authorization must be typed or printed below the signature. All pages of the Tender where entries or amendments have been made shall be signed or initialed by the person signing the Tender.
- Incase the Tenderer is a JV, the Tender shall be signed by an authorized representative of the JV on behalf of the JV, and so as to be legally binding on all the members as evidenced by a power of attorney signed by their legally authorized representatives.
- 205 Any inter-lineation, erasures, or overwriting shall be valid only if they are signed or initialed by the person signing the Tender.

D. SUBMISSION AND OPENING OF TENDERS

21.0 Sealing and Marking of Tenders

- The Tenderer shall deliver the Tender in a single sealed envelope, or in a single sealed package, or in a single sealed container bearing the name and Reference number of the Tender, addressed to the Procuring Entity and a warning not to open before the time and date for Tender opening date. Within the single envelope, package or container, the Tenderer shall place the following separate, sealed envelopes:
 - a) in an envelope or package or container marked "ORIGINAL", all documents comprising the Tender, as described in ITT 11; and
 - b) in a nenvelope or package or container marked "COPIES", all required copies of the Tender; and
 - c) if alternative Tenders are permitted in accordance with ITT 13, and if relevant:
 - i) in an envelope or package or container marked "ORIGINAL -ALTERNATIVE TENDER", the alternative Tender; and
 - ii) in the envelope or package or container marked "COPIES- ALTERNATIVE TENDER", all required copies of the alternative Tender.

The inner envelopes or packages or containers shall:

- a) bear the name and address of the Procuring Entity,
- b) bear the name and address of the Tenderer; and
- c) bear the name and Reference number of the Tender.
- If an envelope or package or container is not sealed and marked as required, the *Procuring Entity* will assume no responsibility for the misplacement or premature opening of the Tender. Tenders misplaced or opened prematurely will not be accepted.

22.0 Deadline for Submission of Tenders

- Tenders must be received by the Procuring Entity at the address specified in the **TDS** and no later than the date and time also specified in the **TDS**. When so specified in the **TDS**, tenderers shall have the option of submitting their Tenders electronically. Tenderers submitting Tenders electronically shall follow the electronic Tender submission procedures specified in the **TDS**.
- The Procuring Entity may, at its discretion, extend the deadline for the submission of Tenders by amending the TenderDocumentsinaccordance with ITT 8, in which case all rights and obligations of the Procuring Entity and Tenderers previously subject to the deadline shall there after be subject to the deadline as extended.

23.0 Late Tenders

The Procuring Entity shall not consider any Tender that arrives after the deadline for submission of tenders, in accordance with ITT 22. Any Tender received by the Procuring Entity after the deadline for submission of Tenders shall be declared late, rejected, and returned unopened to the Tenderer.

240 Withdrawal, Substitution, and Modification of Tenders

- A Tenderer may withdraw, substitute, or modify its Tenderafterith as been submitted by sending a written notice, duly signed by an authorized representative, and shall include a copy of the authorization in accordance with ITT 20.3, (except that withdrawal notices do not require copies). The corresponding substitution or modification of the Tender must accompany the respective written notice. All notices must be:
 - a) prepared and submitted in accordance with ITT 20 and ITT 21 (except that withdrawals notices do not require copies), and in addition, the respective envelopes shall be clearly marked "WITHDRAWAL," "SUBSTITUTION," "MODIFICATION;" and
 - b) received by the Procuring Entity prior to the deadline prescribed for submission of Tenders, in accordance with ITT 22.
- 242 Tenders requested to be withdrawn in accordance with ITT 24.1 shall be returned unopened to the Tenderers.
- No Tender may be withdrawn, substituted, or modified in the interval between the deadline for submission of Tenders and the expiration of the period of Tender validity specified by the Tenderer on the Form of Tender or any extension thereof.

25. Tender Opening

- Except in the cases specified in ITT 23 and ITT 24.2, the Procuring Entity shall publicly open and read out all Tenders received by the deadline, at the date, time and place specified **in the TDS**, in the presence of Tenderers' designated representatives who chooses to attend. Any specific electronic Tender opening procedures required if electronic Tendering is permitted in accordance with ITT 22.1, shall be as specified in the **TDS**.
- First, envelopes marked "WITHDRAWAL" shall be opened and read out and the envelopes with the corresponding Tender shall not be opened but returned to the Tenderer. No Tender withdrawal shall be permitted unless the corresponding withdrawal notice contains a valid authorization to request the withdrawal and is read out at Tender opening.
- Next, envelopes marked "SUBSTITUTION" shall be opened and read out and exchanged with the corresponding Tender being substituted, and the substituted Tender shall not be opened, but returned to the Tenderer. No Tender substitution shall be permitted unless the corresponding substitution notice contains a valid authorization to request the substitution and is read out at Tender opening.
- Next, envelopes marked "MODIFICATION" shall be opened and read out with the corresponding Tender. No Tender modification shall be permitted unless the corresponding modification notice contains a valid authorizationtorequestthemodificationandisreadoutatTenderopening.
- Next, all remaining envelopes shall be opened one at a time, reading out: the name of the Tenderer and whether there is a modification; the total Tender Price, per lot (contract) if applicable, including any discounts and alternative Tenders; the presence or absence of a Tender Security or Tender-Securing Declaration, if required; and any other details as the Procuring Entity may consider appropriate.
- Only Tenders, alternative Tenders and discounts that are opened and read out at Tender opening shall be considered further for evaluation. The Form of Tender and pages of the Bill of Quantities (to be decided on by the tender opening committee) are to be initialed by the members of the tender opening committee attending the opening.
- 25.7 At the Tender Opening, the Procuring Entity shall neither discuss the merits of any Tender nor reject any Tender (except for late Tenders, in accordance with ITT 23.1).
- 258 The Procuring Entity shall prepare minutes of the Tender Opening that shall include, as a minimum:
 - a) the name of the Tendere rand whether there is a withdrawal, substitution, or modification;
 - b) the Tender Price, per lot (contract) if applicable, including any discounts;
 - c) any alternative Tenders;
 - d) the presence or absence of a Tender Security, if new as required;
 - e) number of pages of each tender document submitted.
- The Tenderers' representatives who are present shall be requested to sign the minutes. The omission of a Tenderer's signature on the minutes shall not invalidate the contents and effect of the minutes. A copy of the tender opening register shall be distributed to all Tenderers.

E. EVALUATION AND COMPARISON OF TENDERS

26. Confidentiality

- Information relating to the evaluation of Tenders and recommendation of contract award shall not be disclosed to Tenderers or any other persons not officially concerned with the Tender process until information on Intention to Award the Contract is transmitted to all Tenderers in accordance with ITT 43.
- Any effort by a Tenderer to influence the Procuring Entity in the evaluation of the Tenders or Contract award decisions may result in the rejection of its tender.
- Not withstanding ITT 26.2, from the time of tender opening to the time of contract award, if a tenderer wishes to contact the Procuring Entity on any matter related to the tendering process, it shall do so in writing.

27.0 Clarification of Tenders

- To assist in the examination, evaluation, and comparison of the tenders, and qualification of the tenderers, the Procuring Entity may, at its discretion, ask any tenderer for a clarification of its tender, given a reasonable time for a response. Any clarification submitted by a tenderer that is not in response to a request by the Procuring Entity shallnot be considered. The Procuring Entity's request for clarification and the response shall be in writing. No change, including any voluntary increase or decrease, in the prices or substance of the tender shall be sought, offered, or permitted, except to confirm the correction of arithmetic errors discovered by the Procuring Entity in the evaluation of the tenders, in accordance with ITT 31.
- 272 If a tenderer does not provide clarifications of its tender by the date and time set in the Procuring Entity's request for clarification, its Tender may be rejected.

28.0 Deviations, Reservations, and Omissions

- **28.1** During the evaluation of tenders, the following definitions apply:
 - a) "Deviation" is a departure from the requirements specified in the tender document;
 - b) "Reservation" is the setting of limiting conditions or withholding from complete acceptance of the requirements specified in the tender document; and
 - c) "Omission" is the failure to submit part or all of the information or documentation required in the Tender document.

29.0 Determination of Responsiveness

- 29.1 The Procuring Entity's determination of a Tender's responsiveness is to be based on the contents of the tender itself, as defined in ITT 11.
- A substantially responsive Tender is one that meets the requirements of the Tender document without material deviation, reservation, or omission. A material deviation, reservation, or omission is one that, if accepted, would:
 - a) Affect in any substantial way the scope, quality, or performance of the Works specified in the Contract;
 - b) limit in any substantial way, inconsistent with the tender document, the Procuring Entity's rights or the tenderer's obligations under the proposed contract;
 - c) if rectified, would unfairly affect the competitive position of other tenderers presenting substantially responsivetenders.
- 293 The Procuring Entity shall examine the technical aspects of the tender submitted in accordance with ITT 16, to confirm that all requirements of Section VII, Works' Requirements have been met without any material deviation, reservation or omission.
- 29.4 If a tender is not substantially responsive to the requirements of the tender document, it shall be rejected by the Procuring Entity and may not subsequently be made responsive by correction of the material deviation, reservation, or omission.

30.0 Non-material Non-conformities

- *30.1* Provided that a tender is substantially responsive, the Procuring Entity may waive any non-conformities in the tender.
- 30.2 Provided that a Tender is substantially responsive, the Procuring Entity may request that the tenderer submit the necessary information or documentation, within a reasonable period of time, to rectify non-material non-conformities in the tender related to documentation requirements. Requesting information or documentation on such non-conformities shall not be related to any aspect of the price of the tender. Failure of the tenderer to comply with the request may result in the rejection of its tender.
- 30.3 Provided that a tender is substantially responsive, the Procuring Entity shall rectify quantifiable non-material non-conformities related to the Tender Price. To this effect, the Tender Price shall be adjusted, for comparison purposes only, to reflect the price of a missing or non-conforming item or component in the manner specified in the TDS.

31.0 Arithmetical Errors

- 31.1 The tender sum as submitted and read out during the tender opening shall be absolute and final and shall not be the subject of correction, adjustment or amendment in any way by any person or entity.
- 31.2 Provided that the Tender is substantially responsive, the Procuring Entity shall handle errors on the following basis:
 - a) Any error detected if considered a major deviation that affects the substance of the tender, shall lead to disqualification of the tender as non-responsive.
 - b) Any errors in the submitted tender arising from a miscalculation of unit price, quantity, subtotal and total bidpriceshallbe considered as a major deviation that affects the substance of the tender and shall lead to disqualification of the tender as non-responsive. and
 - c) if there is a discrepancy between words and figures, the amount in words shall prevail
- 313 Tenderers shall be notified of any error detected in their bid during the notification of award.

32.0 Conversion to Single Currency

For evaluation and comparison purposes, the currency (ies) of the Tender shall be converted into a single currency as specified in the **TDS**.

33.0 Margin of Preference and Reservations

- A margin of preference may be allowed only when the contract is open to international competitive tendering where foreign contractors are expected to participate in the tendering process and where the contract exceeds the value/threshold specified in the Regulations.
- 332 A margin of preference shall not be allowed unless it is specified so in the TDS.
- 333 Contracts procured on basis of international competitive tendering shall not be subject to reservations exclusive to specific groups as provided in ITT 33.4.
- Where it is intended to reserve a contract to as pecific group of businesses (these groups are Small and Medium Enterprises, Women Enterprises, Youth Enterprises and Enterprises of persons living with disability, as the case may be), and who are appropriately registered as such by the authority to be specified in the **TDS**, a procuring entity shall ensure that the invitation to tender specifically indicates that only businesses or firms belonging to the specified group are eligible to tender. No tender shall be reserved to more than one group. If not so stated in the Invitation to Tender and in the Tender documents, the invitation to tender will be open to all interested tenderers.

34.0 Nominated Subcontractors

- 34.1 Unless otherwise stated in the **TDS**, the Procuring Entity does not intend to execute any specific elements of the Works by subcontractors selected/nominated by the Procuring Entity. Incase the Procuring Entity nominates a subcontractor, the subcontract agreement shall be signed by the Subcontractor and the Procuring Entity. The main contract shall specify the working arrangements between the main contractor and the nominated subcontractor.
- 34.2 Tenderers may propose sub-contracting up to the percentage of total value of contracts or the volume of works as specified in the TDS. Subcontractors proposed by the Tenderer shall be fully qualified for their parts of the Works.
- 343 Domestic subcontractor's qualifications shall not be used by the Tenderer to qualify for the Works unless their specialized parts of the Works were previously designated so by the Procuring Entity in the **TDS** as can be met by subcontractors referred to hereafter as 'Specialized Subcontractors', in which case, the qualifications of the Specialized Subcontractors proposed by the Tenderer may be added to the qualifications of the Tenderer.

35. Evaluation of Tenders

35.1 The Procuring Entity shall use the criteria and methodologies listed in this ITT and Section III, Evaluation and Qualification Criteria. No other evaluation criteria or methodologies shall be permitted. By applying the criteria and methodologies the Procuring Entity shall determine the Lowest Evaluated Tender in accordance with ITT 40.

- 352 To evaluate a Tender, the Procuring Entity shall consider the following:
 - a) Price adjustment in accordance with ITT 31.1 (iii); excluding provisional sums and contingencies, if any, but including Daywork items, where priced competitively;
 - b) price adjustment due to discounts offered in accordance with ITT 14.4;
 - c) converting the amount resulting from applying (a) and (b) above, if relevant, to a single currency in accordance with ITT 32;
 - d) price adjustment due to quantifiable non material non-conformities in accordance with ITT 30.3; and
 - e) any additional evaluation factors specified in the **TDS** and Section III, Evaluation and Qualification Criteria.
- 353 The estimated effect of the price adjustment provisions of the Conditions of Contract, applied over the period of execution of the Contract, shall not be considered in Tender evaluation.
- Where the tender involves multiple lots or contracts, the tenderer will be allowed to tender for one or more lots (contracts). Each lot or contract will be evaluated in accordance with ITT 35.2. The methodology to determine the lowest evaluated tenderer or tenderers base done lot (contract) or based on a combination of lots (contracts), will be specified in Section III, Evaluation and Qualification Criteria. In the case of multiple lots or contracts, tenderer will be will be required to prepare the Eligibility and Qualification Criteria Form for each Lot.

36.0 Comparison of tenders

The Procuring Entity shall compare the evaluated costs of all substantially responsive Tenders established in accordance with ITT 35.2 to determine the Tender that has the lowest evaluated cost.

37.0 Abnormally low tenders and abnormally high tenders

Abnormally Low Tenders

- An Abnormally Low Tender is one where the Tender price, in combination with other elements of the Tender, appears so low that it raises material concerns as to the capability of the Tenderer in regards to the Tenderer's ability to perform the Contract for the offered Tender Price or that genuine competition between Tenderersis compromised.
- 372 In the event of identification of a potentially Abnormally Low Tender, the Procuring Entity shall seek written clarifications from the Tenderer, including detailed price analyses of its Tender price in relation to the subject matter of the contract, scope, proposed methodology, schedule, allocation of risks and responsibilities and any other requirements of the Tender document.
- 373 After evaluation of the price analyses, in the event that the Procuring Entity determines that the Tenderer has failed to demonstrate its capability to perform the Contract for the offered Tender Price, the Procuring Entity shall reject the Tender.

Abnormally high tenders

- Anabnormally high tender price is one where the tender price, in combination with other constituent elements of the Tender, appears unreasonably too high to the extent that the Procuring Entity is concerned that it (the Procuring Entity) may not be getting value for money or it may be paying too high a price for the contract compared with market prices or that genuine competition between Tenderers is compromised.
- Incase of a nab normally high price, the Procuring Entity shall make a survey of the market prices, check if the estimated cost of the contract is correct and review the Tender Documents to check if the specifications, scope of work and conditions of contract are contributory to the abnormally high tenders. The Procuring Entity may also seek written clarification from the tenderer on the reason for the high tender price. The Procuring Entity shall proceed as follows:
 - i) If the tender price is abnormally high based on wrong estimated cost of the contract, the Procuring Entity may accept or not a ccept the tender depending on the Procuring Entity's budget considerations.
 - ii) If specifications, scope of work and/or conditions of contract are contributory to the abnormally high tender prices, the Procuring Entity shall reject all tenders and may retender for the contract based on revised estimates, specifications, scope of work and conditions of contract, as the case may be.

37.6 If the Procuring Entity determines that the Tender Price is abnormally too high because genuine competition between tenderers is compromised (often due to collusion, corruption or other manipulations), the Procuring Entity shall reject all Tenders and shall institute or cause competent Government Agencies to institute an investigation on the cause of the compromise, before retendering.

380 Unbalanced and/ or front-loaded tenders

- 38.1 If in the Procuring Entity's opinion, the Tender that is evaluated as the lowest evaluated price is seriously unbalanced and/or frontloaded, the Procuring Entity may require the Tenderer to provide written clarifications. Clarifications may include detailed price analyses to demonstrate the consistency of the tender prices with the scope of works, proposed methodology, schedule and any other requirements of the Tender document.
- 382 After the evaluation of the information and detailed price analyses presented by the Tenderer, the Procuring Entity may as appropriate:
 - a) accept the Tender;
 - b) require that the total amount of the Performance Security be increased at the expense of the Tenderer to a level not exceeding a 30% of the Contract Price;
 - c) agree on a payment mode that eliminates the inherent risk of the Procuring Entity paying too much for undelivered works;
 - d) reject the Tender,

39.0 Qualifications of the tenderer

- 39.1 The Procuring Entity shall determine to its satisfaction whether the eligible Tenderer that is selected as having submitted the lowest evaluated cost and substantially responsive Tender, meets the qualifying criteria specified in Section III, Evaluation and Qualification Criteria.
- 39.2 The determination shall be based upon an examination of the documentary evidence of the Tenderer's qualifications submitted by the Tenderer, pursuant to ITT 17. The determination shall not take into consideration the qualifications of other firms such as the Tenderer's subsidiaries, parent entities, affiliates, subcontractors (other than Specialized Sub-contractors if permitted in the Tender document), or any other firm(s) different from the Tenderer.
- 393 An affirmative determination shall be a prerequisite for award of the Contract to the Tenderer. A negative determination shall result in disqualification of the Tender, in which event the Procuring Entity shall proceed to the Tenderer who offers a substantially responsive Tender with the next lowest evaluated price to make a similar determination of that Tenderer's qualifications to perform satisfactorily.

40.0 Lowest evaluated tender

Having compared the evaluated prices of Tenders, the Procuring Entity shall determine the Lowest Evaluated Tender. The Lowest Evaluated Tender is the Tender of the Tenderer that meets the Qualification Criteria and whose Tender has been determined to be:

- a) Most responsive to the Tender document; and
- b) the lowest evaluated price.

41.0 Procuring entity's right to accept any tender, and to reject any or all tenders.

The Procuring Entity reserves the right to accept or reject any Tender and to annul the Tender process and reject all Tenders at any time prior to Contract Award, without there by incurring any liability to Tenderers. Incase of annulment, all Tenders submitted and specifically, Tender securities, shall be promptly returned to the Tenderers.

F. AWARD OF CONTRACT

42.0 Award criteria

The Procuring Entity shall award the Contract to the successful tenderer whose tender has been determined to be the Lowest Evaluated Tender.

430 Notice of Intention to Enter into a Contract/Notification of Award

Upon award of the contract and Prior to the expiry of the Tender Validity Period the Procuring Entity shall issue a Notification of Intention to Enter into a Contract/Notification of award to all tenderers which shall contain, at a minimum, the following information:

- a) the name and address of the Tenderer submitting the successful tender;
- b) the Contract price of the successful tender;
- c) a statement of the reason(s) the tender of the unsuccessful tenderer to whom the letter is addressed was unsuccessful, unless the price information in (c) above already reveals the reason;
- d) the expiry date of the Standstill Period; and
- e) instruction son how to request a debriefing and/ or submit a complaint during the stand still period;

44.0 Stand still Period

- **44.1** The Contract shall not be signed earlier than the expiry of a Standstill Period of 14 days to allow any dissatisfied tender to launch a complaint. Where only one Tender is submitted, the Standstill Period shall not apply.
- Where a Standstill Period applies, it shall commence when the Procuring Entity has transmitted to each Tenderer the Notification of Intention to Enter into a Contract with the successful Tenderer.

45.0 Debriefing by The Procuring Entity

- 45.1 On receipt of the Procuring Entity's Notification of Intention to Enter into a Contract referred to in ITT 43, an unsuccessful tenderer may make a written request to the Procuring Entity for a debriefing on specific issues or concerns regarding their tender. The Procuring Entity shall provide the debriefing within five days of receipt of the request.
- Debriefings of unsuccessful Tenderers may be done in writing or verbally. The Tenderer shall bear its own costs of attending such a debriefing meeting.

46.0 Letter of Award

Prior to the expiry of the Tender Validity Period and upon expiry of the Standstill Period specified in ITT 42.1, upon addressing a complaint that has been filed with in the Standstill Period, the Procuring Entity shall transmit the Letter of Award to the successful Tenderer. The letter of award shall request the successful tenderer to furnish the Performance Security within 21 days of the date of the letter.

47.0 Signing of Contract

- 47.1 Upon the expiry of the fourteen days of the Notification of Intention to enter in to contract and upon the parties meeting their respective statutory requirements, the Procuring Entity shall send the successful Tenderer the Contract Agreement.
- Within fourteen (14) days of receipt of the Contract Agreement, the successful Tenderer shall sign, date, and return it to the Procuring Entity.
- 47.3 The written contract shall be entered into within the period specified in the notification of award and before expiry of the tender validity period.

48.0 Performance Security

48.1 Within twenty-one (21) days of the receipt of the Letter of Award from the Procuring Entity, the successful Tenderer shall furnish the Performance Security and, any other documents required in the TDS, in accordance with the General Conditions of Contract, subject to ITT 38.2 (b), using the Performance Security and other Forms included in Section X, Contract Forms, or another form acceptable to the Procuring Entity. A foreign institution providing a bank guarantee shall have a correspondent financial institution located in Kenya, unless the Procuring Entity has agreed in writing that a correspondent bank is not required.

- **48.2** Failure of the successful Tenderer to submit the above-mentioned Performance Security and other documents required in the **TDS** or sign the Contract shall constitute sufficient grounds for the annulment of the award and forfeiture of the Tender Security. In that event the Procuring Entity may award the Contract to the Tenderer offering the next Best Evaluated Tender.
- Performance security shall not be required for contracts estimated to cost less than the amount specified in the Regulations.

49.0 Publication of Procurement Contract

Within fourteen days after signing the contract, the Procuring Entity shall publish the awarded contract at its notice boards and websites; and on the Website of the Authority. At the minimum, the notice shall contain the following information:

- a) name and address of the Procuring Entity;
- b) name and reference number of the contract being awarded, a summary of its scope and the selection method used;
- c) the name of the successful Tenderer, the final total contract price, the contract duration;
- d) dates of signature, commencement and completion of contract;
- e) names of all Tenderers that submitted Tenders, and their Tender prices as readout at Tender opening.

50.0 Procurement related Complaint

The procedures for making Procurement-related Complaints are as specified in the **TDS**.

SECTION II - TENDER DATA SHEET

The following specific data shall complement, supplement, or amend the provisions in the Instruction to Tenderers (ITT). Whenever there is a conflict, the conditions hererin shall prevail over those in ITT

A. GENER	AL
	The name of the Contract is: PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY.
	The reference number of the contract is: W.P ITEM NO. D1166 NB/NB/2401 JOB NO. 10225L
	MMBE&MA/SDBE&F/01/2024-2025
ITT 1.1	The number and identification of Lots (contracts) comprising this tender are: <i>Not applicable</i>
ITT 2.4	The information made available on competeing firms is as follows: As contained in this tender document.
ITT 2.4	The firms that provided consultancy services for the contract being tendered for are: STATE DEPARTMENT FOR PUBLIC WORKS, P.O.BOX 30743-00100 NAIROBI
ITT 3.1	The maximum number of members in a Joint Venture (JV) shall be: Not Applicable

B. Contents	s of Tender Document	
D. Contents	(i) The Tenderer will submit any request for clarifications in writing at the Address:	
TO - 4	Head of Supply Chain Management	
ITT 7.1	MAJI HOUSE, 3RD FLOOR, NAIROBI COUNTY	
	Email: ps@blueeconomy.go.ke.	
	To reach the Procuring Entity not later than 29th October, 2024	
	(ii) The Procuring Entity shall publish its response at the website www.mibema.go.ke	
	()	
ITT 7.2	A pre-arranged pretender site visit <i>shall</i> take place at the following date, time and place:	
	Date: N/A	
	Time: N/A	
	Place: N/A	
	The Tandagan will submit any questions in whiting to people the Decouning Entity not	
ITT 7.3	The Tenderer will submit any questions in writing, to reach the Procuring Entity not later than <i>29th October</i> , <i>2024</i> before the meeting.	
ITT 7.5	The Procuring Entity's website where Minutes of the pre-Tender meeting and the	
111 7.3	pre-arranged pretender will be published is: www.mibema.go.ke	
ITT 9.1	For Clarification of Tender purposes, for obtaining further information and for	
	purchasing tender documents, the Procuring Entity's address is:	
	Head of Supply Chain Management MAJI HOUSE, 3RD FLOOR, NAIROBI COUNTY	
	P.O.BOX 58187 – 00200	
	Email: ps@blueeconomy.go.ke	
C. Preparat	reparation of Tenders	
ITT 11.1	The Tenderer shall submit the following additional documents in its Tender:	
(h)	As listed under Section III-Evaluation and Qualification Criteria under the	
	heading: Preliminary Examination for Determination of Responsiveness	
TTT 42.4		
ITT 13.1	Alternative Tenders <i>shall not</i> be considered.	
ITT 13.2	Alternative times for completion <i>shall not be</i> permitted.	
ITT 13.4	Alternative technical solutions shall be permitted for the following parts of the Works:	
	Not applicable	
	 	
ITT 14.5	The prices quoted by the Tenderer shall be: <i>Fixed</i>	
ITT 15.2		
(a)	Foreign currency requirements <i>not allowed</i> .	
ITT 18.1	The Tender validity period shall be <u>126</u> days.	

ITT 18.3	(a) The Number of days beyond the expiry of the initial tender validity period will be <u>30</u> days.
	(b) The Tender price shall be adjusted by the following percentages of the tender price:
	(i) By (Not applicable) % the local currency portion of the Contract price adjusted to reflect local inflation during the period of extension, and
	(ii) By (Not applicable) % the foreign currency portion of the Contract price adjusted to reflect the international inflation during the period of extension.
ITT 19.1	Tender shall provide a Tender Security. The type of Tender security the amount of <i>Ksh. 850,000.00</i>
ITT 20.1	In addition to the original of the Tender, the number of copies is: One (1No)
ITT 20.3	The written confirmation of authorization to sign on behalf of the Tenderer shall consist of <i>proof of power of attorney</i>
D. Submiss	ion and Opening of Tenders
ITT 22.1	(A) For <u>Tender submission purposes</u> only, the Procuring Entity's address is:
	STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES.
	PRINCIPAL SECRETARY MAJI HOUSE, 3RD FLOOR, NAIROBI COUNTY
	P.O.BOX 58187 – 00200
	Tenders shall shall not submit tenders electronically.
ITT 25.1	The Tender opening shall take place at the time and the address for Opening of Tenders Provided below:
	STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES.
	RAGATI ROAD, Social Health Authority (SHA) Building
	14TH FLOOR, BOARDROOM NAIROBI COUNTY
	Date and time of tender opening: 5th November, 2024 at 10.00 am
ITT 25.1	If Tenderers are allowed to submit Tenders electronically, they shall follow the electronic tender submission procedures specified below: Not Applicable
E. Evaluati	on, and Comparison of Tenders
ITT 30.3	The adjustment shall be based on the <i>average</i> price of the item or component as quoted in other substantially responsive Tenders. If the price of the item or component cannot be derived from the price of other substantially responsive Tenders, the Procuring Entity shall use its best estimate.
	The currency that shall be used for Tender evaluation and comparison purposes only to convert at the selling exchange rate all Tender prices expressed in various currencies into a single currency is: <i>Kenya Shillings</i>
ITT 32	The source of exchange rate shall be: The Central bank of Kenya (mean rate)
	The date for the exchange rate shall be: the deadline date for Submission of the Tenders.
ITT 33.2	A margin of preference <i>shall not</i> apply.
L	

ITT 33.4	The invitation to tender is extended to the following group that qualify for Reservations <i>Not applicable</i>		
ITT 34.1	At this time, the Procuring Entity <i>does not intend to</i> execute certain specific parts of the Works by subcontractors selected in advance.		
ITT 34.2	Contractor's may propose subcontracting: Maximum percentage of subcontracting permitted is: 10 % of the total contract amount. Tenderers planning to subcontract more than 10% of total volume of work shall specify, in the Form of Tender, the activity (ies) or parts of the Works to be subcontracted along with complete details of the subcontractors and their qualification and experience.		
ITT 34.3	The parts of the Works for which the Procuring Entity permits Tenderers to propose Specialized Subcontractors are designated as follows: 1. Mechanical Installation Works		
	2. Electrical Installation Works		
	For the above-designated parts of the Works that may require Specialized Subcontractors, the relevant qualifications of the proposed Specialized Subcontractors will be added to the qualifications of the Tenderer for the purpose of evaluation.		
ITT 35.2 (e)	Additional requirements apply. These are detailed in the evaluation criteria in Section III , Evaluation and Qualification Criteria		
ITT 48.1	Other documents required in addition to the Performance Security are: 1. Program of Works / Progress Chart 2. Insurances (Contractors All Risk & WIBA)		
ITT 50	The procedures for making a Procurement-related Complaint are detailed in the "Notice of Intention to Award the Contract" herein and are also available from the PPRA Website www.ppra.go.ke or email complaints@ppra.go.ke .		
	If a Tenderer wishes to make a Procurement-related Complaint, the Tenderer should submit its complaint following these procedures, in writing (by the quickest means available, that is either by hand delivery or email to:		
	For the attention: Principal Secretary		
	Procuring Entity: STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES		
	Email address: ps@blueeconomy.go.ke		
	In summary, a Procurement-related Complaint may challenge any of the following (among others):		
	(i) the terms of the Tender Documents; and		
	(ii) the Procuring Entity's decision to award the contract.		

SECTION III - EVALUATION AND QUALIFICATION CRITERIA

1.0 GENERAL PROVISIONS

- This section contains the criteria that the Employer shall use to evaluate tender and qualify tenderers. No other factors, methods or criteria shall be used other than specified in this tender document. The Tenderer shall provide all the information requested in the forms included in Section IV, Tendering Forms. The Procuring Entity shall use the Standard Tender Evaluation Document for Goods and Works for evaluating Tenders.
- Wherever a Tenderer is required to state a monetary amount, Tenderers should indicate the Kenya Shilling equivalent using the rate of exchange determined as follows:
 - a) For construction turnover or financial data required for each year Exchange rate prevailing on the last day of the respective calendar year (in which the amounts for that year is to be converted) was originally established.
 - b) Value of single contract Exchange rate prevailing on the date of the contract signature.
 - (c) Exchange rates shall be taken from the publicly available source identified in the ITT 14.3. Any error in determining the exchange rates in the Tender may be corrected by the Procuring Entity.

12 EVALUATION AND CONTRACT AWARD CRITERIA

The Procuring Entity shall use the criteria and methodologies listed in this Section to evaluate tenders and arrive at the Lowest Evaluated Tender. The tender that (i) meets the qualification criteria, (ii) has been determined to be substantially responsive to the Tender Documents, and (iii) is determined to have the Lowest Evaluated Tender price shall be selected for award of contract.

2.0 PRELIMINARY EXAMINATION FOR DETERMINATION OF RESPONSIVENESS

Preliminary examination for Determination of Responsiveness

The Procuring Entity will start by examining all tenders to ensure they meet in all respects the eligibility criteria and other mandatory requirements in the ITT, and that the tender is complete in all aspects in meeting the requirements provided for in the preliminary evaluation criteria outlined below. The Standard Tender Evaluation Report Document for Goods and Works for evaluating Tenders provides very clear guide on how to deal with review of these requirements. Tenders that do not pass the Preliminary Examination will be considered non-responsive and will not be considered further.

PRELIMINARY EVALUATION

S/No	PRELIMINARY EVALUATION CRITERIA / MANDATORY REQUIREMENTS		
MR1	Dully filled and signed form of tender prepared in accordance with ITT 12		
MR2	Dully filled Schedules including priced Bill of Quantities, completed in accordance with ITT 12 and ITT 14;		
MR3	Provide proof of registration with the National Construction Authority (NCA) category 1 to 4 under Building		
	Works with current annual contractors practicing license.		
	Must submit one original copy of the Tender Document and one copy . Submission of Original and Copy (all		
MR4	Volumes) in the format required by the procuring entity and all the tender document (all volumes) to be TAPE		
	BOUND		
MR5	Properly tape bound (perfect cover, hard cover or case bound), paginated, serialized tender document (each page of the tender submission must have a number and the numbers must be in chronological order). For		
	pagination, Arabic Numerals shall be used, i.e. 1,2,3,4,5,6,7,8,9,10n (n being the last numerical page of the tender document)		
MR6	Tender Security in accordance with ITT 19.1; of Bank Guarantee from a bank by Public Procurement Regulatory Authority (PPRA) or insurance company approved by Insurance Regulatory Authority (IRA) in the amount of Kenya shillings 850,000.00. The tender security shall be as per the form included in Section IV, Tender Forms.		
MR7	Provide proof of power of attorney (of tender signatory if not director of the company/ partner, signed and stamped by Commissioner of Oaths)		

MR8	Valid Copy of Certificate of Incorporation/ Registration. (Certified by a Commissioner of Oaths)		
MR9	Valid Current Tax Compliance Certificate		
MR10	Dully filled, signed and stamped Confidential Business Questionnaire		
MR11	Valid Copy of Current Single Business permit		
MR12	Submission of valid CR12 form showing the list of directors /shareholding (issued within the last 12months) or		
	National Identity Card(s) for Sole Proprietorship/ Partnership		
MR13	Letter of authority to seek references from the Tenderer's bankers.		
MR14	Must fill and submit the Certificate of Independent Tender Determination in the format provided		
MR15	Must fill and submit the Self-declaration form that the person/tenderer is not debarred in the matter of the Public		
	Procurement and Asset Disposal Act 2015 in the format provided - Form SD1.		
MR16	Must fill and submit the Self-declaration that the person/tenderer will not engage in any corrupt or fraudulent		
	practice in the format provided - Form SD2		
MR17	Must fill and submit Declaration and Commitment to The Code of Ethics in the format provided		
MR18	Submit certified copies of audited accounts (Signed by the company Director(s) and Auditors who are Certified		
	Public Accountants registered with Institute of Certified Public Accountants of Kenya (ICPAK)) for the last		
	three (3) years (2021, 2022 and 2023) (Certified by a Commissioner of Oaths)		
MR19	Domestic Contractor's Agreement (witnessed by a notaries agent)- A duly signed and stamped Pre-Contract		
	Agreement not earlier than 3 months between the Main Contractor and the <i>Electrical works</i> , & <i>Mechanical</i>		
	Works Sub contractors stating that if the main contractor is awarded the contract, he shall work with the firms		
	as their domestic sub-contractors (Not necessary if the Main Contractor is also registered for specialist works)		

Note: bidders who do not satisfy any of the above requirements shall be considered non-Responsive and their tenders will not be evaluated further.

Preliminary evaluation criteria for the proposed specialist works listed under ITT 34.3 to be as contained in the following Bills:

- Electrical Installation Works
- Mechanical Installation Works

30 TENDER EVALUATION (ITT 35)

In addition to the criteria listed in ITT 35.2 (a) - (d) the following criteria shall apply if permitted under ITT 35.2(e):

- a) Technical evaluation
- b) Financial evaluation
- c) Due diligence and recommendation for Award

TECHNICAL EVALUATION – Qualification Form

tem No.	Qualification Subject	Qualification Requirement	Document To be Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met)
	1. ELIGIBILITY			<u> </u>
1.1	Nationality	Nationality in accordance with ITT 3.6	Forms ELI - 1.1 and 1.2, with attachments	
1.2	Tax Obligations for Kenyan Tenderers	Has produced a current tax clearance certificate or tax exemption certificate issued by Kenya Revenue Authority in accordance with ITT 3.14.	Attachment	
1.3	Conflict of Interest	No conflicts of interest in accordance with ITT 3.3	Form of Tender	
1.4	PPRA Eligibility	Not having been declared ineligible by the PPRA as described in ITT 3.7	Form of Tender	
1.5	State- owned Enterprise	Meets conditions of ITT 3.8	Forms ELI - 1.1 and 1.2, with attachments	
1.6	Goods, equipment and services to be supplied under the contract	To have their origin in any country that is not determined ineligible under ITT 4.1	Forms ELI - 1.1 and 1.2, with attachments	
	2. HISTORICAL CONTRACT	T NON-PERFORMANCE	<u> </u>	<u> </u>
2.1	History of Non- Performing Contracts	Non-performance of a contract did not occur as a result of contractor default since 1 st January 2020.	Form CON-2	
2.2	Suspension Based on Execution of Tender/Proposal Securing Declaration by the Procuring Entity	Not under suspension based on-execution of a Tender/Proposal Securing Declaration pursuant to ITT 19.9	Form of Tender	
2.3	Pending Litigation	Tender's financial position and prospective long-term profitability still sound according to criteria established in 3.1 and assuming that all pending litigation will NOT be resolved against the Tenderer.	Form CON - 2	
2.4	Litigation History	No consistent history of court/arbitral award decisions against the tenderer since 1st January 2021	Form CON - 2; attach affidavit s stamped by an advocate or commission	

^{1.} Non performance, as decided by the Employer, shall include all contracts where (a) nonperformance was not challenged by the contractor, including through referral to the dispute resolution mechanism under the respective contract, and (b) contracts that were so challenged but fully settled against the contractor. Non performance shall not include contracts where Employers decision was overruled by the dispute resolution mechanism. Non performance must be based on all information on fully settled disputes or litigation, i.e. dispute or litigation that has been resolved in accordance with the dispute resolution mechanism under the respective contract and where all appeal instances available to the Bidder have been exhausted.

^{2.} This requirement also applies to contracts executed by the Bidder as JV member.

Qualification form cont'd

Item No.	Qualification Subject	Qualification Requirement	Document To be Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met)	
	3. FINANCIAL SITUATION AND PERFORMACE				
3.1	Financial Capabilities	The Tenderer shall submit the audited balance sheets or, if not required by the laws of the Tenderer's country, other financial statements acceptable to the Procuring Entity, for the last three (3) years shall be submitted and must demonstrate the current soundness of the Tenderer's financial position and indicate its prospective long-term profitability.	Form FIN - 3.1, with attachments		
3.2	Average Annual Construction Turnover	The Tenderer shall demonstrate that it has a minimum average annual construction turnover of Kenya Shillings 60,000,000.00, equivalent calculated as total certified payments received for contracts in progress and/or completed within the last 3 years, divided by 3 years	Form FIN - 3.2 with attachments		
3.3	Financial Resources	The Tenderers shall demonstrate, to the satisfaction of the Procuring Entity, that it has adequate sources of finance, or has available, liquid assets, unencumbered real assets, lines of credit, and other financial means (independent of any contractual advance payment) to meet the cash flow requirements estimated as Kenya Shillings 10,000,000.00 for works the subject contract(s) net of the Tenderer's other commitments.	Form FIN - 3.3 with attachments		
3.4	Current Contract Commitments / Works in Progress	Tenderers and each member to a JV should provide information on their current commitments on all contracts that have been awarded, or for which a letter of intent or acceptance has been received, or for contracts approaching completion, but for which an unqualified, full completion certificate has yet to be issued. (Tenderer to attach evidence such as copies of letter of award, Signed contract and copies of interim payment certificates)	Form FIN - 3.4 with attachments		

Qualification form Cont'd

Item No.	Qualification Subject	Qualification Requirement	Document To be Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met)
	4. EXPERIENCE			
4.1	General Construction Experience	Experience under construction contracts in the role of prime contractor, JV member, sub-contractor, or management contractor for at least the last 3 years, starting 1st January 2021	4. Form EXP - 4.1 Experience	
4.2 (a)	Specific Construction & Contract Management Experience	A minimum number of 3 similar contracts ¹ specified below that have been satisfactorily and substantially completed as a prime contractor, joint venture member, management contractor or sub-contractor between 1st January 2021 and tender submission deadline i.e. Three (3) contracts, each of minimum value Kenya shillings 40,000,000.00 equivalent.	Form EXP 4.2(a)	
		Bidders shall attach copies of the following: a) Letters of Award or, b) Signed Contract and Completion Certificate for the respective projects. or c) If project is ongoing it must be at least 80% complete. Bidder to attach copies of interim payment certificates		

- 1. The similarity shall be based on the physical size, complexity, methods/technology and/or other characteristics described in the Bills of Quantities and Drawings. Summation of number of small value contracts (less than the value specified under requirement) to meet the overall requirement will not be accepted.
- 2. Substantial completion shall be based on 80% or more works completed under the contract.
- 3. For contracts under which the Bidder participated as a joint venture member or sub-contractor, only the Bidder's share, by value, shall be considered to meet this requirement.
- 4. In the case of JV, the value of contracts completed by its members shall not be aggregated to determine whether the requirement of the minimum value of a single contract has been met. Instead, each contract performed by each member shall satisfy the minimum value of a single contract as required for single entity. In determining whether the JV meets the requirement of total number of contracts, only the number of contracts completed by all members each of value equal or more than the minimum value required shall be aggregated.

Qualification form Cont'd

Item No.	Qualification Subject	Qualification Requirement	Document To be Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met)
	5. Equipment		1	
5.1	Contractors key equipment	Show evidence of ownership/access to essential construction machinery, equipment and plant.	Form EQU: Equipment	
		Notes		
		 If the equipment is owned, must provide CLEAR copies of logbook or proof of ownership. 		
		• If equipment is hired or leased Provide a commitment letter from the lessor of the equipment addressed to the PRINCIPAL SECRETARY-STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES indicating that the lessor shall avail the equipment upon award of the tender and submit a copy of a written agreement to lease between lessee and lessor indicating list of equipment and their corresponding copies of log books or proof of ownership by lessor;		
		The equipment listed shall be available on site when required		
		 a) Relevant Transport 2No Pick-ups 2No Tippers/Lorry Trucks 		
		 b) Relevant Tools and Equipment - 1no. Tile Cutting Machine - 1no. Concrete Mixer - 1no. Hoist - Atleast 4 sets of Steel Scaffolds 		

Item No.	Qualification Subject	Qualification Requirement	Completed by Tenderer	For Procuring Entity's Use (Qualification met or Not Met,
	6. Key Personnel			
5.1	Contractor's Representative and Key Personnel	 a) Project Manager Minimum qualifications and technical experience Bachelor's degree in Architecture, Quantity Surveying, or Construction Management. Registered Professional with the respective registration bodies Board of Registration of Architects and Quantity Surveyors (BORAQS) with a valid practicing license or a Construction Manager who is a professional member of Association of Construction Managers of Kenya (ACMK) and/or Architectural Association of Kenya (AAK)-Construction Project Managers Chapter and/or Institution of Construction Project Managers of Kenya (ICPMK) with current membership certificate. General Experience –15 years. Specific experience in Construction of building works – 10 years. 	Form PER -1 & Form PER -2	
		 b) Site Agent Minimum qualifications and technical experience 5. Higher Diploma in Building Construction or equivalent. 6. Specific experience in Construction of building works – 8 years. 		
		 c) Foreman <u>Minimum qualifications and technical experience</u> 7. Certificate- Building Construction, Electrical, or Mechanical 8. Experience – 8 years 		
		 d) Occupational Health and Safety Personnel Qualifications and technical experience 9. Certificate- Occupational Safety and Health 10. Experience – 5 years 		
		Note: Certified copies of National Identity Cards and certificates to be provided as evidence.		

Note: Bidders who do not satisfy any of the above qualification requirements shall be considered non-Responsive and their tenders will not be evaluated further

FINANCIAL EVALUATION

Upon completion of the technical evaluation a detailed financial evaluation shall follow. The evaluation shall be in the following **three stages:**

- a) Determination of Arithmetic errors
- b) Comparison of Rates; and
- c) Consistency of the Rates.

DUE DILIGENCE AND RECOMMENDATION FOR AWARD

Particulars of The Client, STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES, may post qualification: inspect the premises and under due diligence to seek further clarification/confirmation if

inspect the premises and under due diligence to seek further clarification/confirmation if necessary, to confirm authenticity /compliance of any condition of the tender /qualifications of the tenderer in line with Section 83 of the Public Procurement and Asset

Disposal Act, 2015

Award Criteria: The firm achieving the lowest evaluated price will be awarded the contract in line with

Section 86 and Section 155(4) of the Public Procurement and Disposal Act,2015

SECTION IV - TENDERING FORMS

QUALIFICATION FORMS

1. FOREIGN TENDERERS 40%RULE

Pursuant to ITT 3.9, a foreign tenderer must complete this form to demonstrate that the tender fulfils this condition.

ITEM	Description of work item	Description of location of source	COST IN K.Shillings	Comments, If any	
A	LOCAL LABOR				
1					
2					
3					
4					
5					
В	SUB CONTRACTS FRO	OM LOCAL SOURCES			
1					
2					
3					
5					
С	LOCAL MATERIALS				
1					
2					
3					
5					
D	USE OF LOCAL PLAN	L Γ AND EQUIPMENT			
1					
2					
3					
4					
5					
Е	ADD ANY OTHER ITEM				
1					
2					
3					
4					
5					
6					
	TOTAL COST OF LOCAL CONTENT				
	PERCENTAGE OF CONTRACT PRICE				

2. FORM EQU: EQUIPMENT

The Tenderer shall provide adequate information to demonstrate clearly that it has the capability to meet the requirements for the key equipment listed in Section III, Evaluation and Qualification Criteria. A separate Form shall be prepared for each item of equipment listed, or fo ralternative equipment proposed by the Tenderer.

Item of equipa	ment			
Equipment information	Name of manufacturer	Model and power rating		
	Capacity	Year of manufacture		
Current	Current location			
	Indicate source of the equipment ☐ Owned ☐ Rented ☐ Leased	☐ Specially manufactured		
	Omit the following information for equipment owned by the Tenderer.			
Owner	Name of owner			
	Address of owner			
	Telephone	Contact name and title		
	Fax	Telex		
Agreements	Details of rental / lease / manufacture agreements specific to the project			

3. <u>FORM PER -1</u>

Contractor's Representative and Key Personnel Schedule

Tenderers should provide the names and details of the suitably qualified Contractor's Representative and Key Personnel to perform the Contract. The data on their experience should be supplied using the Form PER-2 below for each candidate.

Contractor' Representative and Key Personnel

1.	Title of position: Contractor's Representative		
	Name of candidate:		
	Duration of	[insert the whole period (start and end dates) for which this position	
	appointment:	will be engaged	
	Time	[insert the number of days/week/months/ that has been scheduled for	
	commitment: for	this position]	
	this position:		
	Expected time	[insert the expected time schedule for this position (e.g. attach high	
	schedule for this	level Gantt chart]	
	position:		
2.	Title of position: [_	J	
	Name of candidate		
	Duration of	[insert the whole period (start and end dates) for which this position	
	appointment:	will be engaged]	
	Time	[insert the number of days/week/months/ that has been scheduled for	
	commitment: for	this position]	
	this position:		
	Expected time	[insert the expected time schedule for this position (e.g. attach high	
	schedule for this	level Gantt chart]	
	position:		
3.	Title of position: [
	Name of candidate		
	Duration of	[insert the whole period (start and end dates) for which this position	
	appointment:	will be engaged]	
	Time	[insert the number of days/week/months/ that has been scheduled for	
	commitment: for	this position]	
	this position:		
	Expected time	[insert the expected time schedule for this position (e.g. attach high	
	schedule for this	level Gantt chart]	
	position:		
4.	Title of position: /		
	Name of candidate		
	Duration of	[insert the whole period (start and end dates) for which this position	
	appointment:	will be engaged]	
	Time	[insert the number of days/week/months/ that has been scheduled for	
	commitment: for	this position]	
	this position:		
	Expected time	[insert the expected time schedule for this position (e.g. attach high	
	schedule for this	level Gantt chart]	
-	position:	sout title?	
5.	Title of position: [in	sert title]	
	Name of candidate Duration of	Singart the whole paried (start and and dates) for which this are iti-	
		[insert the whole period (start and end dates) for which this position	
	appointment: Time	will be engaged] [insert the number of days/week/months/ that has been scheduled for	
	commitment: for		
	this position:	this position]	
	Expected time	[insert the expected time schedule for this position (e.g. attach high	
	schedule for this	level Gantt chart]	
	position:	icvei ounii enurij	

4. **FORM PER - 2:**

Resume and Declaration - Contractor's Representative and Key Personnel.

Name of Tenderer					
Position[#1]:[ti	tle of position from Form PER-1]				
Personnel information	Name:	Date of birth:			
	Address:	E-mail:			
	Professional qualifications:				
	Academic qualifications:				
	Language proficiency: [language and levels of speaking, reading and writing skills]				
Details	Address of Procuring Entity:				
	Telephone:	Contact (manager / personnel officer):			
	Fax:				
	Jobtitle:	Years with present Procuring Entity:			

Summarize professional experience in reverse chronological order. Indicate particular technical and managerial experience relevant to the project.

Project	Role	Duration of involvement	Relevant experience
[main project details]	[role and responsibilities on the project]	[time in role]	[describe the experience relevant to this position]

Declaration

I, the undersigned [insert either "Contractor's Representative" or "Key Personnel" as applicable], certify that to the best of my knowledge and belief, the information contained in this Form PER-2 correctly describes myself, my qualifications and myexperience.

I confirm that I am available as certified in the following table and throughout the expected time schedule for this position as provided in the Tender:

Commitment	Details
Commitment to duration of contract:	[insert period (start and end dates) for which this Contractor's Representative or Key Personnel is available to work on this contract]
Time commitment:	[insert period (start and end dates) for which this Contractor's Representative or Key Personnel is available to work on this contract]

I understand that any misrepresentation or omission in this Form may:

- a) be taken into consideration during Tender evaluation;
- b) result in my disqualification from participating in the Tender;
- c) result in my dismissal from the contract.

Name of Contractor's Representative or Key Personnel: [insert name]
Signature:
Date: (day month year):
Counter signature of authorized representative of the Tenderer:
Signature:
Date: (day month year):

5. TENDERERS QUALIFICATION WITHOUT PREQUALIFICATION

To establish its qualifications to perform the contract in accordance with Section III, Evaluation and Qualification Criteria the Tenderer shall provide the information requested in the corresponding Information Sheets included hereunder.

51 FORM ELI -1.1

Tenderer Information Form
Date:
ITT No. andtitle:
Tenderer's name
In case of Joint Venture (JV), name of each member:
Tenderer's actual or intended country of registration: [indicate country of Constitution]
Tenderer's actual or intended year of incorporation:
Tenderer's legal address [in country of registration]:
Tenderer's authorized representative information Name: Address: Telephone/Fax numbers: E-mail address:
 1. Attached are copies of original documents of Articles of Incorporation (or equivalent documents of constitution or association), and/or documents of registration of the legal entity named above, in accordance with ITT 3.6 In case of JV, letter of intent to form JV or JV agreement, in accordance with ITT 3.5 In case of state-owned enterprise or institution, in accordance with ITT 3.8, documents establishing: Legal and financial autonomy Operation under commercial law Establishing that the Tenderer is not under the supervision of the Procuring Entity 2. Included are the organizational chart, a list of Board of Directors, and the beneficial ownership.

52 FORM ELI -1.2

Tenderer's JV Information Form (to be completed for each member of Tenderer's JV)

Date:
ITT No. andtitle:
Tenderer's JV name:
JV member's name:
JV member's country of registration:
JV member's year of constitution:
JV member's legal address in country of constitution:
JV member's authorized representative information Name: Address: Telephone/Fax numbers: E-mailaddress:
 Attached are copies of original documents of □ Articles of Incorporation (or equivalent documents of constitution or association), and/or registration documents of the legal entity named above, in accordance with ITT 3.6. □ In case of a state-owned enterprise or institution, documents establishing legal and financial autonomy, operation in accordance with commercial law, and that they are not under the supervision of the Procuring Entity, in accordance with ITT 3.5.
2. Included are the organizational chart, a list of Board of Directors, and the beneficial ownership.

53 **FORM CON –2**

Historical Contract Non-Performance, Pending Litigation and Litigation History

Tenderer siv	enderer sname:				
JVMember'	VMember's NameITT No. andtitle:				
Non-Perf	Formed Contracts in	n accordance with Section III, Evaluation and Qualification C	Criteria		
		e did not occur since 1 st January <i>[insert year]</i> specified in Sect tion Criteria, Sub-Factor 2.1.	ion III,		
	act(s) not performe ication Criteria, red	d since 1 st January [insert year] specified in Section III, Evaluquirement 2.1	nation and		
	act(s) withdrawn si ication Criteria, red	nce 1 st January <i>[insert year]</i> specified in Section III, Evaluation quirement 2.1	on and		
Year	Non- performed portion of contract	Contract Identification	Total Contract Amount (current value, currency, exchange rate and Kenya Shilling equivalent)		
[insert year]	[insert amount and percentage]	Contract Identification: [indicate complete contract name/ number, and any other identification] Name of Procuring Entity: [insert full name] Address of Procuring Entity: [insert street/city/country] Reason(s) for nonperformance: [indicate main reason(s)]	[insert amount]		
Pending Litigation, in accordance with Section III, Evaluation and Qualification Criteria					
 □ No pending litigation in accordance with Section III, Evaluation and Qualification Criteria, Sub-Factor 2.3. □ Pending litigation in accordance with Section III, Evaluation and Qualification Criteria, Sub-Factor 2.3 as indicated below. 					

Year of dispute	Amount in disput (currency)	e Contract Identification	Total Contract Amount (currency), Kenya Shilling Equivalent (exchange rate)
		Contract Identification: Name of Procuring Entity: Address of Procuring Entity: Matter in dispute: Party who initiated the dispute: Status of dispute:	
		Contract Identification: Name of Procuring Entity: Address of Procuring Entity: Matter in dispute: Party who initiated the dispute: Status of dispute:	
Litigation Hi	story in accordance with	Section III, Evaluation and Qualification Criter	ia
Factor 2.4 ☐ Litigation	1 .	nce with Section III, Evaluation and Qualification with Section III, Evaluation and Qualification Crit	
Year of award	Outcome as percentage of Net Worth	Contract Identification	Total Contract Amount (currency), Kenya Shilling Equivalent (exchange rate)
[insert year]	[insert percentage]	Contract Identification: [indicate complete contract name, number, and any other identification]	[insert amount]
		Name of Procuring Entity: [insert full name] Address of Procuring Entity: [insert street/city/country]	
		Matter in dispute: [indicate main issues in dispute]	
		Party who initiated the dispute: [indicate "Procuring Entity" or "Contractor"] Reason(s) for Litigation and award decision [indicate main reason(s)]	

Include details relating to potential bid-rigging practices such as previous occasions where tenders were withdrawn, joint bids with competitors, subcontracting work to unsuccessful tenderers, etc.

5.4 **FORM FIN – 3.1:**

Financial Situation and Performance
Tenderer's Name:
Date:
JV Member's Name
ITT No. and title:

5.4.1. Financial Data

Type of Financial information in	Historic information for previousyears,				
(currency)	(amount in currency, currency, exchange rate*, USD equivalent)				
	Year1	Year2	Year 3	Year4	Year 5
Statement of Financial Position (Information	from Balance S	Sheet)	1	1
Total Assets (TA)					
Total Liabilities (TL)					
Total Equity/Net Worth (NW)			13/6		
Current Assets (CA)	4		CA		
Current Liabilities (CL)					
Working Capital (WC)	AARA	A B E E			
Information from Income Statem	nent				
Total Revenue (TR)					
Profits Before Taxes (PBT)					
Cash Flow Information	l			1	
Cash Flow from Operating Activities					

^{*}Refer to ITT 15 for the exchange rate

5A2 Sources of Finance

Specify sources of finance to meet the cash flow requirements on works currently in progress and for future contract commitments.

No.	Source of finance	Amount (Kenya Shilling equivalent)
1		
2		
3		

E 42	T	1	.1	
543	rına	nciai	aocu	ments

- a) reflect the financial situation of the Tenderer or incase of JV member, and not an affiliated entity (such as parent company or group member).
- b) Be independently audited or certified in accordance with local legislation.
- c) Be complete, including all notes to the financial statements.
- d) Correspond to accounting periods already completed and audited.

Attached are copies of financial statements for the_	years required above; and
complying with the requirements.	

¹If the most recent set of financial statements is for a period earlier than 12 months from the date of Tender, the reason for this should be justified.

5.5 FORM FIN - 3.2:

Average Annual Construction Turnover

Tenderer's Name:	
Date:	
JV Member's Name	
ITT No. and title:	

	Annual turnover data (construction only)					
Year	Amount Currency	Exchange rate	Kenya Shilling equivalent			
[indicate year]	[insert amount and indicate currency]					
Average Annual Construction Turnover *						

^{*} See Section III, Evaluation and Qualification Criteria, Sub-Factor 3.2.

5.6 FORMFIN-3.3:

Financial Resources

Specify proposed sources of financing, such as liquid assets, unencumbered real assets, lines of credit, and other financia lmeans, net of current commitments, available to meet the total construction cash flow demands of the subject contractor contracts as specified in Section III, Evaluation and Qualification Criteria.

Fina	Financial Resources				
No.	Source of financing	Amount (Kenya Shilling equivalent)			
1					
2					
3					
4					

5.7 FORMFIN-3.4:

Current Contract Commitments / Works in Progress

Tenderers and each member to a JV should provide information on their current commitments on all contracts that have been awarded, or for which a letter of intent or acceptance has been received, or for contracts approaching completion, but for which an unqualified, full completion certificate has yet to be issued.

Curi	Current Contract Commitments						
No.	Name of Contract	Procuring Entity's Contact Address, Tel,	Valueof Outstanding Work [Current Kenya Shilling /month Equivalent]	Estimated Completion Date	Average Monthly Invoicing Over Last Six Months [Kenya Shilling /month)]		
1							
2							
3							
4							
5							

58 FORM EXP -4.1

General Construction Experience

Tenderer'sName:	Date:
3	
JVMember'sName_	ITT No. andtitle:

Page____of___pages

Starting Year	Ending Year	Contract Identification	Role of Tenderer
		Contract name: Brief Description of the Works performed by the Tenderer: Amount of contract: Name of Procuring Entity: Address:	
		Contract name: Brief Description of the Works performed by the Tenderer: Amount of contract: Name of Procuring Entity: Address:	
		Contract name: Brief Description of the Works performed by the Tenderer: Amount of contract: Name of Procuring Entity: Address:	

59 FORM EXP - 4.2(a)

Specific Construction and Contract Management Experience

Tenderer's Name: Date: JV Member's Name ITT No. and title:				
Similar Contract No.	Information	1		
Contract Identification				
Award date				
Completion date				
Role in Contract	Prime Contractor □	Member in JV □	Management Contractor	Sub- contractor
Total Contract Amount			Kenya Shilling	
If member in a JV or sub-contractor, specify participation in total Contract amount				
Procuring Entity's Name:				
Address: Telephone/fax number E-mail:				
Description of the similarity in accordance with Sub-Factor 4.2(a) of Section III:				
1 Amount				
Physical size of required works items				
3 Complexity				
4 Methods/Technology				
5 Construction rate for key activities				
6 Other Characteristics				

5.10 FORM EXP - 4.2 (b)

Construction Experience in Key Activities

Tenderer's Name:					
Date:					
Tenderer's JV Member Name:					
Sub-contractor's Name ² (as per ITT 34):ITT No. and title:		<u> </u>			
All Sub-contractors for key activities must co Evaluation and Qualification Criteria, Sub-Fa		formatio	on in this	form as per IT	T 34 and Section II
1. Key Activity No One:					
	Informatio	n			
Contract Identification					
Award date					
Completion date					
Role in Contract	Prime Contractor	Men JV □	nber in	Management Contractor	Sub-contractor
Total Contract Amount				Kenya Shillir	ıg
Quantity (Volume, number or rate of production, as applicable) performed under the contract per year or part of the year	Total quantithe contract	ty in		ercentage articipation	Actual Quantity Performed (i) x (ii)
Yearl					
Year 2					
Year 3					
Year 4					
Procuring Entity's Name:					
Address: Telephone/fax number E-mail:					
Description of the key activities in accordance with Sub-Factor 4.2(b) of Section III:					

 $[\]overline{^2}$ If applicable

OTHER FORMS

6. FORM OF TENDER

(Amended and issued pursuant to PPRA CIRCULAR No. 02/2022)

INSTRUCTIONS TO TENDERERS

- i) All italicized text is to help the Tenderer in preparing this form.
- ii) The Tenderer must prepare this Form of Tender on stationery with its letterhead clearly showing the Tenderer's complete name and business address. Tenderers are reminded that this is a mandatory requirement.
- iii) Tenderer must complete and sign CERTIFICATE OF INDEPENDENT TENDER DETERMINATION and the SELF DECLARATION FORMS OF THE TENDERER as listed under (xxii) below.

Date	of this Tender submission:[insert date (as day, month and year) of Tender submission] Tender
Nam	e and Identification:[insert identification] Alternative
No.:	[insert identification No if this is a Tender for an alternative]
То:	[Insert complete name of Procuring Entity]
for	te of this Tender submission: [insert date (as day, month and year) of Tender submission] Request Tender No.: [insert identification] Name and description of Tender [Insert as per ITT) Alternative No.: sert identification No if this is a Tender for an alternative]
To:	[insert complete name of Procuring Entity]
Dea	ar Sirs,
1.	In accordance with the Conditions of Contract, Specifications, Drawings and Bills of Quantities for the execution of the above named Works, we, the undersigned offer to construct and complete the Works and remedy any defects therein for the sum¹ of Kenya Shillings [[Amount in figures]
	The above amount includes foreign currency ² amount (s) of [state figure or a percentage and currency] [figures][words]
2.	We undertake, if our tender is accepted, to commence the Works as soon as is reasonably possible after the receipt of the Architect notice to commence, and to complete the whole of the Works comprised in the Contract within the time stated in the Special Conditions of Contract.
3.	We agree to adhereby this tender until[Insert date], and it shall remain binding upon us and may be accepted at any time before that date.
4.	We understand that you are not bound to accept the lowest or any tender you may receive.
5.	We, the under signed, further declare that: i) No reservations: We have examined and have no reservations to the tender document, including Addenda issuedinaccordance with ITT 28;
	ii) <u>Eligibility:</u> We meet the eligibility requirements and have no conflict of interest in accordance with ITT 3

and 4;

¹ This sum should be carried forward from the Summary of the Bills of Quantities.

² The percentage quoted above should not include provisional sums, and not more than two foreign currencies are allowed.

- iii) <u>Tender Securing Declaration</u>: We have not been suspended nor declared ineligible by the Procuring Entity based on execution of a Tender-Securing or Proposal-Securing Declaration in the Procuring Entity's Country in accordance with ITT 19.8;
- *Conformity*: We offer to execute in conformity with the tendering documents and in accordance with the implementation and completion specified in the construction schedule, the following Works: [insert a brief description of the Works];
- v) <u>Tender Price:</u> The total price of our Tender, excluding any discounts offered in item 1 above is: [Insert one of the options below as appropriate]
- vi Option 1, incase of one lot: Total priceis: [insert the total price of the Tender in words and figures, indicating the various amounts and the respective currencies]; or

Option2, in case of multiple lots:

- (a) Total price of each lot [insert the total price of each lot in words and figures, indicating the various amounts and the respective currencies]; and
- (b) <u>Total price of all lots</u> (sum of all lots) [insert the total price of all lots in words and figures, indicating the various amounts and the respective currencies];
- vii) <u>Discounts:</u> The discounts offered and the methodology for their application are:
- viii) The discounts offered are: [Specify in detail each discount offered.]
- ix) The exact method of calculations to determine the net price after application of discounts is shown below: [Specify in detail the method that shall be used to apply the discounts];
- x) <u>Tender Validity Period</u>: Our Tender shall be valid for the period specified in TDS 18.1 (as amended, if applicable) from the date fixed for the Tender submission deadline specified in TDS 22.1 (as amended, if applicable), and it shall remain binding upon us and may be accepted at any time before the expiration of that period;
- xi) <u>Performance Security:</u> If our Tender is accepted, we commit to obtain Performance Security in accordance with the Tendering document;
- xii) One Tender Per Tender: Weare not submitting any other Tender(s) as an individual Tender, and we are not participating in any other Tender(s) as a Joint Venture member or as a sub-contractor, and meet the requirements of ITT 3.4, other than alternative Tenders submitted in accordance with ITT 13.3;
- xiii) <u>Suspension and Debarment</u>: We, along with any of our subcontractors, suppliers, Engineer, manufacturers, or service providers for any part of the contract, are not subject to, and not controlled by any entity or individual that is subject to, a temporary suspension or a debarment imposed by the Public Procurement Regulatory Authority or any other entity of the Government of Kenya, or any international organization.
- xiv) <u>State-owned enterprise or institution:</u> [select the appropriate option and delete the other] [We are not a state-owned enterprise or institution]/[We are a state-owned enterprise or institution but meet the requirements of ITT3.8];
- xv) Commissions, gratuities, fees: We have paid, or will pay the following commissions, gratuities, or fees with respect to the tender process or execution of the Contract: [insert complete name of each Recipient, its full address, the reason for which each commission or gratuity was paid and the amount and currency of each such commission or gratuity].

Name of Recipient	Address	Reason	Amount

(If none has been paid or is to be paid, indicate "none.")

- xvi) <u>Binding Contract:</u> We understand that this Tender, together with your written acceptance there of included in your Letter of Acceptance, shall constitute a binding contract between us, until a formal contract is prepared and executed;
- xvii) Not Bound to Accept: We understand that you are not bound to accept the lowest evaluated cost Tender, the Most Advantageous Tender or any other Tender that you may receive;
- xviii) <u>Fraud and Corruption:</u> We here by certify that we have taken steps to ensure that no personacting for us or on our behalf engages in any type of Fraud and Corruption; and
- xix) <u>Collusive practices:</u> We hereby certify and confirm that the tender is genuine, non-collusive and made with the intention of accepting the contract if awarded. To this effect we have signed the "Certificate of Independent Tender Determination" attached below.
- we undertake to adhere by the Code of Ethics for Persons Participating in Public Procurement and Asset Disposal, copy available from _______(specify website) during the procurement process and the execution of any resulting contract.
- xxi) **Beneficial Ownership Information:** We commit to provide to the procuring entity the Beneficial Ownership Information in conformity with the Beneficial Ownership Disclosure Form upon receipt of notification of intention to enter into a contract in the event we are the successful tenderer in this subject procurement proceeding.
- xxii) We, the Tenderer, have duly completed, signed and stamped the following Forms as part of our Tender:
 - a) Tenderer's Eligibility; Confidential Business Questionnaire to establish we are no tin any conflict to interest.
 - (b) Certificate of Independent Tender Determination to declare that we completed the tender without colluding with other tenderers.
 - (a) Self-Declaration of the Tenderer to declare that we will, if awarded a contract, not engage in any form of fraud and corruption.
 - (d) Declaration and commitment to the Code of Ethics for Persons Participating in Public Procurement and Asset Disposal.

Further, we confirm that we have read and understood the full content and scope of fraud and corruption as informed in "Appendix 1 - Fraud and Corruption" attached to the Form of Tender.

Name of the Tenderer: *[insert complete name of person signing the Tender]

Name of the person duly authorized to sign the Tender on behalf of the Tenderer: **[insert complete name of person duly authorized to sign the Tender]

Title of the person signing the Tender: [insert complete title of the person signing the Tender]

Signature of the person named above: [insert signature of person whose name and capacity are shown above]

Date signed [insert	date of signing] day of [insert month], [insert year]	
Datesigned	day of	.,

Notes

^{*} In the case of the Tender submitted by joint venture specify the name of the Joint Venture as Tenderer.

**Person signing the Tender shall have the power of attorney given by the Tenderer to be attached with the Tender.

(a) TENDERER'S ELIGIBILITY-CONFIDENTIAL BUSINESS QUESTIONNAIRE

Instruction to Tenderer

Tender is instructed to complete the particulars required in this Form, *one form for each entity if Tender is a JV*. Tenderer is further reminded that it is an offence to give false information on this Form.

(a) Tenderer's details

	ITEM	DESCRIPTION
1	Name of the Procuring Entity	
2	Reference Number of the Tender	
3	Date and Time of Tender Opening	
4	Name of the Tenderer	
5	Full Address and Contact Details of the Tenderer.	 Country City Location Building Floor Postal Address Name and email of contact person.
6	Current Trade License Registration Number and Expiring date	
7	Name, country and full address (postal and physical addresses, email, and telephone number) of Registering Body/Agency	
8	Description of Nature of Business	
9	Maximum value of business which the Tenderer handles.	
10	State if Tenders Company is listed in stock exchange, give name and full address (postal and physical addresses, email, and telephone number) of state which stock exchange	

General and Specific Details

(b)	Sole Proprietor, provide the following	g details.			
Nam	e in full	Age	•		
Natı Citiz	onalityenship	Country of Or	igin		
(c)	Partnership, provide the following de				
	Names of Partners	Nationality	Citizen	ıship	% Shares owned
1				1	
2					
3					
(d)	Registered Company, provide the formula in the state of public Company in the state of the nominal and issued companies. Nominal Kenya Shillings (Equivalent Issued Kenya Shillings (Equivalent). iii) Give details of Directors as follows:	apital of the Company	••••	•••••	
	Names of Director	Nationality	Citizen	ship	% Shares owned
1				1	
2					
3					
(e)	i) Are there any person/persons in interest or relationship in this fit. If yes, provide details as follows:	rm? Yes/No(Name of Pro	•	who has/have an
	Names of Person	Designation in Procuring Entit		Interest or F Tenderer	Relationship with
1		1 locaring Entit	, y	Tenderer	
2					
3					
			<u> </u>		

(ii) Conflict of interest disclosure

	Type of Conflict	Disclosure YES ORNO	If YES provide details of the relationship with Tenderer
1	Tenderer is directly or indirectly controls, is controlled by or is under common control with another tenderer.		
2	Tenderer receives or has received any direct or indirect subsidy from another tenderer.		
3	Tenderer has the same legal representative as another tenderer		
4	Tender has a relationship with another tenderer, directly or through common third parties, that puts it in a position to influence the tender of another tenderer, or influence the decisions of the Procuring Entity regarding this tendering process.		
5	Any of the Tenderer's affiliates participated as a consultant in the preparation of the design or technical specifications of the works that are the subject of the tender.	A	
6	Tenderer would be providing goods, works, non-consulting services or consulting services during implementation of the contract Specified in this Tender Document.		
7	Tenderer has a close business or family relationship with a professional staff of the Procuring Entity who are directly or indirectly involved in the preparation of the Tender document or specifications of the Contract, and/or the Tender evaluation process of such contract.	MBE	
8	Tenderer has a close business or family relationship with a professional staff of the Procuring Entity who would be involved in the implementation or supervision of the such Contract.		
9	Has the conflict stemming from such relationship stated in item 7 and 8 above been resolved in a manner acceptable to the Procuring Entity throughout the tendering process and execution of the Contract.		

Certification

(Signature)	(Date)	
Title or Designation		
Full Name		
submission.		

On behalf of the Tenderer, I certify that the information given above is complete, current and accurate as at the date of

b) <u>CERTIFICATE OF INDEPENDENT TENDER DETERMINATION</u>

I, t	he uı	ndersigned, in submitting the accompanying Letter of Tender to the	[N f D F. dit . l for
res	pons	se to the request for tenders made by:	[Name and number of tender] in [Name of Tenderer] do hereby
ma	ke tr	he following statements that I certify to be true and complete in every re	espect:
Ice	rtify	, on behalf of	[Name of Tenderer]that:
1.	I ha	ave read and I understand the contents of this Certificate;	
2.		understand that the Tender will be disqualified if this Certificate is found spect;	not to be true and complete in every
3.		mthe authorized representative of the Tenderer with authority to sign the onder on behalf of the Tenderer;	is Certificate, and to submit the
4.		or the purposes of this Certificate and the Tender, I understand that the walividual or organization, other than the Tenderer, whether or not affiliate	
	a) b)	Has been requested to submit a Tender in response to this request for could potentially submit a tender in response to this request for tender abilities or experience;	
5.	Th	neTenderer discloses that [check one of the following, as applicable]:	
	a)	The Tenderer has arrived at the Tender independently from, and with agreement or arrangement with, any competitor;	out consultation, communication,
	b)	theTenderer has entered into consultations, communications, agreemed competitors regarding this request for tenders, and the Tenderer discomplete details thereof, including the names of the competitors and consultations, communications, agreements or arrangements;	scloses, in the attached document(s),
6.		particular, without limiting the generality of paragraphs (5)(a) or(5)(b) a mmunication, agreement or arrangement with any competitor regarding	
	a)b)c)d)	,	he request for Tenders; except as
7.	reg for	addition, there has been no consultation, communication, agreement garding the quality, quantity, specifications or delivery particulars of the r tenders relates, except as specifically authorized by the procuring rsuant toparagraph(5)(b) above;	works or services to which this request
8.	ind Co	the terms of the Tender have not been, and will not be, knowingly directly, to any competitor, prior to the date and time of the official tendentract, whichevercomesfirst, unless otherwise required by aw or a graph (5)(b) above.	der opening, or of the awarding of the
	me_ le		

[Name, title and signature of authorized agent of Tenderer and Date]

(c) SELF- DECLARATION FORMS

FORM SD1

SELF DECLARATION THAT THE PERSON/TENDERER IS NOT DEBARRED IN THE MATTER OF THE PUBLIC PROCUREMENT AND ASSET DISPOSAL ACT 2015.

	, of Post Office Box being a resident of
1.	THAT I am the Company Secretary/ Chief Executive/Managing Director/Principal Officer/Direct or of
2.	THAT the aforesaid Bidder, its Directors and subcontractors have not been debarred from participating in procurement proceeding under Part IV of the Act.
3.	THAT what is deponed to here in above is true to the best of my knowledge, information and belief.
	(Title) (Signature) (Date)
	Bidder Official Stamp

FORM SD2

SELF DECLARATION THAT THE PERSON/TENDERER WILL NOT ENGAGE IN ANY CORRUPT OR FRAUDULENT PRACTICE.

• • •	
1.	THAT I am the Chief Executive/Managing Director/Principal Officer/Director of
2.	THAT theafore said Bidder, its servants and/oragents/subcontractorswillnotengageinanycorruptorfraudulent practice and has not been requested to pay any inducement to any member of the Board, Management, Staff and/or employees and/or agents of (insert name of the Procuring entity) which is the procuring entity.
3.	THAT the aforesaid Bidder, its servants and/or agents /subcontractors have not offered any inducement to any member of the Board, Management, Staff and/or employees and/or agents of
4.	THAT the aforesaid Bidder will not engage /has not engaged in any corrosive practice with other bidders participating in the subject tender
5.	THAT what is deponed to here in above is true to the best of my knowledge information and belief.
	(Title) (Signature) (Date)
	Bidder's Official Stamp

DECLARATION AND COMMITMENT TO THE CODE OF ETHICS

I (person) on behalf of (Name of the Business/ Company/Firm)
declare that I have read and fully understood the contents of the
Public Procurement & Asset Disposal Act, 2015, Regulations and the Code of Ethics for persons participating in
Public Procurementand Asset Disposal and my responsibilities under the Code.
I do here by commit to abide by the provisions of the Code of Ethics for persons participating in Public Procuremen and Asset Disposal.
Name of Authorized signatory
Sign
Position
Office address
E-mail
Name of the Firm/Company.
Date
(Company Seal/ Rubber Stamp where applicable)
Witness
Name
Sign
Date

(d) APPENDIX 1 - FRAUD AND CORRUPTION

(Appendix 1 shall not be modified)

1. Purpose

1.1 The Government of Kenya's Anti-Corruption and Economic Crime laws and their sanction's policies and procedures, Public Procurement and Asset Disposal Act (no. 33 of 2015) and its Regulation, and any other Kenya's Acts or Regulations related to Fraud and Corruption, and similar offences, shall apply with respect to Public Procurement Processes and Contracts that are governed by the laws of Kenya.

2. Requirements

- 21 The Government of Kenya requires that all parties including Procuring Entities, Tenderers, (applicants/proposers), Consultants, Contractors and Suppliers; any Sub-contractors, Sub-consultants, Service providers or Suppliers; any Agents (whether declared or not); and any of their Personnel, involved and engaged in procurement under Kenya's Laws and Regulation, observe the highest standard of ethics during the procurement process, selection and contract execution of all contracts, and refrain from Fraud and Corruption and fully comply with Kenya's laws and Regulations as per paragraphs 1.1 above.
- 22 Kenya's public procurement and asset disposal act (no. 33 of 2015) under Section 66 describes rules to be followed and actions to be taken in dealing with Corrupt, Coercive, Obstructive, Collusive or Fraudulent practices, and Conflicts of Interest in procurement including consequences for offences committed. A few of the provisions noted below highlight Kenya's policy of no tolerance for such practices and behavior:
 - 1) A person to whom this Act applies shall not be involved in any corrupt, coercive, obstructive, collusive or fraudulent practice; or conflicts of interest in any procurement or as set disposal proceeding;
 - 2) A person referred to under subsection (1) who contravenes the provisions of that sub-section commits an offence;
 - 3) Without limiting the generality of the subsection (1) and (2), the person shall be:
 - a) disqualified from entering into a contract for a procurement or asset disposal proceeding; or
 - b) if a contract has already been entered into with the person, the contract shall be voidable;
 - 4) The voiding of a contract by the procuring entity under subsection (7) does not limit any legal remedy the procuring entity may have;
 - 5) An employee or agent of the procuring entity or a member of the Board or committee of the procuring entity whohas a conflict of interest with respect to a procurement:
 - a) Shall not take part in the procurement proceedings;
 - b) shall not, after a procurement contract has been entered in to, take part in any decision relating to the procurement or contract; and
 - c) shall not be a subcontract or for the tender to whom was awarded contract, or a member of the group of tenderers to whom the contract was awarded, but the subcontractor appointed shall meet all the requirements of this Act.
 - 6) An employee, agent or member described in subsection (1) who refrains from doing anything prohibited under that subsection, but for that subsection, would have been within his or her duties shall disclose the conflictofinteresttotheprocuringentity;
 - 7) If a person contravenes subsection (1) with respect to a conflict of interest described in subsection (5)(a) and the contract is awarded to the person or his relative or to another person in whom one of them had a direct or indirect pecuniary interest, the contract shall be terminated and all costs incurred by the public entity shall be made good by the awarding officer. Etc.
- 3. In compliance with Kenya's laws, regulations and policies mentioned above, the Procuring Entity:

- a) Defines broadly, for the purposes of the above provisions, the terms setf orth below as follows:
 - i) "corrupt practice" is the offering, giving, receiving, or soliciting, directly or indirectly, of anything of value to influence improperly the actions of another party;
 - ii) "fraudulent practice" is any act or omission, including is representation, that knowingly or recklessly misleads, or attempts to mislead, a party to obtain financial or other benefit or to avoid an obligation;
 - iii) "collusive practice" is an arrangement between two or more parties designed to achieve an improper purpose, including to influence improperly the actions of another party; "coercive practice" is impairing or harming, or threatening to impair or harm, directly or indirectly, any party or the property of the party to influence improperly the actions of a party;
 - iv) "obstructive practice" is:
 - Deliberately destroying, falsifying, altering, or concealing of evidence material to the
 investigation or making false statements to investigators in order to materially impede
 investigation by Public Procurement Regulatory Authority (PPRA) or any other appropriate
 authority appointed by Government of Kenya into allegations of a corrupt, fraudulent, coercive,
 or collusive practice; and/or threatening, harassing, or intimidating any party to prevent it from
 disclosing its knowledge of matters relevant to the investigation or from pursuing the
 investigation; or
 - acts intended to materially impede the exercise of the PPRA's or the appointed authority's inspection and audit rights provided for under paragraph 2.3 e. below.
- b) Defines more specifically, in accordance with the above procurement Act provisions set forth for fraudulent and collusive practices as follows:
 - "fraudulent practice" includes a misrepresentation of fact in order to influence a procurement or disposal processorthe exercise of a contract to the detriment of the procuring entity or the tenderer or the contractor, and includes collusive practices amongst tenderers prior to or after tender submission designed to establish tender prices at artificial non-competitive levels and to deprive the procuring entity of the benefits of free and open competition.
- c) Rejects a proposal for award of a contract if PPRA determines that the firm or individual recommended for award, any of its personnel, or its agents, or its sub-consultants, sub-contractors, service providers, suppliers and/ or their employees, has, directly or indirectly, engaged in corrupt, fraudulent, collusive, coercive, or obstructive practices in competing for the contract in question;
- d) Pursuant to the Kenya's above stated Acts and Regulations, may recommend to appropriate authority(ies) for sanctioning and debarment of a firm or individual, as applicable under the Acts and Regulations;
- Requires that a clause be included in Tender documents and Request for Proposal documents requiring(i) Tenderers (applicants/proposers), Consultants, Contractors, and Suppliers, and their Sub-contractors, Sub-consultants, Service providers, Suppliers, Agents personnel, permit the PPRA or any other appropriate authority appointed by Government of Kenya to inspect² all accounts, records and other documents relating to the procurement process, selection and/or contract execution, and to have them audited by auditors appointed by the PPRA or any other appropriate authority appointed by Government of Kenya; and
- f) Pursuant to Section 62 of the above Act, requires Applicants/Tenderers to submit along with their Applications/Tenders/Proposals a "Self-Declaration Form" as included in the procurement document declaring that they and all parties involved in the procurement process and contract execution have not engaged/will not engage in any corrupt or fraudulent practices.

¹For the avoidance of doubt, a party's in eligibility to be awarded a contract shall includee, without limitation, (i) applying for pre-qualification, expressing interest in a consultancy, and tendering, either directly or as a nominated sub-contractor, nominated consultant, nominated manufacturer or supplier, or nominated service provider, in respect of such contract, and (ii) entering into an addendum or amendment introducing a material modification to any existing contract.

² Inspections in this context usually are investigative (i.e., forensic) in nature. They involve fact-finding activities undertaken by the Investigating Authority or persons appointed by the Procuring Entity to address specific matters related to investigations/audits, suc has evaluating the veracity of an allegation of possible Fraud and Corruption, through the appropriate mechanisms. Such activity includes but is not limited to: accessing and examining a firm's or individual's financial records and information, and making copies thereof as relevant; accessing and examining any other documents, data and information (whether in hard copyor electronic format) deemed relevant for th einvestigation/audit, and making copies there of as relevant; interviewing staff and other relevant individuals; performing physical inspections and site visits; and obtaining third party verification of information.

2. FORM OF TENDER SECURITY-DEMAND BANK GUARANTEE

Beneficiary:					
	Request for Tenders No:				
Da	Date:				
TE	NDER GUARANTEE No.:				
Gu	arantor:				
1.	We have been informed that(here inafter called "the Applicant") has submitted or will submit to the Beneficiary its Tender (here inafter called" the Tender") for the execution ofunder Request for Tenders No("the ITT").				
2.	Furthermore, we understand that, according to the Beneficiary's conditions, Tenders must be supported by a Tender guarantee.				
3.	At the request of the Applicant, we, as Guarantor, hereby irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of() upon receipt by us of the Beneficiary's complying demand, supported by the Beneficiary's statement, whether in the demand itself or a separate signed document accompanying or identifying the demand, stating that either the Applicant:				
(a)) has withdrawn its Tender during the period of Tender validity set forth in the Applicant's Letter of Tender ("the Tender Validity Period"), or any extension thereto provided by the Applicant; or				
b)	having been notified of the acceptance of its Tender by the Beneficiary during the Tender Validity Period or any extension there to provided by the Applicant, (i) has failed to execute the contract agreement, or (ii) has failed to furnish the Performance.				
4.	This guarantee will expire: (a) if the Applicant is the successful Tenderer, upon our receipt of copies of the contract agreement signed by the Applicant and the Performance Security and, or (b) if the Applicant is not the successful Tenderer, upon the earlier of (i) our receipt of a copy of the Beneficiary's notification to the Applicant of the results of the Tendering process; or (ii) thirty days after the end of the Tender Validity Period.				
5.	Consequently, any demand for payment under this guarantee must be received by us at the office indicated above onor before that date.				
	[signature(s)]				

4. FORM OF TENDER SECURITY (TENDER BOND)

	[TheSuretyshallfillin this Tender Bond Form in accordance with the instructions		
	indicated.] BOND NO		
1.	BY THIS BOND [name of tenderer] as Principal (hereinafter called "the Principal"), and [name, legal title, an address of surety], authorized to transact business in [name of country of Purchaser], as Surety (hereinafter called "the Surety"), are held and firmly bound unto [name of Purchaser] as Obligee (hereinafter called "the Purchaser") in the sum of [amount of Bond][amount in words], for the payment of which sum, well and truly the be made, we, the said Principal and Surety, bind ourselves, our successors and as signs, jointly and severally firmly by these presents.		
2.	WHERE AS the Principal has submitted or will submit a written Tender to the Purchaser dated thedayon, 20, for the supply of <i>[name of Contract]</i> (herein after called the "Tender").		
3.	NOW, THEREFORE, THE CONDITION OF THIS OBLIGATION is such that if the Principal:		
	a) Has with drawn its Tender during the period of Tender validity set forth in the Principal's Letter of Tender ("the Tender Validity Period"), or any extension there to provided by the Principal; or		
	b) Having been notified of the acceptance of its Tender by the Purchaser during the Tender Validity Period or any extension there to provided by the Principal;(i) failed to execute the Contract agreement; or (ii) hasfailedtofurnish the Performance Security, in accordance with the Instructions to tenderers ("ITT") of the Purchaser's Tendering document.		
	then the Surety undertakes to immediately pay to the Purchaser up to the above amount upon receipt of the Purchaser's first written demand, without the Purchaser having to substantiate its demand, provided that in its demand the Purchaser shall state that the demand arises from the occurrence of any of the above events specifying which event (s) has occurred.		
4.	The Surety here by agrees that its obligation will remain in full force and effect upto and including the date 3 days after the date of expiration of the Tender Validity Period set forth in the Principal's Letter of Tender or an extension thereto provided by the Principal.		
5.	IN TESTIMONY WHEREOF, the Principal and the Surety have caused these presents to be executed in their respective names this day of20.		
	Principal: Surety: Corporate Seal (where appropriate)		
	(Signature) (Signature) (Printed name and title) (Printed name and title)		

4. FORM OF TENDER - SECURING DECLARATION

ſΤΊ	he Bidder shall complete this Form in accordance with the instructions indicated]	
	te:	
	nder No.:	
	:	
1.	I/We understand that, according to your conditions, bids must be supported by a Tender-Securing Declaration.	
2.	I/We accept that I/we will automatically be suspended from being eligible for tendering in any contract with the Purchaser for the period of time of [insert number of months or years] starting on [insert date], if we are in breach of ourobligation(s) under the bid conditions, because we—(a) have withdrawn our tender during the period of tender validity specified by us in the Tendering Data Sheet; or (b) having been notified of the acceptance of our Bid by the Purchaser during the period of bid validity, (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with the instructions to tenders.	
3.	 I/We understand that this Tender Securing Declaration shall expire if we are not the successful Tenderer(s), upon the earlier of: a) Our receipt of a copy of your notification of the name of the successful Tenderer; or b) thirty days after the expiration of our Tender. 	
4.	I/We understand that if Iam /we are/ in a Joint Venture, the Tender Securing Declaration must be in the name of the Joint Venture that submits the bid, and the Joint Venture has not been legally constituted at the time of bidding, the Tender Securing Declaration shall be in the names of all future partners as named in the letter of intent.	
Sig	ned:	
sol	e proprietor, etc.)	
Na	me:	
bid	for and on behalf of: [insert complete name of Tenderer]	
Da	ated on day of	

5. Appendix to Tender

Schedule of Currency requirements

Summary of currencies of the Tender for	[insert name of Section of the Works]	
Name of currency	Amounts payable	
Local currency:		
Foreign currency #1:		
Foreign currency #2:		
Foreign currency #3:		
Provisional sums expressed in local currency	[To be entered by the Procuring Entity]	



SECTION V - BILLS OF QUANTITIES

Bills of Quantities as annexed in the Tender Document

SECTION VI - SPECIFICATIONS

The specifications shall be in accordance with Ministry of Works General Specifications 1976 edition together with any amendments issued thereto.

If there is any discrepancy between the Drawings, Bills of Quantities and the General Specifications, the Project manager shall give direction

SECTION VII - DRAWINGS

DRAWING TITLE	DRAWING NO.
As issued by the Project Manager	



SECTION VIII - GENERAL CONDITIONS OF CONTRACT (GCC)

General Conditions of Contract

1. GENERAL PROVISIONS

1.1 Definitions

In this Contract, except where context otherwise requires, the following terms shall be interpreted as indicated below. Words indicating persons or parties include corporations and other legal entities, except where the context requires otherwise.

- "Accepted Contract Amount" means the amount accepted in the Letter of Acceptance for the execution and completion of the Works and the remedying of any defects.
- "Base Date" means a date 30 day prior to the submission of tenders.
- "Bill of Quantities" means the priced and completed Bill of Quantities forming part of the tender.
- "Completion Date" meansthedateofcompletionoftheWorksascertifiedbytheEngineer.
- "Contract Price" means the price defined in the contract and there after as adjusted in accordance with the provisions of the Contract.
- "Contract" means the agreement entered into between the Procuring Entity and the Contractor as recorded in the Agreement Form and signed by the parties including all attachments and appendices thereto and all documents incorporated by reference therein to execute, complete, and maintain the Works.
- "Contractor's Documents" means the calculations, computer programs and other software, progress reports, drawings, manuals, models and other documents of a technical nature (if any) supplied by the Contractor under the Contract.
- "Contractor's Equipment" means all apparatus, machinery, vehicles and other things required for the execution and completion of the Works and the remedying of any defects. However, Contractor's Equipment excludes Temporary Works, Procuring Entity's Equipment (if any), Plant, Materials and any other things intended to form or forming part of the Permanent Works.
- "Contractor's Personnel" means the Contractor's Representative and all personnel whom the Contractor utilizes on Site, who may include the staff, labor and other employees of the Contractor and of each Subcontractor; and any other personnel assisting the Contractor in the execution of the Works.
- "Contractor's Representative" means the person named by the Contractor in the Contractor appointed from time to time by the Contractor who acts on behalf of the Contractor.
- "Contractor" means the person(s) named as contractor in the Form of Tender accepted by the Procuring Entity.
- "Cost" means expenditure reasonably incurred (or to be incurred) by the Contractor, whether on or off the Site, including overhead and similar charges, but does not include profit.
- "Day" means a calendar day and "year" means 365 days.
- "Dayworks" means Work inputs subject to payment on a time basis for labour and the associated materials and plant.

- "Defect" means any part of the Works not completed in accordance with the Contract.
- "Defects Liability Certificate" means the certificate issued by Architect upon correction of defects by the Contractor.
- "Defects Liability Period" means the period named in the Special Conditions of Contract and calculated from the Completion Date, within which the contractor is liable for any defects that may develop in the handed over works.
- "Defects Notification Period" means the period for notifying defects in the Works or a Section (as the case may be) under Sub-Clause 11.1 [Completion of Outstanding Work and Remedying Defects], which extends over the days stated in the Special Conditions of Contract.
- "Drawings" means the drawings of the Works, as included in the Contract, and any additional and modified drawings issued by (or on behalf of) the Procuring Entity in accordance with the Contract.
- **"Final Payment Certificate"** means the payment certificate issued under Sub-Clause 14.13 [Issue of Final Payment Certificate].
- "Final Statement" means the statement defined in Sub-Clause 14.11 [Application for Final Payment Certificate].
- "Force Majeure" is defined in Clause19 [Force Majeure].
- **"Foreign Currency"** means a currency of another country (not Kenya) in which part (or all) of the Contract Price is payable, but not the Local Currency.
- "Goods" means Contractor's Equipment, Materials, Plant and Temporary Works, or any of them as appropriate.
- "Interim Payment Certificate" means a payment certificate issued under Clause 14 [Contract Price and Payment], other than the Final Payment Certificate.
- **"Laws"** means all national legislation, statutes, ordinances, and regulations and by-laws of any legally constituted public authority.
- "Letter of Acceptance" means the letter of formal acceptance of a tender, signed by Procuring Entity, including any annexed memoranda comprising agreements between and signed by both Parties.
- "Local Currency" means the currency of Kenya.
- "Materials" means things of all kinds (other than Plant) intended to form or forming part of the Permanent Works, including the supply-only materials (if any) to be supplied by the Contractor under the Contract.
- "Notice of Dissatisfaction" means the notice given by either Party to the other under Sub-Clause 20.3 indicating its dissatisfaction and intention to commence arbitration.
- **"Special Conditions of Contract"** means the pages completed by the Procuring Entity entitled Special Conditions of Contract which constitute Part A of the Special Conditions.
- "Party" means the Procuring Entity or the Contractor, as the context requires.
- "Payment Certificate" means a payment certificate issued under Clause 14 [Contract Price and Payment].
- "Performance Certificate" means the certificate issued under Sub-Clause 11.9 [Performance Certificate].
- "Performance Security" means the security (or securities, if any) under Sub-Clause 4.2 [Performance Security].
- "Permanent Works" means the permanent works to be executed by the Contractor under the Contract.
- "Plant" means the apparatus, machinery and other equipment intended to form or forming part of the Permanent Works, including vehicles purchased for the Procuring Entity and relating to the construction or operation of the Works.
- "Procuring Entity's Equipment" means the apparatus, machinery and vehicles (if any) made available by the

Procuring Entity for the use of the Contract or in the execution of the Works, as stated in the Specification; but does not include Plant which has not been taken over by the Procuring Entity.

- "Procuring Entity's Personnel" means the Engineer, the Engineer, the assistants and all other staff, labor and other employees of the Architect and of the Procuring Entity; and any other personnel notified to the Contractor, by the Procuring Entity or the Engineer, as Procuring Entity's Personnel.
- "Procuring Entity" means the Entity named in the Special Conditions of Contract.
- "Engineer" is the person named in the Appendix to Conditions of Contract (or any other competent person appointed by the Procuring Entity and notified to the Contractor, to act in replacement of the Engineer) who is responsible for supervising the execution of the Works and administering the Contract and shall be an "Architect" or a "Quantity Surveyor" registered under the Architects and Quantity Surveyors Act Cap 525 or an "Engineer" registered under Engineers Registration Act Cap 530.
- **"Engineer"** means the person appointed by the Procuring Entity to act as the Architect for the purposes of the Contract and named in the Special Conditions of Contract, or other person appointed from time to time by the Procuring Entity and notified to the Contractor
- **"Provisional Sum"** means a sum (if any) which is specified in the Contract as a provisional sum, for the execution of any part of the Works or for the supply of Plant, Materials or services under Sub-Clause 13.5 [Provisional Sums].
- "Retention Money" means the accumulated retention moneys which the Procuring Entity retains under Sub-Clause 14.3 [Application for Interim Payment Certificates] and pays under Sub-Clause 14.9 [Payment of Retention Money].
- "Schedules" means the document(s) entitled schedules, completed by the Contractor and submitted with the Form of Tender, as included in the Contract.
- "Section" means a part of the Works specified in the Special Conditions of Contract as a Section (if any)
- "Site Investigation Reports" are those reports that may be included in the tendering documents which a ref actual and interpretative about the surface and sub-surface condition sat the Site.
- "Site" means the places where the Permanent Works are to be executed, including storage and working areas, and to which Plant and Materials are to be delivered, and any other places as may be specified in the Contract as forming part of the Site.
- "Specification" means the document entitled specification, as included in the Contract, and any additions and modifications to the specification in accordance with the Contract. Such document specifies the Works.
- "Start Date" or "Commencement Date" is the latest date when the Contractor shall commence execution of the Works. It does not necessarily coincide with the Site possession date(s).
- "Statement" means a statement submitted by the Contractor as part of an application, under Clause 14 [Contract Price and Payment], for a payment certificate.
- "Subcontractor" means any person named in the Contract as a subcontractor, or any person appointed as a subcontractor, for a part of the Works.
- "Taking-Over Certificate" means a certificate issued under Clause 10 [Procuring Entity's Taking Over].
- "Temporary Works" means all temporary works of every kind (other than Contractor's Equipment) required on Site for the execution and completion of the Permanent Works and the remedying of any defects.
- "Temporary works" means works designed, constructed, installed, and removed by the Contractor which are needed for construction or installation of the Works.
- **"Tender"** means the Form of Tender and all other documents which the Contractor submitted with the Form of Tender, as included in the Contract.
- "Tests after Completion" means the tests (if any) which are specified in the Contract and which are carried out in

accordance with the Specification after the Works or a Section (as the case may be) are taken over by the Procuring Entity.

- "Testson Completion" means the tests which are specified in the Contractor agreed by both Parties or instructed as a Variation, and which are carried out under Clause 9 [Tests on Completion] before the Works or a Section (as the case may be) are taken over by the Procuring Entity.
- "Time for Completion" means the time for completing the Works or a Section (as the case may be) as stated in the Special Conditions of Contract (with any extension calculated from the Commencement Date.
- "Unforeseeable" means not reasonably foreseeable by an experienced contractor by the Base Date.
- "Variation" means any change to the Works, which is instructed or approved as a variation under Clause 13 [Variations and Adjustments].
- "Works" means the items the Procuring Entity requires the Contractor to undertake as defined in the Appendix to Conditions of Contract. "Works" may also mean the Permanent Works and the Temporary Works, or either of them as appropriate.

1.2 Interpretation

In the Contract, except where the context requires otherwise:

- a) Words indicating one gender include all genders;
- b) words indicating the singular also include the plural and words indicating the plural also include the singular;
- c) provisions including the word "agree", "agreed" or "agreement" require the agreement to be recorded in writing;
- d) "written" or "in writing" means hand-written, type-written, printed or electronically made, and resulting in a permanent record; and

The marginal words and other headings shall not be taken into consideration in the interpretation of these Conditions.

1.3 Communications

- 1.3.1 Wherever these Conditions provide for the giving or issuing of approvals, certificates, consents, determinations, notices, requests and discharges, these communications shall be:
 - a) In writing and delivered by hand (against receipt), sent by mail or courier, or transmitted using any of the agreed systems of electronic transmission as stated in the Special Conditions of Contract; and
 - b) delivered, sent, or transmitted to the address for the recipient's communications as stated in the Special Conditions of Contract. However:
 - i) if the recipient gives notice of another address, communications shall thereafter be delivered accordingly; and
 - ii) if the recipient has not stated otherwise when requesting an approval or consent, it may be sent to the address from which the request was issued.
- Approvals, certificates, consents and determinations shall not be unreasonably withheld or delayed. When a certificate is issued to a Party, the certifier shall send a copy to the other Party. When a notice is issued to a Party, by the other Party or the Engineer, a copy shall be sent to the Architect or the other Party, as the case may be.

1.4 Law and Language

- **1.41** The Contract shall be governed by the laws of **Kenya**.
- 1.4.2 The ruling language of the Contract shall be English.

1.5 Priority of Documents

The documents forming the Contract are to be taken as mutually explanatory of one another. For the purposes of interpretation, the priority of the documents shall be in accordance with the following sequence:

- a) The Contract Agreement,
- b) The Letter of Acceptance,
- c) The Special Conditions Part A,
- d) the Special Conditions Part B
- e) the General Conditions of Contract
- f) the Form of Tender,
- g) the Specifications and Bills of Quantities
- h) the Drawings, and
- i) the Schedules and any other documents forming part of the Contract.

If an ambiguity or discrepancy is found in the documents, the Architect shall issue any necessary clarification or instruction.

1.6 Contract Agreement

The Parties shall enter into a Contract Agreement within 14 days after the Contractor receives the Contract Agreement, unless the Special Conditions establish otherwise. The Contract Agreement shall be based upon the formannexed to the Special Conditions. The costs of stamp duties and similar charges (if any) imposed by law in connection with entry into the Contract Agreement shall be borne by the Procuring Entity.

1.7 Assignment

The Contractor shall not assign the whole or any part of the Contract or any benefit or interest in or under the Contract. However, the contractor:

- a) May as sign the whole or any part with the prior consent of the Procuring Entity, and
- b) may, as security in favor of a bank or financial institution, assign its right to moneys due, or to become due, under the Contract.

1.8 Care and Supply of Documents

- 1.8.1 The Specifications and Drawings shall be in the custody and care of the Procuring Entity. Unless otherwise stated in the Contract, two copies of the Contract and of each subsequent Drawings and Bills of Quantities shall be supplied to the Contractor, who may make or request further copies at the cost of the Contractor.
- 1.8.2 Each of the Contractor's Documents shall be in the custody and care of the Contractor, unless and until taken over bythe Procuring Entity. Unless otherwise stated in the Contract, the Contractor shall supply to the Architect two copies of each of the Contractor's Documents.
- 1.8.3 The Contractor shall keep, on the Site, a copy of the Contract, publications named in the Specification, the Contractor's Documents (if any), the Drawings and Variations and other communications given under the Contract. The Procuring Entity's Personnel shall have the right of access to all these documents at all reasonable times.
- 1.84 If a Party becomes aware of an error or defect in a document which was prepared for use in executing the Works, the Party shall promptly give notice to the other Party of such error or defect.

1.9 Timely provision of Drawings or Instructions

- 1.9.1 The Contractor shall give notice to the Architect whenever the Works are likely to be delayed or disrupted if any necessary drawing or instruction is not issued to the Contractor within a particular time, which shall be reasonable. The notice shall include details of the necessary drawing or instruction, details of why and by when it should be issued, and the nature and amount of the delay or disruption likely to be suffered if it is late.
- 1.92 If the Contractor suffers delay and/or incurs Cost as a result of a failure of the Architect to issue the notified drawing or instruction within a time which is reasonable and is specified in the notice with supporting details, the Contractor shall give a further notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and

- b) payment of any other associated costs accrued, which shall be included in the Contract Price.
- 1.93 After receiving this further notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- However, if and to the extent that the Architect failure was caused by any error or delay by the Contractor, including an error in, or delay in the submission of, any of the Contractor's Documents, the Contractor shall not be entitled to such extension of time, or costs accrued.

1.10 Procuring Entity's Use of Contractor's Documents

- 1.10.1 As agreed between the Parties, the Contractor shall retain the copyright and other intellectual property rights in the Contractor's Documents and other design documents made by (or on behalf of) the Contractor.
- 1.102 The Contractor shall be deemed (by signing the Contract) to give to the Procuring Entity a non-terminable transferable non-exclusive royalty-free license to copy, use and communicate the Contractor's Documents, including making and using modifications of them. This license shall:
 - a) apply throughout the actual or intended working life (whichever is longer) of the relevant parts of the Works,
 - b) entitle any person in proper possession of the relevant part of the Works to copy, use and communicate the Contractor's Documents for the purposes of completing, operating, maintaining, altering, adjusting, repairing and demolishing the Works, and
 - c) in the case of Contractor's Documents which are in the form of computer programs and other software, permit their use on any computer on the Site and other places as envisaged by the Contract, including replacements of any computers supplied by the Contractor.
- 1.103 The Contractor's Documents and other design documents made by (or on behalf of) the Contractor shall not, without the Contractor's consent, be used, copied or communicated to a third party by (or on behalf of) the Procuring Entity for purposes other than those permitted under Sub-Clause 1.10.2.

1.11 Contractor's Use of Procuring Entity's Documents

As agreed between the Parties, the Procuring Entity shall retain the copyright and other intellectual property rights in the Specification, the Drawings and other documents made by (or on behalf of) the Procuring Entity. The Contractor may, at his cost, copy, use, and obtain communication of these documents for the purposes of the Contract. They shall not, without the Procuring Entity's consent, be copied, used or communicated to a third party by the Contractor, except as necessary for the purposes of the Contract.

1.12 Confidential Details

- 1.12.1 The Contractor's and the Procuring Entity's Personnel shall ensure confidentiality at all times. The confidentiality shall survive termination or completion of the contract. They shall disclose all such confidential and other information as may be reasonably required in order to verify compliance with the Contract and allow its proper implementation.
- 1.122 The Contractor's and the Procuring Entity's Personnel shall also treat the details of the Contract as private and confidential, except to the extent necessary to carry out their respective obligations under the Contract or to comply with applicable Laws. Each of them shall not publish or disclose any particulars of the Works prepared by the other Party without the previous agreement of the other Party. However, the Contractor shall be permitted to disclose any publicly available information, or information otherwise required to establish his qualifications to compete for other projects.

1.13 Compliance with Laws

The Contractor shall, in performing the Contract, comply with applicable Laws. Unless otherwise stated in the Special Conditions of Contract:

a) The Procuring Entity shall have obtained (or shall obtain) the planning, zoning, building permit or similar permission for the Permanent Works, and any other permissions described in the Specifications as having been (or to be) obtained by the Procuring Entity; and the Procuring Entity shall indemnify and hold the Contractor harmless against and from the consequences of any failure to do so; and

b) the Contractor shall give all notices, pay all taxes, duties and fees, and obtain all permits, licenses and approvals, as required by the Laws in relation to the execution and completion of the Works and the remedying of any defects; and the Contractor shall indemnify and hold the Procuring Entity harmless against and from the consequences of any failure to do so, unless the Contractor is impeded to accomplish these actions and shows evidence of its diligence.

1.14 Joint and Several Liability

If the Contractor constitutes (under applicable Laws) a joint venture, consortium or other unincorporated grouping of two or more persons:

- a) These persons shall be deemed to be jointly and severally liable to the Procuring Entity for the performance of the Contract;
- b) these persons shall notify the Procuring Entity of their leader who shall have authority to bind the Contractor and each of these persons; and
- c) the Contractor shall not alter its composition or legal status without the prior consent of the Procuring Entity.

1.15 Inspections and Audit by the Procuring Entity

Pursuant to paragraph 2.2(e). of Appendix B to the General Conditions, the Contractor shall permit and shall cause its subcontractors and sub-consultants to permit, the Public Procurement Regulatory Authority, Procuring Entity and/or persons appointed or designated by the Government of Kenya to inspect the Site and/or the accounts and records relating to the procurement process, selection and/or contract execution, and to have such accounts and records audited by auditors appointed by the Procuring Entity if requested by the Procuring Entity. The Contractor's and its Subcontractors' and sub-consultants' attention is drawn to Sub-Clause 15.6 (Fraud and Corruption) which provides, inter alia, that acts intended to materially impede the exercise ofthe Procuring Entity's inspection and audit rights constitute a prohibited practice subject to contract termination (as well as to a determination of in eligibility pursuant to the Procuring Entity's prevailing sanctions procedures).

2 THE PROCURING ENTITY

2.1 Right of Access to the Site

- 21.1 The Procuring Entity shall give the Contractor right of access to, and possession of, all parts of the Site within the time (or times) stated in the **Special Conditions of Contract.** The right and possession may not be exclusive to the Contractor. If, under the Contract, the Procuring Entity is required to give (to the Contractor) possession of any foundation, structure, plant or means of access, the Procuring Entity shall do so in the time and manner stated in the Specification. However, the Procuring Entity may withhold any such right or possession until the Performance Security has been received.
- If no such time is stated in the Special Conditions of Contract, the Procuring Entity shall give the Contractor right of access to, and possession of, the Site within such times as required to enable the Contractor to proceed without disruption in accordance with the programme submitted under Sub-Clause 8.3 [Programme].
- 213 If the Contractor suffers delay and/or incurs Cost as a result of a failure by the Procuring Entity to give any such right or possession within such time, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) payment of any such Cost-plus profit, which shall be included in the Contract Price.
- 2.1.4 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- However, if and to the extent that the Procuring Entity's failure was caused by any error or delay by the Contractor, including an error in, or delay in the submission of, any of the Contractor's Documents, the Contractor shall not be entitled to such extension of time, Cost or profit.

22 Permits, Licenses or Approvals

- The Procuring Entity shall provide, at the request of the Contractor, such reasonable assistance as to allow the Contractor to obtain properly:
 - a) Copies of the Laws of Kenya which are relevant to the Contract but are not readily available, and
 - b) any permits, licenses or approvals required by the Laws of Kenya:
 - i) which the Contractor is required to obtain under Sub-Clause 1.13 [Compliance with Laws],
 - ii) for the delivery of Goods, including clearance through customs, and
 - iii) for the export of Contractor's Equipment when it is removed from the Site.

23 Procuring Entity's Personnel

The Procuring Entity shall be responsible for ensuring that the Procuring Entity's Personnel and the Procuring Entity's other contractors on the Site:

- a) co-operate with the Contractor's efforts under Sub-Clause 4.6 [Co-operation], and
- b) take actions similar to those which the Contractor is required to take under sub-paragraphs (a), (b) and (c) of Sub-Clause 4.8 [Safety Procedures] and under Sub-Clause 4.18 [Protection of the Environment].

24 Procuring Entity's Financial Arrangements

The Procuring Entity shall make and maintain all necessary financial arrangements which will enable the Procuring Entity to pay the Contract Price punctually (as estimated at that time) in accordance with Clause14 [Contract Price and Payment].

3 THE ENGINEER

3.1 Architect Duties and Authority

- 3.1.1 The Procuring Entity shall appoint the Architect who shall carry out the duties as signed to him in the Contract. The Architect staff shall include suitably qualified Assistants and other professionals who are competent to carry out these duties. The Architect Name and Address shall be provided in the **Special Conditions of Contract.**
- 3.12 The Architect shall have no authority to amend the Contract.
- 3.13 The Architect May exercise the authority attributable to the Architect as specified in or necessarily to be implied from the Contract. If the Architectis required to obtain the approval of the Procuring Entity before exercising a specified authority, the requirements shall be as stated in the Special Conditions of Contract. The Procuring Entity shall promptly inform the Contractor of any change to the authority attributed to the Engineer.
- 3.14 However, whenever the Architect exercises a specified authority for which the Procuring Entity's approvalis required, then (for the purposes of the Contract) the contractor shall require the Architect toprovideevidence of such approval before complying with the instruction.
- 3.15 Except as otherwise stated in these Conditions:
 - a) Whenever carrying out duties or exercising authority, specified in or implied by the Contract, the Architect shallbedeemedtoactfortheProcuring Entity;
 - b) the Architect has no authority to relieve either Party of any duties, obligations or responsibilities under the Contract;
 - any approval, check, certificate, consent, examination, inspection, instruction, notice, proposal, request, test, or similar act by the Architect (including absence of disapproval) shall not relieve the Contractor from any responsibility he has under the Contract, including responsibility for errors, omissions, discrepancies and non-compliances; and
 - d) any act by the Architect in response to a Contractor's request shall be notified in writing to the Contractor within 14 days of receipt.

3.1.6 The following provisions shall apply:

The Architect shall obtain the specific approval of the Procuring Entity before taking action under thefollowing Sub-Clauses of these Conditions:

- a) Sub-Clause 4.12: agreeing or determining an extension of time and/or additional cost.
- b) Sub-Clause 13.1: instructing a Variation, except;
 - i) In an emergency situation as determined by the Engineer, or
 - ii) If such a Variation would increase the Accepted Contract Amount by less than the percentage specified in the **Special Conditions of Contract.**
- c) Sub-Clause 13.3: Approving a proposal for Variation submitted by the Contractor in accordance with Sub Clause 13.1 or 13.2.
- d) Sub-Clause 13.4: Specifying the amount payable in each of the applicable three currencies.
- 3.1.7 Not withstanding the obligation, as set out above, to obtain approval, if, in the opinion of the Engineer, an emergency occurs affecting the safety of life or of the Works or of adjoining property, he may, without relieving the Contractor of any of his duties and responsibility under the Contract, instruct the Contractor to execute all such work or to do all such things as may, in the opinion of the Engineer, be necessary to abate or reduce the risk. The Contractor shall forth with comply, despite the absence of approval of the Procuring Entity, with any such instruction of the Engineer. The Architect shall determine an addition to the Contract Price, in respect of such instruction, in accordance with Clause 13 and shall notify the Contractor accordingly, with a copy to the Procuring Entity.

3.2 Delegation by the Engineer

- 32.1 The Architect may from time to time assign duties and delegate authority to assistants and may also revoke such assignment or delegation. These assistants may include a resident Engineer, and/or independent inspectors appointed to inspect and/ or test items of Plant and/or Materials. The assignment, delegation or revocation shall be in writing and shall not take effect until copies have been received by both Parties. However, unless otherwise agreed by both Parties, the Architect shall not delegate the authority to determine any matter in accordance with Sub-Clause 3.5 [Determinations].
- Each assistant, to whom duties have been assigned or authority has been delegated, shall only be authorized to issue instructions to the Contractor to the extent defined by the delegation. Any approval, check, certificate, consent, examination, inspection, instruction, notice, proposal, request, test, or similar act by an assistant, in accordance with the delegation, shall have the same effect as though the act had been an act of the Engineer. However:
 - a) Any failure to disapprove any work, Plant or Materials shall not constitute approval, and shall therefore not prejudice the right of the Architect to reject the work, Plant or Materials;
 - b) If the Contractor questions any determination or instruction of an assistant, the Contractor may refer the matter to the Engineer, who shall promptly confirm, reverse or vary the determination or instruction.

33 Instructions of the Engineer

- 33.1 The Architect may issue to the Contractor (at anytime) instructions and additional or modified Drawings which may benecessary for the execution of the Works and the remedying of any defects, all in accordance with the Contract. The Contractor shall only take instructions from the Engineer, or from an assistant to whom the appropriate authority has been delegated under Clause 3.2.1.
- The Contractor shall comply with the instructions given by the Architect or delegated assistant, on any matter related to the Contract. Whenever practicable, their instructions shall be given in writing. If the Architec tor a delegated assistant:
 - a) Gives an oral instruction,
 - b) receives a written confirmation of the instruction, from (or on behalf of) the Contractor, within two working days after giving the instruction, and

c) does not reply by issuing a written rejection and/or instruction within two working days after receiving the confirmation,

Then the confirmation shall constitute the written instruction of the Architect or delegated assistant (as the case may be).

3.4 Replacement of the Engineer

If the Procuring Entity intends to replace the Engineer, the Procuring Entity shall, in not less than 21 days before the intended ateo freplacement, give notice to the Contractor of the name, address and relevant experience of the intended person to replace the Engineer.

35 Determinations

- 35.1 Whenever these Conditions provide that the Architect shall proceed in accordance with this Sub-Clause 3.5 to agreeor determine any matter, the Architect shall consult with each Party in an endeavor to reach agreement. If agreement is not achieved, the Architect shall make a fair determination in accordance with the Contract, taking due regard of all relevant circumstances.
- 3.5.1 The Architect shall give notice to both Parties of each agree mentor determination, with supporting particulars, within 30 days from the receipt of the corresponding claim or request except when otherwise specified. Each Party shall give effect to each agreement or determination unless and until revised under Clause 20 [Claims, Disputes and Arbitration].

4 THE CONTRACTOR

4.1 Contractor's General Obligations

- 4.1.1 The Contractor shall design (to the extent specified in the Contract), execute and complete the Works in accordance with the Contract and with the Architect instructions, ands hall remedy any defects in the Works.
- 4.1.2 The Contractor shall provide the Plant and Contractor's Documents specified in the Contract, and all Contractor's Personnel, Goods, consumables and other things and services, whether of a temporary or permanent nature, required in and for this design, execution, completion and remedying of defects.
- 4.13 All equipment, material, and services to be incorporated in or required for the Works shall have their origin in any eligible source country.
- 4.14 The Contractor shall be responsible for the adequacy, stability and safety of all Site operations and of all methods of construction. Except to the extent specified in the Contract, the Contractor (i) shall be responsible for all Contractor's Documents, Temporary Works, and such design of each item of Plant and Materials as is required for the item to be in accordance with the Contract, and (ii) shall not otherwise be responsible for the designor specification of the Permanent Works.
- 4.15 The Contractor shall, whenever required by the Engineer, submit details of the arrangements and methods which the Contractor proposes to adopt for the execution of the Works. No significant alteration to these arrangements and methods shall be made without this having previously been notified to the Engineer.
- 4.1.6 If the Contract specifies that the Contractor shall design any part of the Permanent Works, then unless otherwise stated in the Special Conditions:
 - a) The Contractor shall submit to the Architect the Contractor's Documents for this part in accordance with the procedures specified in the Contract;
 - b) these Contractor's Documents shall be in accordance with the Specification and Drawings, shall be written in the language for communications defined in Sub-Clause 1.4 [Law and Language], and shall include additional information required by the Architect to add to the Drawings for co-ordination of each Party's designs;
 - c) the Contractor shall be responsible for this part and it shall, when the Works are completed, befit for such purposes for which the part is intended as are specified in the Contract; and
 - d) prior to the commencement of the Tests on Completion, the Contractor shall submit to the Architectthe "as-built" documents and, if applicable, operation and maintenance manuals in accordance with the

Specification and in sufficient detail for the Procuring Entity to operate, maintain, dismantle, reassemble, adjust and repair this part of the Works. Such part shall not be considered to be completed for the purposes of taking-over under Sub-Clause 10.1 [Taking Over of the Works and Sections] until these documents and manuals have been submitted to the Engineer.

42 Performance Security

- 421 The Contractor shall obtain (at his cost) a Performance Security for proper performance, in the amount stated in the **Special Conditions of Contract** and denominated in the currency (ies) of the Contract or in a freely convertible currency acceptable to the Procuring Entity. If an amount is not stated in the Special Conditions of Contract, this Sub-Clause shall not apply.
- The Contractor shall deliver the Performance Security to the Procuring Entity within 30 days after receiving the Notification of Award and shall send a copy to the Engineer. The Performance Security shall be issued by a reputable bank selected by the Contractor and shall be in the form annexed to the Special Conditions, as stipulated by the Procuring Entity in the Special Conditions of Contract, or in another form approved by the Procuring Entity.
- The Contractor shall ensure that the Performance Security is valid and enforceable until the Contractor has executed and completed the Works and remedied any defects. If the terms of the Performance Security specify its expiry date, and the Contractor has not become entitled to receive the Performance Certificate by the date 30 days prior to the expiry date, the Contractor shall extend the validity of the Performance Security until the Works have been completed and any defects have been remedied.
- The Procuring Entity shall not make a claim under the Performance Security, except for amounts to which the Procuring Entity is entitled under the Contract.
- The Procuring Entity shall indemnify and hold the Contractor harmless against and from all damages, losses and expenses (including legal fees and expenses) resulting from a claim under the Performance Security to the extent to which the Procuring Entity was not entitled to make the claim.
- 42.6 The Procuring Entity shall return the Performance Security to the Contractor within 14 days after receiving a copy of the Taking-Over Certificate.
- Without limitation to the provisions of the rest of this Sub-Clause, whenever the Architect determines an addition or a reduction to the Contract Price as a result of a change in cost and/ or legislation, or as a result of a Variation, amounting to more than 25 percent of the portion of the Contract Price payable in a specific currency, the Contractor shall at the Architect request promptly increase, or may decrease, as the case may be, the value of the Performance Security in that currency by an equal percentage.

43 Contractor's Representative

- 43.1 The Contractor shall appoint the Contractor's Representative and shall give him all authority necessary to act on the Contractor's behalf under the Contract. The Contractor's Representative's Name and Address shall be provided in the **Special Conditions of Contract.**
- Unless the Contractor's Representative **is named in the Contract**, the Contractor shall, prior to the Commencement Date, submit to the Architect for consent the name and particulars of the person the Contractor proposes to appoint as Contractor's Representative. If consent is with held or subsequently revoked in terms of Sub-Clause 6.9 [Contractor's Personnel], or if the appointed person fails to act as Contractor's Representative, the Contractor shall similarly submit the name and particulars of an other suitable person for such appointment.
- The Contractor shall not, without the prior consent of the Engineer, revoke the appointment of the Contractor's Representative or appoint are placement.
- 43.4 The whole time of the Contractor's Representative shall be given to directing the Contractor's performance of the Contract. If the Contractor's Representative is to be temporarily absent from the Site during the execution of the Works, a suitable replacement person shall be appointed, subject to the Architect prior consent, and the Architect shall be notified accordingly.
- The Contractor's Representative shall, on behalf of the Contractor, receive instructions under Sub-Clause 3.3 [Instructions of the Engineer].

- 43.6 The Contractor's Representative may delegate any powers, functions and authority to any competent person, and may at any time revoke the delegation. Any delegation or revocation shall not take effect until the Architect has received prior notice signed by the Contractor's Representative, naming the person and specifying the powers, functions and authority being delegated or revoked.
- 43.7 The Contractor's Representative shall be fluent in the language for communications defined in Sub-Clause 1.4 [Law and Language]. If the Contractor's Representative's delegates are not fluent in the said language, the Contractor shall make competent interpreter savailable during all working hours in a number deemed sufficient by the Engineer.

4.4 Sub-contractors

- 4.4.1 The Contractor shall not subcontract the whole of the Works. The contractor may however subcontract the works as provided in Clause 34.2.
- The Contractor shall be responsible for the acts or defaults of any Subcontractor, his agents or employees, as if theyweret heacts or defaults of the Contractor. Unless otherwise stated in the Special Conditions:
 - a) The Contractor shall not be required to obtain consent to suppliers solely of Materials, or to a subcontract for which the Subcontractor is named in the Contract;
 - b) The prior consent of the Procuring Entity shall be obtained to other proposed Subcontractors;
 - c) the Contractor shall give the Procuring Entity not less than 14 days' notice of the intended date of the commencement of each Subcontractor's work, and of the commencement of such work on the Site; and
 - d) each subcontract shall include provisions which would entitle the Procuring Entity to require the subcontract to be assigned to the Procuring Entity under Sub-Clause 4.5 [Assignment of Benefit of Subcontract] (if or when applicable) or in the event of termination under Sub-Clause 15.2 [Termination by Procuring Entity].
- The Contractor shall ensure that the requirements imposed on the Contractor by Sub-Clause 1.12 [Confidential Details] apply equally to each Subcontractor.
- 4.4.4 Wher epracticable, the Contractor shall give fair and reasonable opportunity for contractors from Kenya to be appointed as Subcontractors.

45 Assignment of Benefit of Subcontract

If a Subcontractor's obligations extend beyond the expiry date of the relevant Defects Notification Period and the Engineer, prior to this date, instructs the Contractor to assign the benefit of such obligations to the Procuring Entity, then the Contractor shall do so. Unless otherwise stated in the assignment, the Contractor shall have no liability to the Procuring Entity for the work carried out by the Subcontractor after the assignment takes effect.

4.6 Co-operation

- 4.6.1 The Contractor shall, as specified in the Contract or as instructed by the Engineer, allow appropriate opportunities for carrying out work to:
 - a) The Procuring Entity's Personnel,
 - b) Any other contractors employed by the Procuring Entity, and
 - c) The personnel of any legally constituted public authorities, who may be employed in the execution on or near the Site of any work not included in the Contract.
- Any such instruction shall constitute a Variation if and to the extent that it cause sthe Contractor to suffer delays and/ortoincur Unforeseeable Cost. Services for these personnel and other contractors may include the use of Contractor's Equipment, Temporary Works or access arrangements which are the responsibility of the Contractor.
- 463 If, under the Contract, the Procuring Entity is required to give to the Contractor possession of any foundation, structure, plant or means of access in accordance with Contractor's Documents, the Contractor shall submit such documents to the Architect in the time and manner stated in the Specification.

4.7 Setting Out of the Works

- 4.7.1 The Contractor shall set out the Works in relation to original points, lines and levels of reference specified in the Contractor notified by the Engineer. The Contractor shall be responsible for the correct positioning of all parts of the Works, and shall rectify any error in the positions, levels, dimensions or alignment of the Works.
- 4.72 The Procuring Entity shall be responsible for any errors in these specified or notified items of reference, but the Contractor shall use reasonable efforts to verify their accuracy before they are used.
- 4.73 If the Contractor suffers delay and/or incurs Cost from executing work which was necessitated by an errorin these items of reference, and an experienced contractor could not reasonably have discovered such error and avoided this delay and/ or Cost, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) payment of any such costs accrued, which shall be included in the Contract Price.
- 4.7.4 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) whether and (if so) to what extent the error could not reasonably have been discovered, and (ii) the matters described in sub-paragraphs (a) and (b) above related to thise.

4.8 Safety Procedures

The Contractor shall:

- a) Comply with all applicable safety regulations,
- b) Takec are for the safety of all persons entitled to be on the Site,
- c) Use reasonable efforts to keep the Site and Works clear of unnecessary obstruction so as to avoid danger to these persons,
- d) provide fencing, lighting, guarding and watching of the Works until completion and taking over under Clause 10 [Procuring Entity's Taking Over], and
- e) provide any Temporary Works (including roadways, footways, guards and fences) which may be necessary, because of the execution of the Works, for the use and protection of the public and of owners and occupiers of adjacent land.

49 Quality Assurance

- 49.1 The Contractor shall institute a quality assurance system to demonstrate compliance with the requirements of the Contract. The system shall be in accordance with the details stated in the Contract. The Architect shall be entitled a audit any aspect of the system.
- Details of all procedures and compliance documents shall be submitted to the Architectf or information before each design and execution stage is commenced. When any document of a technical nature is issued to the Engineer, evidence of the prior approval by the Contractor itself shall be apparent on the document itself.

Compliance with the quality assurance system shall not relieve the Contractor of any of his duties, obligations or responsibilities under the Contract.

4.10 Site Data

- 4.10.1 The Procuring Entity shall have made available to the Contractor for his information, prior to the Base Date, all relevant data in the Procuring Entity's possession on sub-surface and hydrological conditions at the Site, including environmental aspects. The Procuring Entity shall similarly make available to the Contractor all such data which come into the Procuring Entity's possession after the Base Date. The Contractor shall be responsible for interpreting all such data.
- 4.102 To the extent which was practicable (taking account of cost and time), the Contractor shall be deemed to have obtained all necessary information as to risks, contingencies and other circumstances which may influence or affect the Tender or Works. To the same extent, the Contractor shall be deemed to have inspected and examined

the Site, its surroundings, the above data and other available information, and to have been satisfied before submitting the Tender as to all relevant matters, including (without limitation):

- a) The form and nature of the Site, including sub-surface conditions,
- b) the hydrological and climatic conditions,
- c) the extent and nature of the work and Goods necessary for the execution and completion of the Works and the remedying of any defects,
- d) the Laws, procedures and labour practices of Kenya, and
- e) the Contractor's requirements for access, accommodation, facilities, personnel, power, transport, water and other services.

4.11 Sufficiency of the Accepted Contract Amount

- 4.11.1 TheContractor shall be deemed to:
 - a) Have satisfied itself as to the correctness and sufficiency of the Accepted Contract Amount, and
 - b) have based the Accepted Contract Amount on the data, interpretations, necessary information, inspections, examinations and satisfaction as to all relevant matters referred to in Sub-Clause 4.10 [Site Data].
- 4.112 Unless otherwise stated in the Contract, the Accepted Contract Amount covers all the Contractor's obligations under the Contract (including those under Provisional Sums, if any) and all things necessary for the proper execution and completion of the Works and the remedying of any defects.

4.12 Unforeseeable Physical Conditions

- 4.12.1 In this Sub-Clause, "physical conditions" means natural physical conditions and man-made and other physical obstructions and pollutants, which the Contractor encounters at the Site when executing the Works, including sub-surface and hydrological conditions but excluding climatic conditions.
- 4.12.2 If the Contractor encounters adverse physical conditions which he considers to have been Unforeseeable, the Contractor shall give notice to the Architect as soon as practicable.
- 4.123 This notice shall describe the physical conditions, so that they can be inspected by the Architect and shall set out the reasons why the Contractor considers them to be Unforeseeable. The Contractor shall continue executing the Works, using such proper and reasonable measures as are appropriate for the physical conditions, and shall comply with any instructions which the Architect may give. If an instruction constitutes a Variation, Clause 13 [Variations and Adjustments] shall apply.
- 4.12.4 If and to the extent that the Contractor encounters physical conditions which are Unforeseeable, gives such a notice, and suffers delay and/or incurs Cost due to these conditions, the Contractor shall be entitled subject to notice under Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) payment of any such Cost, which shall be included in the Contract Price.
- 4.125 Upon receiving such notice and inspecting and/or investigating these physical conditions, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) whether and (if so) to what extent these physical conditions were Unforeseeable, and (ii) the matters described in sub-paragraphs (a) and (b) above related to this extent.
- 4.126 However, before additional Cost is finally agreed or determined under sub-paragraph (ii), the Architect may also review whether other physical conditions in similar parts of the Works (if any) were more favorable than could reasonably have been foreseen when the Contractor submitted the Tender. If and to the extent that these more favorable conditions were encountered, the Architect may proceed in accordance with Sub-Clause 3.5

[Determinations] to agree or determine the reductions in Cost which were due to these conditions, which may be included (as deductions) in the Contract Price and Payment Certificates. However, the net effect of all adjustments under sub-paragraph (b) and all these reductions, for all the physical conditions encountered in similar parts of the Works, shall not result in a net reduction in the Contract Price.

4.12.7 The Architect shall take account of any evidence of the physical conditions foreseen by the Contractorwhen submitting the Tender, which shall be made available by the Contractor, but shall not be bound by the Contractor's interpretation of any such evidence.

4.13 Rights of Way and Facilities

Unless otherwise specified in the Contract the Procuring Entity shall provide effective access to and possession of the Site including special and/or temporary rights-of-way which are necessary for the Works. The Contractor shall obtain, at his risk and cost, any additional rights of way or facilities out side the Site which he may require for the purposes of the Works.

4.14 Avoidance of Interference

- 4.14.1 The Contractor shall not interfere unnecessarily or improperly with:
 - a) The convenience of the public, or
 - b) The access to and use and occupation of all roads and foot paths, irrespective of whether they are public or in the possession of the Procuring Entity or of others.
- 4.14.2 The Contractor shall indemnify and hold the Procuring Entity harmless against and from all damages, losses and expenses (including legal fees and expenses) resulting from any such unnecessary or improper interference.

4.15 Access Route

- 4.15.1 The Contractor shall be deemed to have been satisfied as to the suitability and availability of access routes to the Site at Base Date. The Contractor shall use reasonable efforts to prevent any road or bridge from being damaged by the Contractor's traffic or by the Contractor's Personnel. These efforts shall include the proper use of appropriate vehicles and routes.
- 4.15.2 Except as otherwise stated in these Conditions:
 - a) The Contractor shall (as be tween the Parties) be responsible for any maintenance which may be required for his use of access routes;
 - b) the Contractor shall provide all necessary signs or directions along access routes, and shall obtain any permission which may be required from the relevant authorities for his use of routes, signs and directions:
 - c) the Procuring Entity shall not be responsible for any claims which may arise from the use or otherwise of any access route;
 - d) the Procuring Entity does not guarantee the suitability or a vailability of particular access routes; and
 - e) Costs due to non-suitability or non-availability, for the use required by the Contractor, of access routes shall be borne by the Contractor.

4.16 Transport of Goods

Unless otherwise stated in the Special Conditions:

- a) the Contractor shall give the Architect not less than 21 days' notice of the date on which any Plant or a major item of other Goods will be delivered to the Site;
- b) the Contractor shall be responsible for packing, loading, transporting, receiving, unloading, storing and protecting all Goods and other things required for the Works; and
- c) the Contractor shall indemnify and hold the Procuring Entity harmless against and from all damages, losses and expenses (including legal fees and expenses) resulting from thetransport of Goods and shall negotiate and pay all claims arising from their transport.

4.17 Contractor's Equipment

The Contractor shall be responsible for all Contractor's Equipment. When brought on to the Site, Contractor's Equipment shall be deemed to be exclusively intended for the execution of the Works. The Contractor shall not remove from the Site any major items of Contractor's Equipment without the consent of the Engineer. However, consent shall not be required for vehicles transporting Goods or Contractor's Personnel off Site.

4.18 Protection of the Environment

- 4.18.1 The contractor shall comply with the applicable environmental laws, regulations and policies.
- 4.182 The Contractor shall take all reasonable steps to protect the environment (both on and off the Site) and to limit damage and nuisance to people and property resulting from pollution, noise and other results of his operations.
- 4.183 The Contractors hall ensure that emissions, surfaced is charges and effluent from the Contractor's activities shall not exceed the values stated in the Specification or prescribed by applicable Laws.

4.19 Electricity, Water and Gas

- 4.19.1 The Contractor shall, except as stated below, be responsible for the provision of all power, water and other services he may require for his construction activities and to the extent defined in the Specifications, for the tests
- 4.192 The Contractor shall be entitled to use for the purposes of the Works such supplies of electricity, water, gas, and other services as may be available on the Site and of which details and prices are given in the Specifications. The Contractor shall, at his risk and cost, provide any apparatus necessary for his use of these services and for measuring the quantities consumed.
- 4.193 The quantities consumed and the amounts due (at these prices) for such services shall be agreed or determined by the Architect in accordance with Sub-Clause 2.5 [Procuring Entity's Claims] and Sub-Clause 3.5 [Determinations]. The Contractor shall pay these amounts to the Procuring Entity.

4.20 Procuring Entity's Equipment and Free-Issue Materials

- 4.20.1 The Procuring Entity shall make the Procuring Entity's Equipment (if any) available for the use of the Contractor in the execution of the Works in accordance with the details, arrangements and prices stated in the Specification. Unless otherwise stated in the Specification:
 - a) The Procuring Entity shall be responsible for the Procuring Entity's Equipment, except that
 - b) the Contractor shall be responsible for each item of Procuring Entity's Equipment whilst any of the Contractor's Personnel is operating it, driving it, directing it or in possession or control of it.
- 420.1 The appropriate quantities and the amounts due (at such stated prices) for the use of Procuring Entity's Equipment shall be agreed or determined by the Architect in accordance with Sub-Clause 2.5 [Procuring Entity's Claims] and Sub-Clause 3.5 [Determinations]. The Contractor shall pay these amounts to the Procuring Entity.
- 4202 The Procuring Entity shall supply, free of charge, the "free-issue materials" (if any) in accordance with the details stated in the Specification. The Procuring Entity shall, at his risk and cost, provide these materials at the time and place specified in the Contract. The Contractor shall then visually inspect them and shall promptly give notice to the Architect of any shortage, defect or default in these materials. Unless otherwise agreed by both Parties, the Procuring Entity shall immediately rectify the notified shortage, defector default.
- 4203 After this visual inspection, the free-issue materials shall come under the care, custody and control of the Contractor. The Contractor's obligations of inspection, care, custody and control shall not relieve the Procuring Entity of liability for any shortage, defect or default not apparent from a visual inspection.

4.21 Progress Reports

- 4.21.1 Unless otherwise stated in the Special Conditions, monthly progress reports shall be prepared by the Contractor and submitted to the Architect in six copies. The first report shall cover the period up to the end of the first calendar month following the Commencement Date. Reports shall be submitted monthly thereafter, each within 7 days after the last day of the period to which it relates.
- 4212 Reporting shall continue until the Contractor has completed all work which is known to be outstanding at the completion date stated in the Taking-Over Certificate for the Works. Each report shall include:
 - a) charts and detailed descriptions of progress, including each stage of design (if any), Contractor's Documents, procurement, manufacture, delivery to Site, construction, erection and testing; and including these stages for work by each nominated Subcontractor (as defined in Clause 5 [NominatedSubcontractors]),
 - b) photographs showing the status of manufacture and of progress on the Site;
 - c) for the manufacture of each main item of Plant and Materials, the name of the manufacturer, manufacture location, percentage progress, and the actual or expected dates of:
 - i) commencement of manufacture,
 - ii) Contractor's inspections,
 - iii) tests, and
 - iv) shipment and arrival at the Site;
 - d) the details described in Sub-Clause 6.10 [Records of Contractor's Personnel and Equipment];
 - e) copies of quality assurance documents, test results and certificates of Materials;
 - f) list of notices given under Sub-Clause 2.5 [Procuring Entity's Claims] and notices given under Sub-Clause 20.1 [Contractor's Claims];
 - g) safety statistics, including details of any hazardous incidents and activities relating to environmental aspects and public relations; and
 - h) comparison so factual and planned progress, with details of any events or circumstances which may jeopardize the completion in accordance with the Contract, and the measures being (or to be) adopted to overcome delays.

4.22 Security of the Site

Unless otherwise stated in the Special Conditions:

- a) The Contractor shall be responsible for keeping unauthorized persons off the Site, and
- b) authorized persons shall be limited to the Contractor's Personnel and the Procuring Entity's Personnel; and to any other personnel notified to the Contractor, by the Procuring Entity or the Engineer, as authorized personnel of the Procuring Entity's other contractors on the Site.

4.23 Contractor's Operations on Site

- 423.1 The Contractor shall confine his operations to the Site, and to any additional areas which may be obtained by the Contractor and agreed by the Architect as additional working areas. The Contractor shall take all necessary precautions to keep Contractor's Equipment and Contractor's Personnel within the Site and these additional areas, and to keep them off adjacentl and.
- During the execution of the Works, the Contractor shall keep the Site free from all unnecessary obstruction and shall store or dispose of any Contractor's Equipment or surplus materials. The Contractor shall clear away and remove from the Site any wreckage, rubbish and Temporary Works which are no longer required.
- 4233 Upon the issue of a Taking-Over Certificate, the Contractor shall clear away and remove, from that part of the Site and Works to which the Taking-Over Certificate refers, all Contractor's Equipment, surplus material, wreckage, rubbish and Temporary Works. The Contractor shall leave that part of the Site and the Works in a clean and safe condition. However, the Contractor may retain on Site, during the Defects Notification Period, such Goods as are required for the Contractor to fulfil obligations under the Contract.

4.24 Fossils

- 424.1 All fossils, coins, articles of value or antiquity, and structures and other remains or items of geological or archaeological interest found on the Site shall be placed under the care and authority of the Procuring Entity. The Contractor shall take reasonable precautions to prevent Contractor's Personnel or other persons from removing or damaging any of these findings.
- The Contractor shall, upon discovery of any such finding, promptly give notice to the Engineer, who shall issue instructions for dealing with it. If the Contractor suffers delay and/or incurs Cost from complying with the instructions, the Contractor shall give a further notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) payment of any such Cost, which shall be included in the Contract Price.

 After receiving this further notice, the Architect shall proceed in accordance with Sub-Clause 3.5

 [Determinations] to agree or determine these matters.

5. NOMINATED SUBCONTRACTORS

5.1 Definition of "nominated Sub contractor."

In this Contract, "nominated Subcontractor" means a Subcontractor:

- a) Who is nominated by the Procuring Entity, or
- b) Contractor has nominated as a Subcontractor subject to Sub-Clause 5.2 [Objection to Notification].

52 Objection to Nomination

The Contractor shall not be under any obligation to employ a nominated Subcontractor against whom the Contractor raises reasonable objection by notice to the Procuring Entity as soon as practicable, with supporting particulars. An objection shall be deemed reasonable if it arises from (among other things) any of the following matters, unless the Procuring Entity agrees in writing to indemnify the Contractor against and from the consequences of the matter:

- a) there are reasons to believe that the Subcontractor does not have sufficient competence, resources or financial strength;
- b) the nominated Subcontractor does not accept to indemnify the Contractor against and from any negligence or misuse of Goods by the nominated Subcontractor, his agents and employees; or
- c) the nominated Subcontractor does not accept to enter into a subcontract which specifies that, for the subcontracted work (including design, if any), the nominated Subcontractor shall:
 - i) undertake to the Contractor such obligations and liabilities as will enable the Contractor to discharge hisobligations and liabilities under the Contract;
 - ii) indemnify the Contractor against and from all obligations and liabilities arising under or in connection with the Contract and from the consequences of any failure by the Subcontractor to perform these obligations or to fulfil these liabilities, and
 - iii) be paid only if and when the Contractor has received from the Procuring Entity payments for sums due under the Subcontract referred to under Sub-Clause 5.3 [Payment to nominated Subcontractors].

53 Payments to nominated Subcontractors

The Contractor shall pay to the nominated Subcontractor the amounts shown on the nominated Subcontractor's invoices approved by the Contractor which the Architect certifies to be due in accordance with the subcontract. These amounts plus other charges shall be included in the Contract Price in accordance with sub-paragraph (b) of Sub-Clause 13.5 [Provisional Sums], except as stated in Sub-Clause 5.4 [Evidence of Payments].

54 Evidence of Payments

5.4.1 Before issuing a Payment Certificate which includes an amount payable to a nominated Subcontractor, the Architect may request the Contractor to supply reasonable evidence that the nominated Subcontractor has received all amounts due in accordance with previous Payment Certificates, less applicable deductions for retention or otherwise. Unless the Contractor:

- (a) Submits this reasonable evidence to the Engineer, or
- (b) i) Satisfies the Architect in writing that the Contractor is reasonably entitled to withhold or refuse to pay these amounts, and
 - ii) Submits to the Architect reasonable evidence that the nominated Subcontractor has been notified of the Contractor's entitlement, then the Procuring Entity may (at his sole discretion) pay, direct to the nominated Subcontractor, part or all of such amounts previously certified (less applicable deductions) as are due to the nominated Subcontractor and for which the Contractor has failed to submit the evidence described in sub-paragraphs (a) or (b) above. The Contractor shall then repay, to the Procuring Entity, the amount which the nominated Subcontractor was directly paid by the Procuring Entity.

6 STAFF AND LABOR

6.1 Engagement of Staff and Labor

Except as otherwise stated in the Specification, the Contractor shall make arrangements for the engagement of all staff and labor, local or otherwise, and for their payment, feeding, transport, and, when appropriate, housing. The Contractor is encouraged, to the extent practicable and reasonable, to employ staff and labor with appropriate qualifications and experience from sources within Kenya.

6.2 Rates of Wages and Conditions of Labor

- The Contractor shall pay rates of wages, and observe conditions of labor, which are not lower than those established for the trade or industry where the work is carried out. If no established rates or conditions are applicable, the Contractor shall pay rates of wages and observe conditions which are not lower than the general level of wages and conditions observed locally by Procuring Entity's whose trade or industry is similar to that of the Contractor.
- The Contractor shall inform the Contractor's Personnel about their liability to pay personal income taxes in Kenya in respect of such of their salaries, wages, allowances and any benefits as are subject to tax under the Laws of Kenya for the time being in force, and the Contractor shall perform such duties in regard to such deductions there of as may be imposed on him by such Laws.

63 Persons in the Service of Procuring Entity

The Contractor shall not recruit, or attempt to recruit, staff and labour from amongst the Procuring Entity's Personnel.

6.4 Labor Laws

The Contractor shall comply with all the relevant labour Laws applicable to the Contractor's Personnel, including Laws relating to their employment, employment of children, health, safety, welfare, immigration and emigration, and shall allow them all their legal rights. The Contractor shall require his employees to obey all applicable Laws, including those concerning safety at work.

65 Working Hours

No work shall be carried out on the Site on locally recognized days of rest, or outside the normal working hours stated in the **Special Conditions of Contract**, unless:

- a) Otherwise stated in the Contract.
- b) The Architect gives consent, or
- c) The work is unavoidable, or necessary for the protection of life or property or for the safety of the Works, in which case the Contractor shall immediately advise the Engineer, provided that work done outside the normal working hours shall be considered and paid for as overtime.

6.6 Facilities for Staff and Labor

Except as otherwise stated in the Specification, the Contractor shall provide and maintain all necessary accommodation and welfare facilities on site for the Contractor's Personnel. The Contractor shall also provide facilities for the Procuring Entity's Personnel as stated in the Specifications. The Contractor shall not permit any of the Contractor's Personnel to maintain any temporary or permanent living quarters within the structures forming part of the Permanent Works.

6.7 Health and Safety

- 67.1 The Contractor shall at all times take all reasonable precautions to maintain the health and safety of the Contractor's Personnel. In collaboration with loca lhealth authorities, the Contractor shall ensure that medical staff, first aid facilities, sick bay and ambulance service are available at all times at the Site and at any accommodation for Contractor's and Procuring Entity's Personnel, and that suitable arrangements are made for all necessary welfare and hygiene requirements and for the prevention of epidemics.
- The Contractor shall appoint an accident prevention officer at the Site, responsible for maintaining safety and protection against accidents. This person shall be qualified for this responsibility and shall have the authority to issue instructions and take protective measures to prevent accidents. Throughout the execution of the Works, the Contractor shall provide what ever is required by this person to exercise this responsibility and authority.
- 6.73 The Contractor shall send, to the Engineer, details of any accident as soon as practicable after its occurrence. The Contractor shall maintain records and make reports concerning health, safety and welfare of persons, and damage to property, as the Architect may reasonably require.
- 6.7.4 The Contractor shall conduct an awareness programme on HIV and other sexually transmitted diseases via an approved service provider and shall undertake such other measures taken to reduce the risk of the transfer of these diseases between and among the Contractor's Personnel and the local community, to promote early diagnosis and to assist affected individuals.

68 Contractor's Superintendence

- 68.1 Throughout the execution of the Works, and as long thereafter as is necessary to fulfil the Contractor's obligations, the Contractor shall provide all necessary super intendence to plan, arrange, direct, manage, inspect and test the work.
- Superintendence shall be given by a sufficient number of persons having adequate knowledge of the language for communications (defined in Sub-Clause 1.4 [Law and Language]) and of the operations to be carried out (including the methods and techniques required, the hazards likely to be encountered and methods of preventing accidents), for the satisfactory and safe execution of the Works.

69 Contractor's Personnel

- 69.1 The Contractor's Personnel shall be appropriately qualified, skilled and experienced in their respective trades or occupations. The Contractors Key personnel shall be named in the Special Conditions of Contract. The Architect may require the Contractor to remove (or cause to be removed) any person employed on the Site or Works, including the Contractor's Representative if applicable, who:
 - a) Persists in any misconduct or lack of care,
 - b) Carries out duties in competently or negligently,
 - c) fails to conform with any provisions of the Contract,
 - d) persists in any conduct which is prejudicial to safety, health, or the protection of the environment, or
 - e) based on reasonable evidence, is determined to have engaged in Fraud and Corruption during the execution of the Works.
- 692 If appropriate, the Contractor shall then appoint (or cause to be appointed) a suitable replacement person.

6.10 Records of Contractor's Personnel and Equipment

The Contractor shall submit, to the Engineer, details showing the number of each class of Contractor's Personnel and of each type of Contractor's Equipment on the Site. Details shall be submitted each calendar month, in a form approved by the Engineer, until the Contractor has completed all work which is known to be outstanding at the completion date stated in the Taking-Over Certificate for the Works.

6.11 Disorderly Conduct

The Contractor shall at all times take all reasonable precautions to prevent any unlawful, riotous or disorderly conduct by or amongst the Contractor's Personnel, and to preserve peace and protection of persons and property on and near the Site.

6.12 Foreign Personnel

- 6.12.1 The Contractor shall not employ foreign personnel unless the contractor demonstrates that there are no Kenyans with the required skills.
- 6.12.2 The Contractor shall be responsible for the return of any foreign personnel to the place where they were recruited or to their domicile. In the event of the death in Kenya of any of these personnel or members of their families, the Contractor shall similarly be responsible for making the appropriate arrangements for their return or burial.

6.13 Supply of Water

The Contractor shall, having regard to local conditions, provide on the Site an adequate supply of drinking and other water for the use of the Contractor's Personnel.

6.14 Measures against Insect and Pest Nuisance

The Contractor shall a tall times take the necessary precautions to protect the Contractor's Personnel employed on the Site from insect and pest nuisance, and to reduce the danger to their health. The Contractor shall comply with all the regulations of the local health authorities, including use of appropriate insecticide.

6.15 Alcoholic Liquor or Drugs

The Contractor shall not, otherwise than in accordance with the Laws of Kenya, onsite, import, sell, give, barter or otherwise dispose of any alcoholic liquor or drugs, or permit or allow importation, sale, gift, barter or disposal there of by Contractor's Personnel.

6.16 Prohibition of Forced or Compulsory Labour

The Contractor shall not employ forced labor, which consists of any work or service, not voluntarily performed, that is exacted from an individual under threat of force or penalty, and includes any kind of involuntary or compulsory labor, such as indentured labor, bonded labor or similar labor-contracting arrangements.

6.17 Prohibition of Harmful Child Labor

The Contractor shall not employ children in a manner that is economically exploitative, or is likely to be hazardous, or to interfere with, the child's education, or to be harmful to the child's health or physical, mental, spiritual, moral, or social development. Where the relevant labour laws of Kenya have provisions for employment of minors, the Contractor shall follow those laws applicable to the Contractor. Children below the age of 18 years shall not be employed in dangerous work.

6.18 Employment Records of Workers

The Contractor shall keep complete and accurate records of the employment of labour at the Site. The records shall include the names, ages, genders, hours worked and wages paid to all workers. These records shall be summarized on a monthly basis and submitted to the Engineer. These records shall be included in the details to be submitted by the Contractor under Sub-Clause 6.10 [Records of Contractor's Personnel and Equipment].

6.19 Workers' Organizations

The Contractor shall comply with the relevant labor laws that recognize workers' rights to form and to join workers' organizations of their choosing without interference.

620 Non-Discrimination and Equal Opportunity

The Contractor shall base the labour employment on the principle of equal opportunity and fair treatment and shall not discriminate with respect to aspects of the employment relationship, including recruitment and hiring, compensation (including wages and benefits), working conditions and terms of employment, access to training, promotion, termination of employ mentor retirement, and discipline.

7. PLANT, MATERIALS AND WORKMANSHIP

7.1 Manner of Execution

The Contractor shall carry out the manufacture/assemble of plant, the production and manufacture of Materials, and all other execution of the Works:

- a) In the manner (if any) specified in the Contract,
- b) in a proper workman like and careful manner, in accordance with recognized good practice, and
- c) with properly equipped facilities and non-hazardous Materials, except as otherwise specified in the Contract.

7.2 Samples

The Contractor shall submit the following samples of Materials, and relevant information, to the Architect for consent prior to using the Material sin or for the Works:

- a) manufacturer's standard samples of Materials and samples specified in the Contract, all at the Contractor's cost, and
- b) additional samples instructed by the Architect as a Variation.

Each sample shall be labeled as to origin and intended use in the Works.

73 Inspection

- 73.1 The Procuring Entity's Personnel shall at all reasonable times:
 - a) Have full access to all parts of the Site and to all places from which natural Materials are being obtained, and
 - b) during production, manufacture and construction (at the Site and elsewhere), be entitled to examine, inspect, measure and test the materials and workmanship, and to check the progress of manufacture of Plant and production and manufacture of Materials.
- The Contractor shall give the Procuring Entity's Personnel full opportunity to carry out these activities, including providing access, facilities, permissions and safety equipment. No such activity shall relieve the Contractor from any obligation or responsibility.
- 733 The Contractor shall give notice to the Architect whenever any work is ready and before it is covered up, put out of sight, or packaged for storage or transport. The Architect shall then either carry out the examination, inspection, measurement or testing without unreasonable delay, or promptly give notice to the Contractor that the Architect does not require to do so. If the Contractor fails to give the notice, he shall, if and when required by the Engineer, uncover the work and there after reinstate and make good, all at the Contractor's cost.

7.4 Testing

- 7.4.1 This Sub-Clause shall apply to all tests specified in the Contract.
- Except as otherwise specified in the Contract, the Contractor shall provide all apparatus, assistance, documents and other information, electricity, equipment, fuel, consumables, instruments, labor, materials, and suitably qualified and experienced staff, as are necessary to carry out the specified tests efficiently. The Contractor shall agree, with the Engineer, the time and placef ort he specified testing of any Plant, Materials and other parts of the Works.
- 7.43 The Architect may, under Clause 13 [Variations and Adjustments], vary the location or details of specified tests, or instruct the Contractor to carry out additional tests. If these varied or additional tests show that the tested Plant, Materials or workmanship is not in accordance with the Contract, the cost of carrying out this Variation shall be borne by the Contractor, not withstanding other provisions of the Contract.
- 7.4.4 The Architect shall give the Contractor not less than 24 hours' notice of the Architect intention to attend the tests. If the Architect does not attend at the time and place agreed, the Contractor may proceed with the tests, unless otherwise instructed by the Engineer, and the tests shall then be deemed to have been made in the Architect presence.

- 7.45 If the Contractor suffers delay and/ or incurs Cost from complying with these instructions or as a result of a delay for which the Procuring Entity is responsible, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) payment of any such Cost-plus profit, which shall be included in the Contract Price.
- 7.4.6 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- 7.4.7 The Contractor shall promptly forward to the Architect duly certified reports of the tests. When the specified tests have be enpassed, the Architect shall endorse the Contractor's test certificate, or issue a certificate to him, to that effect. If the Architect has not attended the tests, he shall be deemed to have accepted the readings as accurate.

7.5 Rejection

- 75.1 If, as a result of an examination, inspection, measurement or testing, any Plant, Materials or workmanship is found to be defective or otherwise not in accordance with the Contract, the Architect may reject the Plant, Materials or workmanship by giving notice to the Contractor, with reasons. The Contractor shall then promptly make good the defect and ensure that the rejected item complies with the Contract.
- 752 If the Architect requires this Plant, Materials or workmanship to be retested, the tests shall be repeated under the same terms and conditions. If the rejection and retesting cause the Procuring Entity to incur additional costs, the Contractor shall subject to Sub-Clause 2.5 [Procuring Entity's Claims] pay these costs to the Procuring Entity.

7.6 Remedial Work

- 7.6.1 Not withstanding any previous test or certification, the Architect may instruct the Contractorto:
 - a) Remove from the Site and replace any Plant or Materials which is not in accordance with the Contract,
 - b) remove and re-execute any other work which is not in accordance with the Contract, and
 - c) execute any work which is urgently required for the safety of the Works, whether because of an accident, unforeseen able event or otherwise.
- 7.62 The Contractor shall comply with the instruction within a reasonable time, which shall be the time (if any) specified in the instruction, or immediately if urgency is specified under sub-paragraph (c).
- 7.63 If the Contractor fails to comply with the instruction, the Procuring Entity shall be entitled to employ and pay other persons to carry out the work. Except to the extent that the Contractor would have been entitled to payment for the work, the Contractor shall subject to Sub-Clause 2.5 [Procuring Entity's Claims] pay to the Procuring Entity all costs arising from this failure.
- 7.64 If the contractor repeatedly delivers defective work, the Procuring Entity may consider termination in accordance with Clause 15.

7.7 Ownership of Plant and Materials

Except as otherwise provided in the Contract, each item of Plant and Materials shall become the property of the Procuring Entity at whichever is the earlier of the following times, free from liens and other encumbrances:

- a) When it is in corporated in the Works;
- b) when the Contractor is paid the corresponding value of the Plant and Materials under Sub-Clause 8.10 [Payment for Plant and Materials in Event of Suspension].

7.8 Royalties

Unless otherwise stated in the Specification, the Contractor shall pay all royalties, rents and other payments for:

- a) Natural materials obtained from outside the Site, and
- b) the disposal of material from demolitions and excavations and of other surplus material (whether natural orman-made), except to the extent that disposal are as within the Site are specified in the Contract.

8 COMMENCEMENT, DELAYS AND SUSPENSION

8.1 Commencement of Works

- 8.1.1 Except as otherwise specified in the Special Conditions of Contract, the Commencement Date shall be the date at which the following precedent condition shave all been fulfilled and the Architect notification recording the agreement of both Parties on such fulfilment and instructing to commence the Work is received by the Contractor:
 - a) Signature of the Contract Agreement by both Parties, and if required, approval of the Contract by relevant authorities of Kenya;
 - b) except if otherwise specified in the Special Conditions of Contract, effective access to and possession of the Site given to the Contractor together with such permission(s) under (a) of Sub-Clause 1.13 [Compliance with Laws] as required for the commencement of the Works.
 - c) Receipt by the Contractor of the Advance Payment under Sub-Clause 14.2 [Advance Payment] provided that the corresponding bank guarantee has been delivered by the Contractor.
- 8.12 If the said Architect instruction is not received by the Contractor within 180 days from his receipt of the Letter of Acceptance, the Contractor shall be entitled to terminate the Contract under Sub-Clause 1 6.2 [Termination Contractor].
- 8.13 The Contractor shall commence the execution of the Works as soon as is reasonably practicable after the Commencement Date and shall then proceed with the Works with due expedition and without delay.

82 Time for Completion

The Contractor shall complete the whole of the Works, and each Section (if any), within the Time for Completion for the Works or Section (as the case may be), including:

- a) Achieving the passing of the Testson Completion, and
- b) completing all work which is stated in the Contract as being required for the Works or Section to be considered to be completed for the purposes of taking-over under Sub-Clause 10.1 [Taking Over of the Works and Sections].

83 Programme

- 83.1 The Contractor shall submit a detailed time programme to the Architect within 1 4 days after receiving the notice under Sub-Clause 8.1 [Commencement of Works]. The Contractor shall also submit a revised programme whenever the previous programme is inconsistent with actual progress or with the Contractor's obligations. Each programme shall include:
 - a) The order in which the Contractor intends to carry out the Works, including the anticipated timing of each stage of design (if any), Contractor's Documents, procurement, manufacture of Plant, delivery to Site, construction, erection and testing,
 - b) each of these stages for work by each nominated Subcontractor (as defined in Clause 5 [Nominated Subcontractors]).
 - c) the sequence and timing of inspections and tests specified in the Contract, and
 - d) a supporting report which includes:
 - i) a general description of the methods which the Contractor intends to adopt, and of the major stages, in the execution of the Works, and
 - details showing the Contractor's reasonable estimate of the number of each class of Contractor's Personnel and of each type of Contractor's Equipment, required on the Site for each major stage.
- Unless the Engineer, within 14 days after receiving a programme, gives notice to the Contractor stating the extent to which it does not comply with the Contract, the Contractor shall proceed in accordance with the programme, subject to his other obligations under the Contract. The Procuring Entity's Personnel shall be entitled to rely upon the programme when planning their activities.
- 833 The Contractor shall promptly give notice to the Architect of specific probable future events or circumstances which may adversely affect the work, increase the Contract Price or delay the execution of the Works.

If, at anytime, the Architect gives notice to the Contractor that a programme fails (to the extent stated) to comply with the Contractor to be consistent with actual progress and the Contractor's stated intentions, the Contractor shall submit a revised programme to the Architect in accordance with this Sub-Clause.

8.4 Extension of Time for Completion

- The Contractor shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to an extension of the Time for Completion if and to the extent that completion for the purposes of Sub-Clause 10.1 [Taking Over of the Works and Sections] is or will be delayed by any of the following causes:
 - a) a Variation (unless an adjustment to the Time for Completion has been agreed under Sub-Clause 13.3 [Variation Procedure]) or other substantial change in the quantity of an item of work included in the Contract,
 - b) a cause of delay giving an entitlement to extension of time under a Sub-Clause of these Conditions,
 - c) exceptionally adverse climatic conditions,
 - d) Unforeseeable shortages in the availability of personnel or Goods caused by epidemic or governmental actions, or
 - e) any delay, impediment or prevention caused by or attributable to the Procuring Entity, the Procuring Entity's Personnel, or the Procuring Entity's other contractors.
- If the Contractor considers itself to be entitled to an extension of the Time for Completion, the Contractor shall give notice to the Architect in accordance with Sub-Clause 20.1 [Contractor's Claims]. When determining each extension of time under Sub-Clause 20.1, the Architect shall review previous determinations and may increase, but shall not decrease, the total extension of time.

8.5 Delays Caused by Authorities

If the following conditions apply, namely:

- a) The Contractor has diligently followed the procedures laid down by the relevant legally constituted public authorities in Kenya,
- b) These authorities delay or disrupt the Contractor's work, and
- c) the delay or disruption was Unforeseeable, then this delay or disruption will be considered as a cause of delay under sub-paragraph (b) of Sub-Clause 8.4 [Extension of Time for Completion].

8.6 Rate of Progress

- 8.6.1 If, at anytime:
 - a) Actual progress is too slow to complete within the Time for Completion, and/or
 - b) Progress has fallen (or will fall) behind the current programme under Sub-Clause 8.3 [Programme], other than as a result of a cause listed in Sub-Clause 8.4 [Extension of Time for Completion], then the Architect may instruct the Contractor to submit, under Sub-Clause 8.3 [Programme], a revised programme and supporting report describing the revised methods which the Contractor proposes to adopt in order to expedite progress and complete within the Time for Completion.
- Unless the Architect notifies otherwise, the Contractor shall adopt these revised methods, which mayrequire increases in the working hours and/or in the numbers of Contractor's Personnel and/or Goods, at the risk and cost of the Contractor. If these revised methods cause the Procuring Entity to incur additional costs, the Contractor shall subject to notice under Sub-Clause 2.5 [Procuring Entity's Claims] pay these costs to the Procuring Entity, in addition to delay damages (if any) under Sub-Clause 8.7 below.
- Additional costs of revised methods including acceleration measures, instructed by the Architect to reduce delays resulting from causes listed under Sub-Clause 8.4 [Extension of Time for Completion] shall be paid by the Procuring Entity, without generating, however, any other additional payment benefit to the Contractor.

8.7 Delay Damages

87.1 If the Contractor fails to comply with Sub-Clause 8.2 [Time for Completion], the Contractor shall subject to notice under Sub-Clause 2.5 [Procuring Entity's Claims] pay delay damages to the Procuring Entity for this default. These delay damages shall be the sum stated in the **Special Conditions of Contract**, which shall be paid for everyday which shall elapse between the relevant Time for Completion and the date stated in the

Taking-Over Certificate. However, the total amount due under this Sub-Clause shall not exceed the maximum amount of delay damages (if any) stated in the Special Conditions of Contract.

These delay damages shall be the only damages due from the Contractor for such default, other than in the event of termination under Sub-Clause 15.2 [Termination by Procuring Entity] prior to completion of the Works. These damages shall not relieve the Contractor from his obligation to complete the Works, or from any other duties, obligations or responsibilities which he may have under the Contract.

8.8 Suspension of Work

- 88.1 The Architect may at anytime instruct the Contractor to suspend progress of part or all of the Works. During such suspension, the Contractor shall protect, store and secure such part or the Works a gainst any deterioration, loss or damage.
- The Architect may also notify the cause for the suspension. If and to the extent that the cause is notified and is the responsibility of the Contractor, the following Sub-Clauses 8.9, 8.10 and 8.11 shall not apply.

8.9 Consequences of Suspension

- 89.1 If the Contractor suffers delay and/or incurs Cost from complying with the Architect instructions under Sub-Clause 8.8 [Suspension of Work] and/or from resuming the work, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) Payment of any such Cost, which shall be included in the Contract Price.
- After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- The Contractor shall not be entitled to an extension of time for, or to payment of the Cost incurred in, making good the consequences of the Contractor's faulty design, workmanship or materials, or of the Contractor's failure to protect, store or secure in accordance with Sub-Clause 8.8 [Suspension of Work].

8.10 Payment for Plant and Materials in Event of Suspension

The Contractor shall be entitled to payment of the value (as at the date of suspension) of Plant and/ or Materials which have not been delivered to Site, if:

- a) The work on Plant or delivery of Plant and/or Materials has been suspended for more than 30 days, and
- b) the Contractor has marked the Plant and/or Materials as the Procuring Entity's property in accordance with the Architect instructions.

8.11 Prolonged Suspension

If the suspension under Sub-Clause 8.8 [Suspension of Work] has continued for more than 84 days, the Contractor may request the Architect permission to proceed. If the Architect does not give permission within 30 days after being requested to do so, the Contractor may, by giving notice to the Engineer, treat the suspension as an omission under Clause 13 [Variations and Adjustments] of the affected part of the Works. If the suspension affects the whole of the Works, the Contractor may give notice of termination under Sub-Clause 16.2 [Termination by Contractor].

8.12 Resumption of Work

After the permission or instruction to proceed is given, the Contractor and the Architect shall jointly examine the Works and the Plant and Materials affected by the suspension. The Contractor shall make good any deterioration or defect in or loss of the Works or Plant or Materials, which has occurred during the suspension after receiving from the Architect an instruction to this effect under Clause 13 [Variations and Adjustments].

9. TESTS ON COMPLETION

9.1 Contractor's Obligations

- 9.1.1 The Contractor shall carry out the Tests on Completion in accordance with this Clause and Sub-Clause 7.4 [Testing], after providing the documents in accordance with sub-paragraph (d) of Sub-Clause 4.1 [Contractor's General Obligations].
- 9.12 The Contractor shall give to the Architect not less than 21 days' notice of the date after which the Contractor will be ready to carry out each of the Tests on Completion. Unless otherwise agreed, Tests on Completion shall be carried out within 14 days after this date, on such day or days as the Architect shall instruct.
- 9.13 In considering the results of the Tests on Completion, the Architect shall make allowances for the effect of any use of the Works by the Procuring Entity on the performance or other characteristics of the Works. As soon as the Works, or a Section, have passed any Tests on Completion, the Contractor shall submit a certified report of the resultsof these Tests to the Engineer.

9.2 Delayed Tests

- 92.1 If the Tests on Completion are being unduly delayed by the Procuring Entity, Sub-Clause 7.4 [Testing] (fifth paragraph) and/ or Sub-Clause 10.3 [Interference with Tests on Completion] shall be applicable.
- 922 If the Tests on Completion are being unduly delayed by the Contractor, the Architect may by notice require the Contractor to carry out the Tests within 21 days after receiving the notice. The Contractor shall carry out the Testson such day or days within that period as the Contractor may fix and of which he shall give notice to the Engineer.
- 923 If the Contractor fails to carryout the Tests on Completion within the period of 21 days, the Procuring Entity's Personnel may proceed with the Test sat the risk and cost of the Contractor. The Tests on Completion shall then be deemed to have been carried out in the presence of the Contractor and the results of the Tests shall be accepted asaccurate.

93 Retesting of related works

If the Works, or a Section, fail to pass the Tests on Completion, Sub-Clause 7.5 [Rejection] shall apply, and the Architect or the Contractor may require the failed Tests, and Tests on Completion on any related work, to be repeated under the same terms and conditions.

9.4 Failure to Pass Tests on Completion

- 9.4.1 If the Works, or a Section, fail to pass the Tests on Completion repeated under Sub-Clause 9.3 [Retesting], the Architect shall be entitled to:
 - a) Order further repetition of Tests on Completion under Sub-Clause 9.3; or
 - b) if the failure deprives the Procuring Entity of substantially the whole benefit of the Works or Section, reject the Works or Section (as the case may be), in which event the Procuring Entity shall have the same remedies as are provided in sub-paragraph (c) of Sub-Clause 1 1.4 [Failure to Remedy Defects].

10. PROCURING ENTITY'S TAKING OVER

10.1 Taking Over of the Works and Sections

- 10.1.1 Except as stated in Sub-Clause 9.4 [Failure to Pass Tests on Completion], the Works shall be taken over by the Procuring Entity when (i) the Works have been completed in accordance with the Contract, including the matters described in Sub-Clause 8.2 [Time for Completion] and except as allowed in sub-paragraph (a) below, and (ii) a Taking-Over Certificate for the Works has been issued, or is deemed to have been issued in accordance with this Sub-Clause.
- 10.12 The Contractor may apply by notice to the Architect for a Taking-Over Certificate not earlier than 14 days before the Works will, in the Contractor's opinion, be complete and ready for taking over. If the Works are divided into Sections, the Contract or may similarly apply for a Taking-Over Certificate for each Section.

- 10.13 The Architect shall, within 30 days after receiving the Contractor's application:
 - a) Issue the Taking-Over Certificate to the Contract or, stating the date on which the Works or Section were completed in accordance with the Contract, except for any minor out standing work and defects which will not substantially affect the use of the Works or Section for their intended purpose (either until or whilst this work is completed and these defects are remedied); or
 - b) reject the application, giving reasons and specifying the work required to be done by the Contractor to enable the Taking-Over Certificate to be issued. The Contractor shall then complete this work before issuing a further notice undert his Sub-Clause.
- 10.14 If the Architect fails either to issue the Taking-Over Certificate or to reject the Contractor's application within the period of 30 days, and if the Works or Section (as the case may be) are substantially in accordance with the Contract, the Taking-Over Certificate shall be deemed to have been issued on thel ast day of that period.

10.2 Taking Over of Parts of the Works

- 102.1 The Architect may, at the sole discretion of the Procuring Entity, issue a Taking-Over Certificate for any part of the Permanent Works.
- 10.22 The Procuring Entity shall not use any part of the Works (other than as a temporary measure which is either specified in the Contract or agreed by both Parties) unless and until the Architect has issued a Taking-Over Certificate for this part. However, if the Procuring Entity does use any part of the Works before the Taking-Over Certificate is issued:
 - a) The part which is used shall be deemed to have been taken over as from the date on which it is used,
 - b) the Contractor shall cease to be liable for the care of such part as from this date, when responsibility shall pass to the Procuring Entity, and
 - c) if requested by the Contractor, the Architect shall issue a Taking-Over Certificate for this part.
- 1023 After the Architect has issued a Taking-Over Certificate for a part of the Works, the Contractor shall be given the earliest opportunity to take such steps as may be necessary to carry out any outstanding Tests on Completion. The Contractor shall carry out these Tests on Completion as soon as practicable before the expiry date of the relevant Defects Notification Period.
- If the Contractor incurs Cost as a result of the Procuring Entity taking over and/or using a part of the Works, other than such use as is specified in the Contractor agreed by the Contractor, the Contractor shall (i) give notice to the Architect and (ii) be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to payment of any such accrued costs, which shall be included in the Contract Price. After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine this accrued cost.
- If a Taking-Over Certificate has been issued for a part of the Works (other than a Section), the delay damages there after for completion of the remainder of the Works shall be reduced. Similarly, the delay damages for the remainder of the Section (if any) in which this part is included shall also be reduced. For any period of delay after the date stated in this Taking-Over Certificate, the proportional reduction in these delay damages shall be calculated as the proportion which the value of the part so certified bears to the value of the Works or Section (as the case may be) as a whole. The Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these proportions. The provisions of this paragraph shall only apply to the daily rate of delay damages under Sub-Clause 8.7 [Delay Damages] and shall not affect the maximum amount of these damages.

10.3 Interference with Tests on Completion

- 103.1 If the Contractor is prevented, for more than 14 days, from carrying out the Tests on Completion by a cause for which the Procuring Entity is responsible, the Procuring Entity shall be deemed to have taken over the Works or Section (as the case may be) on the date when the Tests on Completion would otherwise have been completed.
- 10.32 The Architect shall then issue a Taking-Over Certificate accordingly, and the Contractor shall carry out the Tests on Completion as soon as practicable, before the expiry date of the Defects Notification Period. The Architect shall require the Tests on Completion to be carried out by giving 14 days' notice and in accordance with the relevant provisions of the Contract.

- 1033 If the Contractor suffers delay and/or incurs Cost as a result of this delay in carrying out the Tests on Completion, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) payment of any such accrued costs, which shall be included in the Contract Price.
- 1034 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

104 Surfaces Requiring Reinstatement

Except as otherwise stated in a Taking-Over Certificate, a certificate for a Section or part of the Works shall not be deemed to certify completion of any ground or other surfaces requiring reinstatement.

11. DEFECTS LIABILITY

11.1 Completion of Outstanding Work and Remedying Defects

- 11.1.1 In order that the Works and Contractor's Documents, and each Section, shall be in the condition required by the Contract (fair wear and tear excepted) by the expiry date of the relevant Defects Notification Period or as soon as practicable there after, the Contractor shall:
 - a) complete any work which is outstanding on the date stated in a Taking-Over Certificate, within such reasonable time as is instructed by the Engineer, and
 - b) execute all work required to remedy defects or damage, as may be notified by (or on behalf of) the Procuring Entity on or before the expiry date of the Defects Notification Period for the Works or Section (as the case may be).
- 11.12 If a defect appears or damage occurs, the Contractor shall be notified accordingly by the Engineer.

11.2 Cost of Remedying Defects

- All work referred to in sub-paragraph (b) of Sub-Clause 11.1 [Completion of Outstanding Work and Remedying Defects] shall be executed at the risk and cost of the Contractor, if and to the extent that the work is attributable to:
 - a) Any design for which the Contractor is responsible,
 - b) Plant, Materials or workmanship not being in accordance with the Contract, or
 - c) Failure by the Contractor to comply with any other obligation.
- If and to the extent that such work is attributable to any other cause, the Contractor shall be notified promptly by (or on behalf of) the Procuring Entity, and Sub-Clause 13.3 [Variation Procedure] shall apply.

113 Extension of Defects Notification Period

- 113.1 The Procuring Entity shall be entitled subject to Sub-Clause 2.5 [Procuring Entity's Claims] to an extension of the Defects Notification Period for the Works or a Section if and to the extent that the Works, Section or a major item of Plant (as the case may be, and after taking over) cannot be used for the purposes for which they are intended by reason of a defect or by reason of damage attributable to the Contractor. However, a Defects Notification Period shall not be extended by more than two years.
- If delivery and/ or erection of Plant and/ or Materials was suspended under Sub-Clause 8.8 [Suspension of Work] or Sub-Clause 16.1 [Contractor's Entitlement to Suspend Work], the Contractor's obligations under this Clause shall not apply to any defectsor damage occurring more than two years after the Defects Notification Period for the Plant and/ or Materials would otherwise have expired.

114 Failure to Remedy Defects

114.1 If the Contractor fails to remedy any defect or damage within a reasonable time, a date may be fixed by the Engineer, on or by which the defect or damage is to be remedied. The Contractor shall be given reasonable notice of this date.

- 11.42 If the Contractor fails to remedy the defect or damage by this notified date and this remedial work was to be executed at the cost of the Contractor under Sub-Clause 11.2 [Costo f Remedying Defects], the Procuring Entity may (at his option):
 - (a) Carry out the work itself or by others, in a reasonable manner and at the Contractor's cost, but the Contractor shall have no responsibility for this work; and the Contractor shall subject to Sub-Clause 2.5 [Procuring Entity's Claims] pay to the Procuring Entity the costs reasonably incurred by the Procuring Entity in remedying the defect or damage;
 - (b) Require the Architect to agree or determine a reasonable reduction in the Contract Price in accordance with Sub-Clause 3.5 [Determinations]; or
 - (c) if the defect or damage deprives the Procuring Entity of substantially the whole benefit of the Works or any major part of the Works, terminate the Contractas a whole, or in respect of such major part which cannot be put to the intended use. Without prejudice to any other rights, under the Contractor otherwise, the Procuring Entity shall then be entitled to recover all sums paid for the Works or for such part (as the case may be), plus financing costs and the cost of dismantling the same, clearing the Site and returning Plant and Materials to the Contractor.

11.5 Removal of Defective Work

If the defector damage cannot be remedied expeditiously on the Site and the Procuring Entity gives consent, the Contractor may remove from the Site for the purposes of repair such items of Plant as are defective or damaged. This consent may require the Contractor to increase the amount of the Performance Security by the full replacement cost of these items, or to provide other appropriate security.

11.6 Further Tests

- 11.6.1 If the work of remedying of any defector damage may affect the performance of the Works, the Architect may require the repetition of any of the tests described in the Contract. The requirement shall be made by notice within 14 days after the defect or damage is remedied.
- These tests shall be carried out in accordance with the terms applicable to the previous tests, except that they shall be carried out at the risk and cost of the Party liable, under Sub-Clause 11.2 [Cost of Remedying Defects], for the cost of the remedial work.

11.7 Right of Access

Unti Ithe Completion Certificate has been issued, the Contractor shall have such right of access to the Works as is reasonably required in order to comply with this Clause, except as may be inconsistent with the Procuring Entity's reasonable security restrictions.

118 Contractor to Search

The Contractor shall, if required by the Engineer, search for the cause of any defecton parts of the works that have already accepted, under the direction of the Engineer. Unless the defect is to be remedied at the cost of the Contractor under Sub-Clause 11.2 [Cost of Remedying Defects], the Cost of the search plus profit shall be agreed or determined by the Architect in accordance with Sub-Clause 3.5 [Determinations] and shall be included in the Contract Price.

11.9 Completion Certificate

- 119.1 Performance of the Contractor's obligations shall not be considered to have been completed until the Architect has issued the Completion Certificate to the Contractor, stating the date on which the Contractor completed his obligations under the Contract.
- The Architect shall issue the Completion Certificate within 30days after the latest of the expiry dates of the Defects Liability Period, or as soon there after as the Contractor has supplied all the Contractor's Documents and completed and tested all the Works, including remedying any defects. A copy of the Completionn Certificate shall be issued to the Procuring Entity.
- 1193 Only the Completion Certificate shall be deemed to constitute acceptance of the Works.

11.10 Unfulfilled Obligations

After the Completion Certificate has been issued, each Party shall remain liable for the fulfilment of any obligation which remains unperformed at that time. For the purposes of determining the nature and extent of unperformed obligations, the Contract shall be deemed to remain in force.

11.11 Clearance of Site

- 11.11.1 Upon receiving the Completion Certificate, the Contractor shall remove any remaining Contractor's Equipment, surplus material, wreckage, rubbish and Temporary Works from the Site.
- 11.112 If all these items have not been removed within 30 days after receipt by the Contractor of the Completion Certificate, the Procuring Entity may sell or otherwise dispose of any remaining items. The Procuring Entity shall be entitled to be paid the costs incurred in connection with, or attributable to, such sale or disposal and restoring the Site.
- 11.113 Any balance of the moneys from the sale shall be paid to the Contractor. If these moneys are less than the Procuring Entity's costs, the Contractor shall pay the outstanding balance to the Procuring Entity.

12 MEASUREMENT AN DEVALUATION

12.1 Works to be Measured

- 12.1.1 The Works shall be measured, and valued for payment, in accordance with this Clause. The Contractor shall show in each application under Sub-Clauses 14.3 [Application for Interim Payment Certificates], 14.10 [Statement on Completion] and 14.11 [Application for Final Payment Certificate] the quantities and other particulars detailing the amounts which he considers to be entitled under the Contract.
- Whenever the Architect requires any part of the Works to be measured, reasonable notice shall be given to the Contractor's Representative, who shall:
 - a) promptly either attend or send another qualified representative to assist the Architect in making the measurement, and
 - b) supply any particulars requested by the Engineer.
- 12.13 If the Contractor fails to attend or send a representative, the measurement made by the Architect shall be accepted as accurate.
- 12.14 Except as otherwise stated in the Contract, wherever any Permanent Works are to be measured from records, these shall be prepared by the Engineer. The Contractor shall, as and when requested, attend to examine and agreet her ecords with the Engineer, and shall sign the same when agreed. If the Contractor does not attend, the records shall be accepted as accurate.
- 12.15 If the Contractor examines and disagrees the records, and/ or does not sign them as agreed, then the Contractor shall give notice to the Architect of the respects in which the records are asserted to be inaccurate. After receiving this notice, the Architect shall review the records and either confirm or vary them and certify the paymentofthe undisputed part. If the Contractor does not so give notice to the Architect within 14 days after being requested to examine the records, they shall be accepted as accurate.

12.2 Method of Measurement

Except as otherwise stated in the Contract:

- a) Measurement shall be made of the net actual quantity of each item of the Permanent Works, and
- b) the method of measurement shall be in accordance with the Bill of Quantities or other applicable Schedules.

123 Evaluation

Except as otherwise stated in the Contract, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine the value of work done by evaluating each item of work, applying the measurement agreed or determined in accordance with the above Sub-Clauses 12.1 and 12.2 and the appropriate rate or price for the item.

- For each item of work, the appropriate rate or price for the item shall be the rate or price specified for such item in the Contractor, if there is no such item, specified for similar work.
- Any item of work included in the Bill of Quantities for which no rate or price was specified shall be considered as included in other rates and prices in the Bill of Quantities and will not be paid for separately.
- However, for a new item of work, a new rate or price shall be appropriate for such item of work if:
 - a) The work is instructed under Clause 13 [Variations and Adjustments],
 - b) no rate or price is specified in the Contract for this item, and
 - c) no specified rate or price is appropriate because the item of work is not of similar character, or is not executed under similar conditions, as any item in the Contract.
- Each new rate or price shall be derived from any relevant rates or prices in the Contract. If no rates or prices are relevant for the new item of work, it shall be derived from the reasonable Cost of executing such work, prevailing market rates, together with profit, taking account of any other relevant matters.
- 123.6 Until such time as an appropriate rate or price is agreed or determined, the Architect shall determine a provisional rate or price for the purposes of Interim Payment Certificates as soon as the concerned work commences.
- 123.7 Where the contract price is different from the corrected tender price, in order to ensure the contractor is not paid less or more relative to the contract price (*which would be the tender price*), payment valuation certificates and variation orders on omissions and additions valued based on rates in the Bill of Quantities or schedule of rates in the Tender, will be adjusted by a <u>plus or minus</u> percentage. The percentage already worked out during tender evaluation is worked out as follows: (*corrected tender price tender price*)/ *tender price X* 100.

124 Omissions

Whenever the omission of any work forms part (or all) of a Variation, the value of which has not been agreed, if:

- a) The Contractor will incur (or has incurred) cost which, if the work had not been omitted, would have been deemed to be covered by a sum forming part of the Accepted Contract Amount;
- b) The omission of the work will result (or has resulted) in this sum not forming part of the Contract Price; and
- c) this cost is not deemed to be included in the evaluation of any substituted work; then the Contractor shall give notice to the Architect accordingly, with supporting particulars. Upon receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine this cost, which shall be included in the Contract Price.

13. VARIATIONS AND ADJUSTMENTS

131. Right to Vary

- 13.1.1 Variations may be initiated by the Architect at any time prior to issuing the Taking-Over Certificate for the Works, either by an instruction or by a request for the Contractor to submit a proposal. No Variation instructed by the Architect under this Clause shall in any way vitiate or in validate the Contract.
- 13.12 The Contractor shall execute and be bound by each Variation, unless the Contractor promptly gives notice to the Architect stating (with supporting particulars) that (i) the Contractor cannot readily obtain the Goods required for the Variation, or (ii) such Variation triggers a substantial change in the sequence or progress of the Works. Upon receiving this notice, the Architect shall cancel, confirm or vary the instruction.
- 13.13 Each Variation may include:
 - a) changes to the quantities of any item of work included in the Contract (however, such changes do not necessarily constitute a Variation),
 - b) changes to the quality and otherc haracteristics of any item of work,
 - c) changes to the levels, positions and/or dimensions of any part of the Works,
 - d) omission of any work unless it is to be carried out by others,
 - e) any additional work, Plant, Materials or services necessary for the Permanent Works, including any associated Tests on Completion, boreholes and other testing and exploratory work, or
 - f) changes to the sequence or timing of the execution of the Works.

13.14 The Contractor shall not make any alteration and/or modification of the Permanent Works, unless and until the Architect instructs after obtaining approval of the Procuring Entity.

132. Variation Order Procedure

- Priortoany Variation Order under Sub-Clause 13.1.4 the Architect shall notify the Contractor of the nature and form of such variation. As soon as possible after having received such notice, the Contractor shall submit to the Engineer:
 - a) A description of work, if any, to be performed and a programme for its execution, and
 - b) the Contractor's proposals for any necessary modifications to the Programme according to Sub-Clause 8.3 or to any of the Contractor's obligations under the Contract, and
 - c) the Contractor's proposals for adjustment to the Contract Price.

Following the receipt of the Contractor's submission the Architect shall, after due consultation with the Employer and the Contractor, decide as soon as possible whether or not the variation shall be carried out. If the Architect decides that the variation shall be carried out, he shall issue a Variation Order clearly identified as such in accordance with the Contractor's submission or as modified by agreement.

If the Architect and the Contractor are unable to agree the adjustment of the Contract Price, the provisions of Sub-Clause 13.2.2 shall apply.

1322 Disagreement on Adjustment of the Contract Price

If the Contractor and the Architecture unable to agree on the adjustment of the Contract Price, the adjustment shall be determined in accordance with the rates specified in the Bills of Quantities or Schedule of Daywork Prices. If the rates contained in the Bills of Quantities or Dayworks Prices are not directly applicable to the specific work in question, suitable rates shall be established by the Architect reflecting the level of pricing in the Dayworks Prices. Where rates are not contained in the said Prices, the amount shall be such as is in all the circumstances reasonable, reflecting a market price. Due account shall be taken of any over-or underrecovery of overheads by the Contractor in consequence of the variation. The Contractor shall also be entitled to be paid:

- a) The cost of any partial execution of the Work srendered useless by any such variation,
- b) The cost of making necessary alterations to Plant already manufactured or in the course of manufacture or of any work done that has to be altered in consequence of such a variation,
- c) any additional costs incurred by the Contractor by the disruption of the progress of the Works as detailed in the Programme, and
- d) the net effect of the Contractor's financec osts, including interest, caused by the variation.

The Architect shall on this basis determine the rates or prices to enable on-account payment to be included in certificates of payment.

1323 Contractor to Proceed

On receipt of a Variation Order, the Contractor shall forth with proceed to carry out the variation and be bound to these Conditions in so doing as if such variation was stated in the Contract. The work shall not be delayed pending the granting of an extension of the Time for Completion or an adjustment to the Contract Price under Sub-Clause31.3.

133 Value Engineering

- 13.3.1 TheContractor may, at anytime, submit to the Architect written proposal which (in the Contractor's opinion) will, if adopted, (i) accelerate completion, (ii) reduce the cost to the Procuring Entity of executing, maintaining or operating the Works, (iii) improve the efficiency or value to the Procuring Entity of the completed Works, or
 - (iv) otherwise be of benefit to the Procuring Entity.
- 13.3.2 The proposal shall be prepared at the cost of the Contractor and shall include the items listed in Sub-Clause 13.3 [Variation Procedure].
- 1323 If a proposal, which is approved by the Engineer, includes a change in the design of part of the Permanent Works, then unless otherwise agreed by both Parties:
 - a) The Contractor shall design this part,

- b) sub-paragraphs (a) to (d) of Sub-Clause 4.1 [Contractor's General Obligations] shall apply, and
- c) if this change results in a reduction in the contract value of this part, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine a fee, which shall be included in the Contract Price. This fee shall behalf (50%) of the difference between the following amounts:
 - such reduction in contract value, resulting from the change, excluding adjustments under Sub-Clause 13.8 [Adjustments for Changes in Legislation] and Sub-Clause 13.8 [Adjustments for Changes in Cost], and
 - ii) the reduction (if any) in the value to the Procuring Entity of the varied works, taking account of any improvement in quality, anticipated life or operational efficiencies.
- 13.3.4 However, if the amount established in item 13.2.3 (c) (i) is less than amount established in item 13.2.3 (c) (ii), there shall not be a fee. However, if the if the amount established in item 13.2.3 (c) (i) is more than amount established in item 13.2.3 (c) (ii), it shall result in a price variation to the Procuring Entity.

134 Variation Procedure for Value Engineering proposal

- 134.1 If the Architect requests a proposal, prior to instructing a Variation, the Contractor shall respond in writinga s soon as practicable, either by giving reasons why he cannot comply (if this is the case) or by submitting:
 - a) A description of the proposed work to be performed and a programme for its execution,
 - b) the Contractor's proposal for any necessary modifications to the programme according to Sub-Clause 8.3 [Programme] and to the Time for Completion, and
 - c) the Contractor's proposal for evaluation of the Variation.
- 13.4.2 The Architect shall, as soon as practicable after receiving such proposal (under Sub-Clause 13.2 [Value Project Engineering] or otherwise), respond with approval, disapproval or comments. The Contractor shall not delay any work whilst a waiting a response.
- Each instruction to execute a Variation, with any requirements for the recording of Costs, shall be issued by the Architect to the Contractor, who shall acknowledge receipt.
- Each Variation shall be evaluated in accordance with Clause 12 [Measurement and Evaluation], unless the Architect instructs or approves otherwise in accordance with this Clause.

135 Payment in Applicable Currencies

If the Contract provides for payment of the Contract Price in more than one currency, then whenever an adjustment is agreed, approved or determined as stated above, the amount payable in each of the applicable currencies shall be specified. For this purpose, reference shall be made to the actual or expected currency proportions of the Cost of the varied work, and to the proportions of various currencies specified for payment of the Contract Price.

136 Provisional Sums

- 13.6.1 Each Provisional Sum shall only be used, in whole or inpart, in accordance with the Architect instructions, and the Contract Price shall be adjusted accordingly. The total sum paid to the Contractor shall include only such amounts, for the work, supplies or services to which the Provisional Sum relates, as the Architect shall have instructed. For each Provisional Sum, the Architect May instruct:
 - a) Work to be executed (including Plant, Materials or services to be supplied) by the Contractor and valued under Sub-Clause 13.3 [Variation Procedure]; and/or
 - b) Plant, Materials or services to be purchased by the Contractor, from a nominated Subcontractor (as defined in Clause 5 [Nominated Subcontractors]) or otherwise; and for which there shall be included in the Contract Price:
 - i) The actual amounts paid (or due to be paid) by the Contractor, and
 - ii) a sum for overhead charges and profit, calculated as a percentage of these actual amounts by applying the relevant percentage rate (if any) stated in the appropriate Schedule. If there is no such rate, the percentage rate stated in **the Special Conditions of Contract** shall be applied.
- 13.62 The Contractor shall, when required by the Engineer, produce quotations, invoices, vouchers and accounts or receipts in substantiation.

137 Dayworks

- 13.7.1 For work of a minor or incidental nature, the Architect may instruct that a Variation shall be executed on a daywork basis. The work shall then be valued in accordance with the Daywork Schedule included in the Contract, and the following procedure shall apply. If a Daywork Schedule is not included in the Contract, this Sub-Clause shall not apply.
- Before ordering Goods for the work, the Contractor shall submit quotations to the Engineer. When applying for payment, the Contractor shall submit invoices, vouchers and accounts or receipts for any Goods.
- 13.73 Except for any items for which the Daywork Schedule specifies that payment is not due, the Contractor shall delive reach day to the Architect accurate statements induplicate which shall include the following details of the resources used in executing the previous day's work:
 - a) The names, occupations and time of Contractor's Personnel,
 - b) the identification, type and time of Contractor's Equipment and Temporary Works, and
 - c) the quantities and types of Plant and Materials used.
- One copy of each statement will, if correct, or when agreed, be signed by the Architect and returned to the Contractor. The Contractor shall then submit priced statements of these resources to the Engineer, prior to their inclusion in the next Statement under Sub-Clause 14.3 [Application for Interim Payment Certificates].

138 Adjustments for Changes in Legislation

- 13.8.1 The Contract Price shall be adjusted to take account of any increase or decrease in Cost resulting from a change in the Laws of Kenya (including the introduction of new Laws and the repeal or modification of existing Laws) or in the judicial or official governmental interpretation of such Laws, made after the Base Date, which affect the Contractor in the performance of obligations under the Contract.
- 13.82 If the Contractor suffers (or will suffer) delay and/or incurs (or will incur) additional Cost as a result of these changes in the Laws or in such interpretations, made after the Base Date, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
 - a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
 - b) payment of any such Cost, which shall be included in the Contract Price.
- 13.83 After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.
- Not withstanding the foregoing, the Contractor shall not be entitled to an extension of time if the relevant delay has already been taken into account in the determination of a previous extension of time and such Cost shall not be separately paid if the same shall already have been taken into account in the indexing of any inputs to the table of adjustment data in accordance with the provisions of Sub-Clause 13.8 [Adjustments for Changes in Cost].

139 Adjustments for Changes in Cost

- 139.1 In this Sub-Clause, "table of adjustment data" means the completed table of adjustment data for local and foreign currencies included in the Schedules. If there is no such table of adjustment data, this Sub-Clause shall not apply.
- 1392 If this Sub-Clause applies, the amounts payable to the Contractor shall be adjusted for rises or falls in the cost of labor, Goods and other inputs to the Works, by the addition or deduction of the amounts determined by the formulae prescribed in this Sub-Clause. To the extent that full compensation for any rise or fall in Costs is not covered by the provisions of this or other Clauses, the Accepted Contract Amount shall be deemed to have included amounts to cover the contingency of other rises and falls in costs.
- 1393 The adjustment to be applied to the amount otherwise payable to the Contractor, as valued in accordance with the appropriate Schedule and certified in Payment Certificates, shall be determined from formulae for each of the currencies in which the Contract Price is payable. No adjustment is to be applied to work valued on the basis of Cost or current prices. The formulae shall be of the following general type:

Price Adjustment Formula

Prices shall be adjusted for fluctuations in the cost of inputs only if **provided for in the SCC.** If so provided, the amounts certified in each payment certificate, before deducting for Advance Payment, shall be adjusted by applying the respective price adjustment factor to the payment amounts due in each currency. A separate formula of the type specified below applies:

P = A + B Im/Io

where:

P is the adjustment factor for the portion of the Contract Price payable.

A and **B** are coefficients **specified in the SCC**, representing then on adjustable and adjustable portions, respectively, of the Contract Price payable and

Im is the index prevailing at the end of the month being invoiced and **Io**c is the index prevailing 30 days before Bid opening for inputs payable.

NOTE: The sum of the two coefficients A and B should be 1 (one) in the formula for each currency. Normally, both coefficients shall be the same in the formulae for all currencies, since coefficient A, for the non adjustable portion of the payments, is a very approximate figure (usually 0.15) to take account of fixed cost elements or other nonadjustable components. The sum of the adjustments for each currency are added to the Contract Price.

- 139.4 The cost indices or reference prices stated in the table of adjustment data shall be used. If their source is in doubt, itshall be determined by the Engineer. Forth is purpose, reference shall be made to the values of the indices at stated dates (quoted in the fourth and fifth columns respectively of the table) for the purposes of clarification of the source; although these dates (and thus these values) may not correspond to the base cost indices.
- Incases where the "currency of index" is not the relevant currency of payment, each index shall be converted into the relevant currency of payment at the selling rate, established by the Central Bank of Kenya, of this relevant currency on the above date for which the index is required to be applicable.
- Until such time as each current cost index is available, the Architect shall determine a provisional index for the issue of Interim Payment Certificates. When a current cost index is available, the adjustment shall be recalculated accordingly.
- 13.9.7 If the Contractor fails to complete the Works within the Time for Completion, adjustment of prices there after shall be made using either (i) each index or price applicable on the date 49 days prior to the expiry of the Time for Completion of the Works, or (ii) the current index or price, whichever is more favorable to the Procuring Entity.
- The weightings (coefficients) for each of the factors of cost stated in the table(s) of adjustment data shall only be adjusted if they have been rendered unreasonable, unbalanced or in applicable, as a result of Variations.

14. CONTRACT PRICE AND PAYMENT

14.1 The Contract Price

- 14.1.1 Unless otherwise stated in the Special Conditions:
 - a) The value of the payment certificate shall be agreed or determined under Sub-Clause 12.3 [Evaluation] and be subject to adjustments in accordance with the Contract;
 - b) the Contractor shall pay all taxes, duties and fees required to be paid by him under the Contract, and the Contract Price shall not be adjusted for any of these costs except as stated in Sub-Clause 13.7 [Adjustments for Changes in Legislation];
 - c) any quantities which may be set out in the Bill of Quantities or other Schedule are estimated quantities and are not to be taken as the actual and correct quantities:

- i) of the Works which the Contractor is required to execute, or
- ii) for the purposes of Clause 12 [Measurement and Evaluation]; and
- d) the Contractor shall submit to the Engineer, within 30 days after the Commencement Date, a proposed breakdown of each lump sum price in the Schedules. The Architect may take account of the break down when preparing Payment Certificates but shall not be bound by it.
- 14.12 Notwithstanding the provisions of subparagraph (b), Contractor's Equipment, including essential spare parts there for, imported by the Contractor for the sole purpose of executing the Contract shall not be exempt from the payment of import duties and taxes upon importation.

14.2 Advance Payment

- 14.2.1 The Procuring Entity shall make an advance payment, as an interest-free loan for mobilization and cashflow support, when the Contractor submits a guarantee in accordance with this Clause. The total advance payment, the number and timing of instalments (if more than one), and the applicable currencies and proportions, shall be as stated in the **Special Conditions of Contract.**
- Unless and until the Procuring Entity receives this guarantee, or if the total advance payment is not stated in the Special Conditions of Contract, this Sub-Clause shall not apply.
- 14.23 The Architect shall deliver to the Procuring Entity and to the Contractor an Interim Payment Certificate for the advance payment or its first instalment after receiving a Statement (under Sub-Clause 14.3 [Application for Interim Payment Certificates]) and after the Procuring Entity receives (i) the Performance Security in accordance with Sub-Clause 4.2 [Performance Security] and (ii) a guarantee in amounts and currencies equal to the a dvance payment. This guarantee shall be issued by a reputable bank or financial institutions elected by the Contractor and shall be in the form annexed to the Special Conditions or in another form approved by the Procuring Entity.
- The Contractor shall ensure that the guarantee is valid and enforceable until the advance payment has been repaid, but its amount shall be progressively reduced by the amount repaid by the Contractor as indicated in the Payment Certificates. If the terms of the guarantee specify its expiry date, and the advance payment has not been repaid by the date 30 days prior to the expiry date, the Contractor shall extend the validity of the guarantee until the advance payment has been repaid.
- Unless stated otherwise in **the Special Conditions of Contract**, the advance payment shall be repaid through percentage deductions from the interim payments determined by the Architect in accordance with Sub-Clause 14.6 [Issue of Interim Payment Certificates], as follows:
 - a) Deductions shall commence in the next interim Payment Certificate following that in which the total of all certified interim payments (excluding the advance payment and deductions and repayments of retention) exceeds 30 percent (30%) of the Accepted Contract Amount less Provisional Sums; and
 - b) deductions shall be made at the amortization rate stated in the **Special Conditions of Contract** of the amount of each Interim Payment Certificate (excluding the advance payment and deductions for its repayments as well as deductions for retention money) in the currencies and proportions of the advance payment until such time as the advance payment has been repaid; provided that the advance payment shall be completely repaid prior to the time when 90 percent (90%) of the Accepted Contract Amount less Provisional Sums has been certified for payment.
- 14.2.6 If the advance payment has not been repaid prior to the issue of the Taking-Over Certificate for the Works or prior to termination under Clause 15 [Termination by Procuring Entity], Clause 16 [Suspension and Termination by Contractor] or Clause 19 [Force Majeure] (as thec ase may be), the whole of the balance then outstanding shall immediately become due and in case of termination under Clause 15 [Termination by Procuring Entity], except for Sub-Clause 14.2.7 [Procuring Entity's Entitlement to Termination for Convenience], payable by the Contractor to the Procuring Entity.

143 Application for Interim Payment Certificates

- 143.1 The Contractor shall submit a Statement (in number of copies indicated in the **Special Conditions of Contract**) to the Architect after the end of each month, in a form approved by the Engineer, showing in detail the amounts to which the Contractor considers itself to be entitled, together with supporting documents which shall include the report on the progress during this month in accordance with Sub-Clause4.21 [Progress Reports].
- 14.32 The Statement shall include the following items, as applicable, which shall be expressed in the various currencies in which the Contract Price is payable, in the sequence listed:
 - a) the estimated contract value of the Works executed and the Contractor's Documents produced up to the end of the month (including Variations but excluding items described in sub-paragraphs (b) to (g) below);
 - b) any amounts to be added and deducted for changes in legislation and changes in cost, in accordance with Sub-Clause 13.7 [Adjustments for Changes in Legislation] and Sub-Clause 13.8 [Adjustments for Changes in Cost];
 - c) any amount to be deducted for retention, calculated by applying the percentage of retention stated in the Special Conditions of Contract to the total of the above amounts, until the amount so retained by the Procuring Entity reaches the limit of Retention Money (if any) stated in the Special Conditions of Contract;
 - d) any amounts to be added for the advance payment and (if more than one instalment) and to be deducted for its repayments in accordance with Sub-Clause 14.2 [Advance Payment];
 - e) any amounts to be added and deducted for Plant and Materials in accordance with Sub-Clause 14.5 [Plant and Materials intended for the Works];
 - f) any other additions or deductions which may have become due under the Contractor otherwise, including those under Clause 20 [Claims, Disputes and Arbitration]; and
 - g) the deduction of amounts certified in all previous Payment Certificates.

144 Schedule of Payments

- 14.4.1 I fthe Contract includes a schedule of payments specifying the instalments in which the Contract Price will be paid, then unless otherwise stated in this schedule:
 - a) The instalments quoted in this schedule of payments shall be the estimated contract values for the purposes of sub-paragraph (a) of Sub-Clause 14.3 [Application for Interim Payment Certificates];
 - b) Sub-Clause 14.5 [Plant and Materials intended for the Works] shall not apply; and
 - c) If these instalments are not defined by reference to the actual progress achieved in executing the Works, and if actual progress is found to be less or more than that on which this schedule of payments was based, then the Architect may proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine revised instalments, which shall take account of the extent to which progress is less or more than that on which the instalments were previously based.
- 14.4.2 If the Contract does not include a schedule of payments, the Contractor shall submit non-binding estimates of the payments which he expects to become due during each quarterly period. The first estimate shall be submitted within 42 days after the Commencement Date. Revised estimates shall be submitted at quarterly intervals, until the Taking-Over Certificate has been issued for the Works.

14.5 Plant and Materials intended for the Works

- 145.1 If this Sub-Clause applies, Interim Payment Certificates shall include, under sub-paragraph (e) of Sub-Clause 14.3, (i) an amount for Plant and Materials which have been sent to the Site for incorporation in the Permanent Works, and (ii) a reduction when the contract value of such Plant and Materials is included as part of the Permanent Works under sub-paragraph (a) of Sub-Clause 14.3 [Application for Interim Payment Certificates].
- 1452 If the lists referred to in sub-paragraphs (b)(i) or (c)(i) below are not included in the Schedules, this Sub-Clause shall not apply.

- 1453 The Architect shall determine and certify each addition if the following conditions are satisfied:
 - a) The Contractor has:
 - i) kept satisfactory records (including the orders, receipts, Costs and use of Plant and Materials) which are available for inspection, and
 - (ii) submitted statement of the Cost of acquiring and delivering the Plant and Materials to the Site, supported by satisfactory evidence;

and either:

- b) the relevant Plant and Materials:
 - i) are those listed in the Schedules for payment when shipped,
 - ii) have been shipped to Kenya, enroute to the Site, in accordance with the Contract; and
 - iii) are described in a clean shipped bill of lading or other evidence of shipment, which has been submitted to the Architect together with evidence of payment of freight and insurance, any other documents reasonably required, and a bank guarantee in a form and issued by an entity approved by the Procuring Entity in amounts and currencies equal to the amount due under this Sub-Clause: this guarantee may be in a similar form to the form referred to in Sub-Clause14.2 [Advance Payment] and shall be valid until the Plant and Materials are properly stored on Site and protected against loss, damage or deterioration; or
- c) the relevant Plant and Materials:
 - i) are those listed in the Schedules for payment when delivered to the Site, and
 - ii) have been delivered to and are properly stored on the Site, are protected against loss, damage or deterioration and appear to be in accordance with the Contract.
- 145.4 The additional amount to be certified shall be the equivalent of eighty percent (80%) of the Architect determination of the cost of the Plant and Materials (including delivery to Site), taking account of the documents mentioned in this Sub-Clause and of the contract value of the Plant and Materials.
- 1455 The currencies for this additional amount shall be the same as those in which payment will become due when the contract value is included under sub-paragraph (a) of Sub-Clause 14.3 [Application for Interim Payment Certificates]. At that time, the Payment Certificate shall include the applicable reduction which shall be equivalent to, and in the same currencies and proportions as, this additional amount for the relevant Plant and Materials.

14.6 Issue of Interim Payment Certificates

- No amount will be certified or paid until the Procuring Entity has received and approved the Performance Security. Thereafter, the Architect shall, within 30 days after receiving a Statement and supporting documents, deliver to the Procuring Entity and to the Contractor an Interim Payment Certificate which shall state the amount which the Architect fairly determines to be due, with all supporting particulars for any reduction or withholding made by the Architect on the Statemen tif any.
- However, prior to issuing the Taking-Over Certificate for the Works, the Architect shall not be bound to issue an Interim Payment Certificate in an amount which would (after retention and other deductions) be less than the minimum amount of Interim Payment Certificates (if any) stated **in the Special Conditions of Contract**. In this event, the Architect shall give notice to the Contractor accordingly.
- 14.63 An Interim Payment Certificate shall not be withheld for any other reason, although:
 - a) if anything supplied or work done by the Contractor is not in accordance with the Contract, the cost of rectification or replacement may be withheld until rectification or replacement has been completed; and/or
 - b) if the Contractor was or is failing to perform any work or obligation in accordance with the Contract, and had been so notified by the Engineer, the value of this work or obligation may be withheld until the work or obligation has been performed.
- 14.6.4 The Architect may in any Payment Certificate make any correction or modification that should properly be made to any previous Payment Certificate. A Payment Certificate shall not be deemed to indicate the Architect acceptance, approval, consent or satisfaction.

14.7 Payment

- 14.7.1 The Procuring Entity shall pay to the Contractor:
 - a) The advance payment shall be paid within 60 days after signing of the contract by both parties or within 60 days after receiving the documents in accordance with Sub-Clause 4.2 [Performance Security] and Sub-Clause 14.2 [Advance Payment], which ever is later;
 - b) The amount certified in each Interim Payment Certificate within 60 days after the Architect Issues Interim Payment Certificate; and
 - c) the amount certified in the Final Payment Certificate within 60 days after the Procuring Entity Issues Interim Payment Certificate; or after determination of any disputed amount shown in the Final Statement in accordance with Sub-Clause 16.2 [Terminationby Contractor].
- 14.72 Payment of the amount due in each currency shall be made into the bank account, nominated by the Contractor, in the payment country (forth is currency) specified in the Contract.

14.8 Delayed Payment

- 14.8.1 If the Contractor does not receive payment in accordance with Sub-Clause 14.7 [Payment], the Contractor shall be entitled to receive financing charges (simple interest) monthly on the amount unpaid during the period of delay. This period shall be deemed to commence on the date for payment specified in Sub-Clause 14.7 [Payment], irrespective (in the case of its sub-paragraph (b) of the date on which any Interim Payment Certificate is is sub-paragraph.
- 14.82 These financing charges shall be calculated at the annual rate of three percentage points above the mean rate of the Central Bank in Kenya of the currency of payment, or if not available, the inter bank offered rate, and shall be paid in such currency.
- 14.8.3 The Contractor shall be entitled to this payment without formal notice and certification, and without prejudice to any other right or remedy.

14.9 Payment of Retention Money

- When the Taking-Over Certificate has been issued for the Works, the first half of the Retention Money shall be certified by the Architect for payment to the Contractor. If a Taking-Over Certificate is issued for a Section or part of the Works, a proportion of the Retention Money shall be certified and paid. This proportion shall behalf (50%) of the proportion calculated by dividing the estimated contract value of the Section or part, by the estimated final Contract Price.
- 14.9.2 Promptly after the latest of the expiry dates of the Defects Liability Periods, the outstanding balance of the Retention Money shall be certified by the Architect for payment to the Contractor. If a Taking-Over Certificate was issued for a Section, a proportion of the second half of the Retention Money shall be certified and paid promptly after the expiry date of the Defects Notification Period for the Section. This proportion shall behalf (50%) of the proportion calculated by dividing the estimated contract value of the Section by the estimated final Contract Price.
- However, if any work remains to be executed under Clause 11 [Defects Liability], the Architects hall be entitled to withhold certification of the estimated cost of this work until it has been executed.
- When calculating these proportions, no account shall be taken of any adjustments under Sub-Clause 13.7 [Adjustments for Changes in Legislation] and Sub-Clause 13.8 [Adjustments for Changes in Cost].
- 14.9.5 Unless otherwise stated in the Special Conditions, when the Taking-Over Certificate has been issued for the Works and the first half of the Retention Money has been certified for payment by the Engineer, the Contractor shall be entitled to substitute a Retention Money Security guarantee, in the form annexed to the Special Conditions or in another form approved by the Procuring Entity and issued by a reputable bank or financial institution selected by the Contractor, for the second half of the Retention Money.

14.9.6 The Procuring Entity shall return the Retention Money Security guarantee to the Contractor within 14 days after receiving a copy of the Completion Certificate.

14.10 Statement at Completion

- 14.10.1 Within 84 days after receiving the Taking-Over Certificate for the Works, the Contractor shall submit to the Architect three copies of a Statement at completion with supporting documents, in accordance with Sub-Clause 14.3 [Application for Interim Payment Certificates], showing:
 - a) the value of all work done in accordance with the Contract up to the date stated in the Taking-Over Certificate for the Works.
 - b) any further sums which the Contractor considers to be due, and
 - c) an estimate of any other amounts which the Contractor considers will become due to him under the Contract. Estimated amounts shall be shown separately in this Statement at completion.
- 14.10.2 The Architect shall then certify in accordance with Sub-Clause 14.6 [Issue of Interim Payment Certificates].

14.11 Application for Final Payment Certificate

- 14.11.1 Within 60 days after receiving the Completion Certificate, the Contractor shall submit, to the Engineer, six copies of a draft final statement with supporting documents showing in detail in a form approved by the Engineer:
 - a) The value of all work done in accordance with the Contract, and
 - b) Any further sums which the Contractor considers to be due to him under the Contractor otherwise.
- 14.11.2 If the Architect disagrees with or cannot verify any part of the draft final statement, the Contractor shall submit such further information as the Architect may reasonably require within 30 days from receipt of said draft and shall make such changes in the draft as may be agreed between them. The Contractor shall then prepare and submit to the Architect the final statement as agreed. This agreed statement is referred to in these Conditions as the "Final Statement".
- 14.11.3 However, if, following discussions between the Architect and the Contractor and any changes to the draft final statement which are agreed, it be comes evident that a dispute exists, the Architect shall deliver to the Procuring Entity (with a copy to the Contractor) an Interim Payment Certificate for the agreed parts of the draft final statement. Thereafter, if the dispute is finally resolved under Sub-Clause 20.4 [Obtaining Dispute Board's Decision] or Sub-Clause 20.5 [Amicable Settlement], the Contractor shall then prepare and submit to the Procuring Entity (with a copy to the Engineer) a Final Statement.

14.12 Discharge

When submitting the Final Statement, the Contractor shall submit a discharge which confirms that the total of the Final Statement represents full and final settlement of all moneys due to the Contractor under or in connection with the Contract. This discharge may state that it becomes effective when the Contractor has received the Performance Security and the out standing balance of this total, in which event the discharge shall be effective on such date.

14.13 Issue of Final Payment Certificate

- 14.13.1 Within 30days after receiving the Final Statement and discharge in accordance with Sub-Clause 14.11 [Application for Final Payment Certificate] and Sub-Clause 14.12 [Discharge], the Architect shall deliver, to the Procuring Entity and to the Contractor, the Final Payment Certificate which shall state:
 - a) The amount which he fairly determines is finally due, and
 - b) After giving credit to the Procuring Entity for all amounts previously paid by the Procuring Entity and for all sums to which the Procuring Entity is entitled, the balance (if any) due from the Procuring Entity to the Contractor or from the Contractor to the Procuring Entity, as the case may be.
- 14.13.2 If the Contractor has not applied for a Final Payment Certificate in accordance with Sub-Clause 14.11 [Application for Final Payment Certificate] and Sub-Clause 14.12 [Discharge], the Architect shall request the Contractor to do so. If the Contractor fails to submit an application within a period of 30 days, the Architect shall issue the Final Payment Certificate for such amount as he fairly determines to be due.

14.14 Cessation of Procuring Entity's Liability

- 14.14.1 The Procuring Entity shall not be liable to the Contractor for any matter or thing under or in connection with the Contract or execution of the Works, except to the extent that the Contractor shall have included an amount expressly for it:
 - a) in the Final Statement and also,
 - b) (except for matters or things arising after the issue of the Taking-Over Certificate for the Works) in the Statement at completion described in Sub-Clause 14.10 [Statement at Completion].
- 14.14.2 However, this Sub-Clause shall not limit the Procuring Entity's liability under his in demnification obligations, or the Procuring Entity's liability in any case of fraud, deliberate default or reckless misconduct by the Procuring Entity.

14.15 Currencies of Payment

The Contract Price shall be paid in the currency or currencies named in the Schedule of Payment Currencies. If more than one currency is so named, payments shall be made as follows:

- a) If the Accepted Contract Amount was expressed in Local Currency only:
 - the proportions or amounts of the Local and Foreign Currencies, and the fixed rates of exchange to be used for calculating the payments, shall be as stated in the Schedule of Payment Currencies, except as otherwise agreed by both Parties;
 - ii) payments and deductions under Sub-Clause 13.5 [Provisional Sums] and Sub-Clause 13.7 [Adjustments for Changes in Legislation] shall be made in the applicable currencies and proportions; and
 - iii) other payments and deductions under sub-paragraphs (a) to (d) of Sub-Clause 14.3 [Application for Interim Payment Certificates] shall be made in the currencies and proportions specified in sub-paragraph (a) (i) above;
- b) payment of the damages specified in the Special Conditions of Contract, shall be made in the currencies and proportions specified in the Schedule of Payment Currencies;
- c) other payments to the Procuring Entity by the Contractor shall be made in the currency in which the sum was expended by the Procuring Entity, or in such currency as may be agreed by both Parties;
- d) if any amount payable by the Contractor to the Procuring Entity in a particular currency exceeds the sum payable by the Procuring Entity to the Contractor in that currency, the Procuring Entity may recover the balance of this amount from the sums otherwise payable to the Contractor in other currencies; and
- e) if no rates of exchange are stated in the Schedule of Payment Currencies, they shall be those prevailing on the Base Date and determined by the Central Bank of Kenya.

15. TERMINATION BY PROCURING ENTITY

15.1 Notice to correct any defects or failures

If the Contractor fails to carry out any obligation under the Contract, the Architect may by notice require the Contractor to make good the failure and to remedy it within 30 days.

15.2 Termination by Procuring Entity

- 152.1 The Procuring Entity shall be entitled to terminate the Contract if the Contractor breaches the contract based on following circumstances which shall include but not limited to:
 - a) fails to comply with Sub-Clause 4.2 [Performance Security] or with a notice under Sub-Clause 15.1 [Notice to Correct],
 - b) abandons the Works or otherwise plainly demonstrates the intention not to continue performance of his obligations under the Contract,

- c) without reasonable excuse fails:
 - to proceed with the Works in accordance with Clause 8 [Commencement, Delays and Suspension], or
 - ii) to comply with a notice issued under Sub-Clause 7.5 [Rejection] or Sub-Clause 7.6 [Remedial Work], within 30 days after receiving it,
- d) subcontracts the major part or whole of the Works or assigns the Contract without the consent of the Procuring Entity,
- e) becomes bankrupt or insolvent, goes into liquidation, has a receiving or administration order made against him, compounds with his creditors, or carries on business under a receiver, trustee or manager for the benefit of his creditors, or if any act is done or event occurs which (under applicable Laws) has a similar effect to any of theseacts or events, or
- f) gives or offers to give (directly or indirectly) to any person any bribe, gift, gratuity, commission or other thing of value, as an induce mentor reward:
- i) for doing or for bearing to do any action in relation to the Contract, or
- ii) for showing or for bearing to show favor or disfavor to any person in relation to the Contract, or
- iii) if any of the Contractor's Personnel, agents or Subcontractors gives or offers to give (directly or indirectly) to any person any such induce mentor reward as is described in this sub-paragraph (f). However, lawful inducements and rewards to Contractor's Personnel shall not entitle termination, or
- g) If the contract or repeatedly fails to remedy delivers defective work,
- h) based on reasonable evidence, has engaged in Fraud and Corruption as defined in paragraph 2.2 of the Appendix B to these General Conditions, incompeting for or in executing the Contract.
- In any of these events or circumstances, the Procuring Entity may, upon giving 14 days' notice to the Contractor, terminate the Contract and expel the Contractor from the Site. However, in the case of subparagraph (e) or (f) or (g) or (h), the Procuring Entity may by notice terminate the Contract immediately.
- 1523 The Procuring Entity's election to terminate the Contract shall not prejudice any other rights of the Procuring Entity, under the Contractor otherwise.
- 15.24 The Contractor shall then leave the Site and deliver any required Goods, all Contractor's Documents, and other design documents made by or for him, to the Engineer. However, the Contractor shall use his best efforts to comply immediately with any reasonable instructions included in the notice (i) for the assignment of any subcontract, and (ii) for the protection of life or property or for the safety of the Works.
- 15.25 After termination, the Procuring Entity may complete the Works and/ or arrange for any other entities to do so. The Procuring Entity and these entities may then use any Goods, Contractor's Documents and other design documents made by or on behalf of the Contractor.
- The Procuring Entity shall then give notice that the Contractor's Equipment and Temporary Works will be released to the Contractor at or near the Site. The Contractor shall promptly arrange their removal, at the risk and cost of the Contractor. However, if by this time the Contractor has failed to make a payment due to the Procuring Entity, these items may be sold by the Procuring Entity in order to recover this payment. Any balance of the proceeds shall then be paid to the Contractor.

153 Valuation at Date of Termination

Assoon as practicable after a notice of termination under Sub-Clause 15.2 [Termination by Procuring Entity] has taken effect, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine the value of the Works, Goods and Contractor's Documents, and any other sums due to the Contractor for work executed in accordance with the Contract.

15.4 Payment after Termination

After a notice of termination under Sub-Clause 15.2 [Termination by Procuring Entity] has taken effect, the Procuring Entity may:

- a) Proceed in accordance with Sub-Clause 2.5 [Procurin Entity's Claims],
- b) withhold further payments to the Contractor until the costs of execution, completion and remedying of any defects, damages for delay in completion (if any), and all other costs incurred by the Procuring Entity, have been established, and/ or

c) recover from the Contractor any losses and damages incurred by the Procuring Entity and any extra costs of completing the Works, after allowing for any sum due to the Contractor under Sub-Clause 15.3 [Valuation at Date of Termination]. After recovering any such losses, damages and extra costs, the Procuring Entity shall pay any balance to the Contractor.

155 Procuring Entity's Entitlement to Termination for Convenience

The Procuring Entity shall be entitled to terminate the Contract, at any time at the Procuring Entity's convenience, by giving notice of such termination to the Contractor. The termination shall take effect 30 days after the later of the dates on which the Contractor receives this notice or the Procuring Entity returns the Performance Security. The Procuring Entity shall not terminate the Contract under this Sub-Clausein order to execute the Works itself or to arrange for the Works to be executed by another contractor or to avoid a termination of the Contract by the Contractor under Clause 16.2 [Termination by Contractor]. After this termination, the Contractor shall proceed in accordance with Sub-Clause 16.3 [Cessation of Work and Removal of Contractor's Equipment] and shall be paid in accordance with Sub-Clause 16.4 [Payment on Termination].

15.6 Fraud and Corruption

The Contractor shall ensure compliance with the Kenya Government's Anti-Corruption Laws and its prevailing sanctions.

15.7 Corrupt gifts and payments of commission

- 15.7.1 The Contractor shall not;
 - a) Offer or give or agree to give to any person in the service of the Procuring Entity any gift or consideration of any kind as an inducement or reward for doing or for bearing to door for having done or for borne to do any act in relation to the obtaining or execution of this or any other Contract for the Procuring Entity or for showing or for bearing to show favor or disfavor to any person in relation to this or any other contract for the Procuring Entity.
 - b) Enter into this or any other contract with the Procuring Entity in connection with which commission has been paid or agreed to be paid by him or on his behalf or to his knowledge, unless before the Contract is made particulars of any such commission and of the terms and conditions of any agreement for the payment there of have been disclosed in writing to the Procuring Entity.
- 15.7.2 Any breach of this Condition by the Contractor or by anyone employed by him or acting on his behalf (whether with or without the knowledge of the Contractor) shall be an offence under the provisions of the Public Procurement and Asset Disposal Act (2015) and the Anti-Corruption and Economic Crimes Act (2003) of the Laws of Kenya.

16 SUSPENSION AND TERMINATION BY CONTRACTOR

16.1 Contractor's Entitlement to Suspend Work

- 16.1.1 If the Architect fails to certify in accordance with Sub-Clause 14.6 [Issue of Interim Payment Certificates] or Sub-Clause 14.7 [Payment], or not receiving instructions that would enable the contractor to proceed with the works in accordance with the program, the Contractor may, after giving not less than 30 days' notice to the Procuring Entity, suspend work (or reduce the rate of work) unless and until the Contractor has received the Payment Certificate, reasonable evidence or payment, as the case may be and as described in the notice.
- The Contractor's action shall not prejudice his entitlements to financing charges under Sub-Clause 14.8 [Delayed Payment] and to termination under Sub-Clause 16.2 [Terminationby Contractor].
- 16.13 If the Contractor subsequently receives such Payment Certificate, evidence or payment (as described in the relevant Sub-Clause and in the above notice) before giving a notice of termination, the Contractor shall resume normal working as soon as is reasonably practicable.
- 16.14 If the Contractor suffers delay and/ori neurs Cost as a result of suspending work (or reducing the rate of work) in accordance with this Sub-Clause, the Contractor shall give notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:

- a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
- b) payment of any such Cost-plus profit, which shall be included in the Contract Price.
- After receiving this notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

163 Termination by Contractor

- 163.1 The Contractor shall be entitled to terminate the Contract if:
 - a) the Architect fails, within 60 days after receiving a Statement and supporting documents, to issue the relevant Payment Certificate,
 - b) the Contractor does not receive the amount due under an Interim Payment Certificate within 90 days after the expiry of the time stated in Sub-Clause1 4.7 [Payment] within which payment is to be made (except for deductions in accordance with Sub-Clause 2.5 [Procuring Entity's Claims]),
 - c) the Procuring Entity substantially fails to perform his obligations under the Contract in such manner as to materially and adversely affect the economic balance of the Contract and/or the ability of the Contractor to perform the Contract,
 - d) a prolonged suspension affects the whole of the Works as described in Sub-Clause 8.11 [Prolonged Suspension], or
 - e) the Procuring Entity becomes bankrupt or insolvent, goes into liquidation, has a receiving or administration order made against him, compounds with his creditors, or carries on business under a receiver, trustee or manager for the benefit of his creditors, or if any act is done or event occurs which (under applicable Laws) has a similar effect to any of these acts or events.
 - f) the Contractor does not receive the Architect instruction recording the agreement of both Parties on the fulfilment of the conditions for the Commencement of Works under Sub-Clause 8.1 [Commencement of Works].
- In any of these events or circumstances, the Contractor may, upon giving 14 days' notice to the Procuring Entity, terminate the Contract. However, in the case of sub-paragraph (f) or (g), the Contractor may by notice terminate the Contract immediately.
- 1633 The Contractor's election to terminate the Contract shall not prejudice any other rights of the Contractor, under the Contractor otherwise.

164 Cessation of Work and Removal of Contractor's Equipment

After a notice of termination under Sub-Clause 15.5 [Procuring Entity's Entitlement to Termination for Convenience], Sub-Clause 16.2 [Termination by Contractor] or Sub-Clause 19.6 [Optional Termination, Payment and Release] has taken effect, the Contractor shall promptly:

- a) cease all further work, except for such work as may have been instructed by the Architect for the protection of life or property or for the safety of the Works,
- b) hand over Contractor's Documents, Plant, Materials and other work, for which the Contractor has received payment, and
- c) remove all other Goods from the Site, except as necessary for safety, and leave the Site.

165 Payment on Termination

After a notice of termination under Sub-Clause 16.2 [Termination by Contractor] has taken effect, the Procuring Entity shall promptly:

- a) Return the Performance Security to the Contractor,
- b) pay the Contractor in accordance with Sub-Clause 19.6 [Optional Termination, Payment and Release], and
- c) pay to the Contractor the amount of any loss or damage sustained by the Contractor as a result of this termination.

17. RISK AND RESPONSIBILITY

17.1 Indemnities

- 17.1.1 The Contractor shall indemnify and hold harmless the Procuring Entity, the Procuring Entity's Personnel, and their respective agents, against and from all claims, damages, losses and expenses (including legal fees and expenses) in respect of:
 - a) Bodily injury, sickness, disease or death, of any person what so ever arising outo for in the course of or by reason of the Contractor's design (if any), the execution and completion of the Works and the remedying of any defects, unless attributable to any negligence, willful actor breach of the Contract by the Procuring Entity, the Procuring Entity's Personnel, or any of their respective agents, and
 - b) damage to or loss of any property, real or personal (other than the Works), to the extent that such damage or loss arises out of or in the course of or by reason of the Contractor's design (if any), the execution and completion of the Works and the remedying of any defects, unless and to the extent that any such damage or loss is attributable to any negligence, willful act or breach of the Contract by the Procuring Entity, the Procuring Entity's Personnel, their respective agents, or anyone directly or indirectly employed by any of them.
- 17.12 The Procuring Entity shall indemnify and hold harmless the Contractor, the Contractor's Personnel, and their respective agents, against and from all claims, damages, losses and expenses (including legal fees and expenses) in respect of (1) bodily injury, sickness, disease or death, which is attributable to any negligence, willful act or breach of the Contract by the Procuring Entity, the Procuring Entity's Personnel, or any of their respective agents, and (2) the matters for which liability may be excluded from insurance cover, as described in sub-paragraphs (d)(i), (ii) and (iii) of Sub-Clause 18.3 [Insurance Against Injury to Persons and Damage to Property], unless and to the extent that any such damage or loss is attributable to any negligence, willful actor breach of the Contract by the contractor, the contractor's Personnel, their respective agents, or anyone directly or indirectly employed by any of them.

17.2 Contractor's Care of the Works

- The Contractor shall take full responsibility for the care of the Works and Goods from the Commencement Date until the Taking-Over Certificate is issued (or is deemed to be issued under Sub-Clause 10.1 [Taking Over of the Works and Sections]) for the Works, when responsibility for the care of the Works shall pass to the Procuring Entity. If a Taking-Over Certificate is issued (or is so deemed to be issued) for any Section or part of the Works, responsibility for the care of the Section or part shall then pass to the Procuring Entity.
- 1722 After responsibility has accordingly passed to the Procuring Entity, the Contractor shall take responsibility for the care of any work which is outstanding on the date stated in a Taking-Over Certificate, until this outstanding work has been completed.
- 17.23 If any loss or damage happens to the Works, Goods or Contractor's Documents during the period when the Contractorisresponsible for their care, from any cause not listed in Sub-Clause 17.3 [Procuring Entity's Risks], the Contractor shall rectify the loss or damage at the Contractor's risk and cost, so that the Works, Goods and Contractor's Documents conform with the Contract.
- 17.24 The Contractor shall be liable for any loss or damage caused by any actions performed by the Contractor after a Taking-Over Certificate has been issued. The Contractor shall also be liable for any loss or damage which occurs after a Taking-Over Certificate has been issued and which arose from a previous event for which the Contractor was liable.

173 Procuring Entity's Risks

The risks referred to in Sub-Clause 17.4 [Consequences of Procuring Entity's Risks] below, in so far as they directly affect the execution of the Works in Kenya, are:

- a) War hostilities (whether war be declared or not),
- b) rebellion, riot, commotion or disorder, terrorism, sabotage by persons other than the Contractor's Personnel.
- c) explosive materials, ionizing gradiation or contamination by radio-activity, except as may be attributable to the Contractor's use of such explosives, radiation or radio-activity,
- d) pressure waves caused by aircraft or other aerial devices traveling at sonic or supersonic speeds,

- e) use or occupation by the Procuring Entity of any part of the Permanent Works, except as may be specified in the Contract,
- f) design of any part of the Works by the Procuring Entity's Personnel or by others for whom the Procuring Entity is responsible, and
- g) any operation of the forces of nature which is Unforeseeable or against which an experienced contractor could not reasonably have been expected to have taken adequate preventive precautions.

174 Consequences of Procuring Entity's Risks

- 17.4.1 If and to the extent that any of the risks listed in Sub-Clause 17.3 above results in loss or damage to the Works, Goods or Contractor's Documents, the Contractor shall promptly give notice to the Architect and shall rectify this loss or damage to the extent required by the Engineer.
- 17.42 If the Contractor suffers delay and/ or incurs Cost from rectifying this loss or damage, the Contractor shall give a further notice to the Architect and shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:
- (a) An extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of TimeforCompletion], and
- (b) Payment of any such Cost, which shall be included in the Contract Price. In the case of sub-paragraphs (e) and (g) of Sub-Clause 17.3 [Procuring Entity's Risks], Accrued Costs shall be payable.
- 17.43 After receiving this further notice, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

175 Intellectual and Industrial Property Rights

- 175.1 In this Sub-Clause, "infringement" shall refer to an infringement (or alleged infringement) of any patent, registered design, copyright, trade mark, trade name, trade secret or other intellectual or industrial property right relating to the Works; and "claim" shall refer to a claim (or proceedings pursuing a claim) alleging an infringement.
- Whenever a Party does not give notice to the other Party of any claim within 30 days of receiving the claim, the first Party shall be deemed to have waived any right to indemnity under this Sub-Clause.
- 1753 The Procuring Entity shall indemnify and hold the Contractor harmless against and from any claim alleging an infringement which is or was:
 - a) An un avoidable result of the Contractor's compliance with the Contract, or
 - b) A result of any Works be ingused by the Procuring Entity:
 - i) for a purpose other than that indicated by, or reasonably to be inferred from, the Contract, or
 - ii) in conjunction with anything not supplied by the Contractor, unless such use was disclosed to the Contractor prior to the Base Date or is stated in the Contract.
- 175.4 The Contractor shall indemnify and hold the Procuring Entity harmless again stand from any other claim which arises out of or in relation to (i) the manufacture, use, sale or import of any Goods, or (ii) any design for which the Contractor is responsible.
- 1755 IfaPartyisentitledtobeindemnified under this Sub-Clause, the indemnifying Party may (at its cost) conduct negotiations for the settlement of the claim, and any litigation or arbitration which may arise from it. The other Party shall, at the request and cost of the indemnifying Party, assist in contesting the claim. This other Party (and its Personnel) shall not make any admission which might be prejudicial to the indemnifying Party, unless the indemnifying Party failed to take over the conduct of any negotiations, litigation or arbitration upon being requested to do so by such other Party.
- 175.6 For operation and maintenance of any plan to requipment installed, the contractor shall grant a non-exclusive and non-transferable license to the Procuring Entity under the patent, utility models ,or other intellectual rights owned by the contractor or a third party from whom the contract or has received the rights to grant sub-licenses and shall also grant to the Procuring Entity a non-exclusive and non-transferable rights (without the rights to sub-license) to use the know how and other technical information disclosed to the contract or under the contract. Nothing contained here-in shall be construed as transferring ownership of any patent, utility model, trademark, design, copy right, know-how or other intellectual rights from the contractor or any other third party to the Procuring Entity.

17.6 Limitation of Liability

- 17.6.1 Neither Party shall be liable to the other Party for loss of use of any Works, loss of profit, loss of any contractor for any in director consequential loss or damage which may be suffered by the other Party in connection with the Contract, other than as specifically provided in Sub-Clause 8.7 [Delay Damages]; Sub-Clause 11.2 [Cost of Remedying Defects]; Sub-Clause 15.4 [Payment after Termination]; Sub-Clause 16.4 [Payment on Termination]; Sub-Clause 17.1 [Indemnities]; Sub-Clause 17.4(b) [Consequences of Procuring Entity's Risks] and Sub-Clause 17.5 [Intellectual and Industrial Property Rights].
- The total liability of the Contractor to the Procuring Entity, under or in connection with the Contract other than under Sub-Clause 4.19 [Electricity, Water and Gas], Sub-Clause 4.20 [Procuring Entity's Equipment and Free- Issue Materials], Sub-Clause 17.1 [Indemnities] and Sub-Clause 17.5 [Intellectual and Industrial Property Rights], shall not exceed the sum resulting from the application of a multiplier (less or greater than one) to the Accepted Contract Amount, as stated in **the Special Conditions of Contract**, or (if such multiplier or other sum is not so stated) the Accepted Contract Amount.
- 17.63 This Sub-Clause shall not limit liability in any case of fraud, deliberate default or reckless misconduct by the defaulting Party.

17.7 Use of Procuring Entity's Accommodation/Facilities

- 17.7.1 The Contractor shall take full responsibility for the care of the Procuring Entity provided accommodation and facilities, if any, as detailed in the Specification, from the respective dates of hand-over to the Contractor until cessation of occupation (where hand-over or cessation of occupation may take place after the date stated in the Taking-Over Certificate for the Works).
- 17.72 If any loss or damage happens to any of the above items while the Contractor is responsible for their care arising from any cause whatsoever other than those for which the Procuring Entity is liable, the Contractor shall, at his own cost, rectify the loss or damage to the satisfaction of the Engineer.

18 INSURANCE

18.1 General Requirements for Insurances

- 18.1.1 In this Clause, "insuring Party" means, for each type of insurance, the Party responsible for effecting and maintaining the insurance specified in the relevant Sub-Clause.
- 18.1.2 Wherever the Contractor is the insuring Party, each insurance shall be effected with insurers and in terms approved by the Procuring Entity. These terms shall be consistent with any terms agreed by both Parties before the date of the Letter of Acceptance. This agreement of terms shall take precedence over the provisions of this Clause.
- 18.13 Wherever the Procuring Entity is the insuring Party, each insurance shall be effected with insurers and in terms acceptable to the Contractor. These terms shall be consistent with any terms agreed by both Parties before the date of the Letter of Acceptance. This agreement of terms shall take precedence over the provisions of this Clause.
- 18.14 If a policy is required to indemnify joint insured, the cover shall apply separately to each insured as though a separate policy had been issued for each of the joint insured. If a policy indemnifies additional joint insured, namely in addition to the insured specified in this Clause, (i) the Contractor shall act under the policy on behalf of these additional joint insured except that the Procuring Entity shall act for Procuring Entity's Personnel, (ii) additional joint insured shall not be entitled to receive payments directly from the insurer or to have any other direct dealings with the insurer, and (iii) the insuring Party shall require all additional joint insured to comply with the conditions stipulated in the policy.
- 18.15 Each policy insuring against loss or damage shall provide for payments to be made in the currencies required to rectify the loss or damage. Payments received from insurers shall be used for the rectification of the loss or damage.

- 18.1.6 The relevant insuring Party shall, within the respective periods stated in **the Special Conditions of Contract** (calculated from the Commencement Date), submit to the other Party:
 - a) Evidence that the insurances described in this Clause have been affected, and
 - b) copies of the policies for the insurances described in Sub-Clause 18.2 [Insurance for Works and Contractor's Equipment] and Sub-Clause 18.3 [Insurance against Injury to Persons and Damage to Property].
- When each premium is paid, the insuring Party shall submit evidence of payment to the other Party. Whenever evidence or policies are submitted, the insuring Party shall also give notice to the Engineer.
- 18.18 Each Party shall comply with the conditions stipulated in each of the insurance policies. The insuring Party shall keep the insurers informed of any relevant changes to the execution of the Works and ensure that insurance is maintained in accordance with this Clause.
- 18.19 Neither Party shall make any material alteration to the terms of any insurance without the prior approval of the other Party. If an insurer makes (or at tempts to make) any alteration, the Party first notified by the insurer shall promptly give notice to the other Party.
- 18.1.10 If the insuring Party fails to effect and keep in force any of the insurances it is required to effect and maintain under the Contractor fails to provide satisfactory evidence and copies of policies in accordance with this Sub- Clause, the other Party may (at its option and without prejudice to any other right or remedy) effect insurance for the relevant coverage and pay the premiums due. The insuring Party shall pay the amount of these premiums to the other Party, and the Contract Price shall be adjusted accordingly.
- 18.1.11 Nothing in this Clause limits the obligations, liabilities or responsibilities of the Contractor or the Procuring Entity, under the other terms of the Contractor otherwise. Any amounts not insured or not recovered from the insurers shall be borne by the Contractor and/or the Procuring Entity.
- 18.1.12 Procuring Entity in accordance with these obligations, liabilities or responsibilities. However, if the insuring Party fails to effect and keep in force an insurance which is available and which it is required to effect and maintain under the Contract, and the other Party neither approves the omission nor effects insurance for the coverage relevant to this default, any moneys which should have been recoverable under this insurance shall be paid by the insuring Party.
- 18.1.13 Payments by one Party to the other Party shall be subject to Sub-Clause 2.5 [Procuring Entity's Claims] or Sub-Clause 20.1 [Contractor's Claims], as applicable.
- 18.1.14 The Contractor shall be entitled to place all insurance relating to the Contract (including, but not limited to the insurance referred to Clause 18) with insurers from any eligible source country.

182 Insurance for Works and Contractor's Equipment

- 182.1 The insuring Party shall insure the Works, Plant, Material sand Contractor's Documents for not less than the full reinstatement cost including the costs of demolition, removal of debris and professional fees and profit. This insurance shall be effective from the date by which the evidence is to be submitted under sub-paragraph (a) of Sub-Clause 18.1 [General Requirements for Insurances], until the date of issue of the Taking-Over Certificate for the Works.
- The insuring Party shall maintain this insurance to provide cover until the date of issue of the Performance Certificate, for loss or damage for which the Contractor is liable arising from a cause occurring prior to the issue of the Taking-Over Certificate, and for loss or damage caused by the Contractor in the course of any other operations (including those under Clause 11 [Defects Liability]).
- The insuring Party shall insure the Contractor's Equipment for not less than the full replacement value, including delivery to Site. For each item of Contractor's Equipment, the insurance shall be effective while it is being transported to the Site and until it is no longer required as Contractor's Equipment.
- 1824 Unless otherwise stated in the Special Conditions, insurances under this Sub-Clause:
 - a) Shall be effected and maintained by the Contractor as insuring Party,

- b) shall be in the joint names of the Parties, who shall be jointly entitled to receive payments from the insurers, payments being held or allocated to the Party actually bearing the costs of rectifying the loss or damage,
- c) shall cover all loss and damage from any cause not listed in Sub-Clause 17.3 [Procuring Entity's Risks],
- d) shall also cover, to the extent specifically required in the tendering documents of the Contract, loss or damage to a part of the Works which is attributable to the use or occupation by the Procuring Entity of another part of the Works, and loss or damage from the risks listed in sub-paragraphs (c), (g) and (h)of Sub-Clause 17.3 [Procuring Entity's Risks], excluding (in each case) risks which are not insurable at commercially reasonable terms, with deductibles per occurrence of not more than the amount stated in the Special Conditions of Contract (if an amount is not so stated,t his sub-paragraph (d) shall not apply), and
- e) may however exclude loss of, damage to, and reinstatement of:
 - i) a part of the Works which is in a defective condition due to a defect in its design, materials or workmanship (but cover shall include any other parts which are lost or damaged as a direct result of this defective condition and not as described in sub-paragraph (ii) below),
 - ii) apart of the Works which is lost or damaged inorder to reinstate any other part of the Works if this other part is in a defective condition due to a defect in its design, materials or workmanship,
 - iii) apart of the Works which has been taken over by the Procuring Entity, except to the extent that the Contractor is liable for the loss or damage, and
 - iv) Goods while they are not in Kenya, subject to Sub-Clause 14.5 [Plant and Materials intended for the Works].
- If, more than one year after the Base Date, the cover described in sub-paragraph (d) above ceases to be available at commercially reasonable terms, the Contractor shall (as insuring Party) give notice to the Procuring Entity, with supporting particulars. The Procuring Entity shall then (i) be entitled subject to Sub-Clause 2.5 [Procuring Entity's Claims] to payment of an amount equivalent to such commercially reasonable terms asthe Contractor should have expected to have paid for such cover, and (ii) be deemed, unless he obtains the cover at commercially reasonable terms, to have approved the omission under Sub-Clause 18.1 [General Requirements for Insurances].

183 Insurance against Injury to Persons and Damage to Property

- 183.1 The insuring Party shall insure against each Party's liability for any loss, damage, death or bodily injury which may occur to any physical property (except things insured under Sub-Clause 18.2 [Insurance for Works and Contractor's Equipment]) or to any person (except persons insured under Sub-Clause 18.4 [Insurance for Contractor's Personnel]), which may arise out of the Contractor's performance of the Contract and occurring before the issue of the Performance Certificate.
- This insurance shall be for a limit per occurrence of not less than the amount stated in **the Special Conditions of Contract**, with no limit on the number of occurrences. If an amount is not stated in the **Special Conditions of Contract**, this Sub-Clause shall not apply.
- 1833 Unless otherwise stated in the Special Conditions, the insurances specified in this Sub-Clause:
 - a) Shall be effected and maintained by the Contractor as insuring Party,
 - b) shall be in the joint names of the Parties,
 - c) shall be extended to cover liability for all loss and damage to the Procuring Entity's property (except things insured under Sub-Clause 18.2) arising out of the Contractor's performance of the Contract, and
 - d) may however exclude liability to the extent that it arises from:
 - i) the Procuring Entity's right to have the Permanent Works executed on, over, under, in or
 - ii) through any land, and to occupy this land for the Permanent Works,
 - iii) damage which is an unavoidable result of the Contractor's obligations to execute the
 - iv) Works and remedy any defects, and
 - v) a cause listed in Sub-Clause 17.3 [Procuring Entity's Risks], except to the extent that cover is available at commercially reasonable terms.

184 Insurance for Contractor's Personnel

- 18.4.1 The Contractor shall effect and maintain insurance against liability for claims, damages, losses and expenses (including legal fees and expenses) arising from injury, sickness, disease or death of any person employed by the Contractor or any other of the Contractor's Personnel.
- The insurance shall cover the Procuring Entity and the Architect against liability for claims, damages, losses and expenses (including legal fees and expenses) arising from injury, sickness, disease or death of any person employed by the Contractoror any othe rof the Contractor's Personnel, except that this insurance may exclude losses and claims to the extent that they arise from any act or neglect of the Procuring Entity or of the Procuring Entity's Personnel.
- 18.43 The insurance shall be maintained in full force and effect during the whole time that these personnel are assisting in the execution of the Works. For a Subcontractor's employees, the insurance may be effected by the Subcontractor, but the Contractor shall be responsible for compliance with this Clause.

19. FORCE MAJEURE

19.1 Definition of Force Majeure

- 19.1.1 In this Clause, "Force Majeure" means an exceptional event or circumstance:
 - a) Which is beyond a Party's control,
 - b) Which such Party could not reasonably have provided against before entering into the Contract,
 - c) which, having arisen, such Party could not reasonably have avoided or over come, and
 - d) which is not substantially attributable to the other Party.
- 19.12 Force Majeure may include, but is not limited to, exceptional events or circumstances of the kind listed below, s olong as conditions (a) to (d) above are satisfied:
 - a) war, hostilities (whether war be declared or not), invasion, act of foreign enemies,
 - b) rebellion, terrorism, sabotage by persons other than the Contractor's Personnel, revolution, insurrection, military or usurped power, or civil war,
 - c) riot, commotion, disorder, strike or lock out by persons other than the Contractor's Personnel,
 - d) munitions of war, explosive materials, ionizing radiation or contamination by radio-activity, except as maybeattributabletotheContractor'suseofsuchmunitions, explosives, radiation or radio-activity, and
 - e) natural catastrophes such as earthquake, hurricane, typhoon or volcanic activity.

192 Notice of Force Majeure

- If a Party is or will be prevented from performing its substantial obligations under the Contract by Force Majeure, then it shall give notice to the other Party of the event or circumstances constituting the Force Majeure and shall specify the obligations, the performance of which is or will be prevented. The notice shall be given within 14 days after the Party became aware, or should have become aware, of the relevant event or circumstance constituting Force Majeure.
- 1922 The Party shall, having given notice, be excused performance of its obligations for so long as such Force Majeure prevents it from performing them.
- Not withstanding any other provision of this Clause, Force Majeure shall not apply to obligations of either Party to make payments to the other Party under the Contract.

193 Duty to Minimize Delay

Each Party shall at all times use all reasonable endeavors to minimize any delay in the performance of the Contract as a result of Force Majeure. A Party shall give notice to the other Party when it ceases to be affected by the Force Majeure.

19.4 Consequences of Force Majeure

194.1 If the Contractor is prevented from performing his substantial obligations under the Contract by Force Majeure of which notice has been given under Sub-Clause 19.2 [Notice of Force Majeure], and suffers delay and/ or incurs Cost by reason of such Force Majeure, the Contractor shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to:

- a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and
- b) if the event or circumstance is of the kind described in sub-paragraphs (i) to (iv) of Sub-Clause 19.1 [Definition of Force Majeure] and, in sub-paragraphs (ii) to (iv), occurs in Kenya, payment of any such Cost, including the costs of rectifying or replacing the Works and/or Goods damaged or destroyed by Force Majeure, to the extent they are not indemnified through the insurance policy referred to in Sub-Clause18.2 [Insurance for Works and Contractor's Equipment].
- 1942 After receiving this notice, the Architect shall proceed in a ccordance with Sub-Clause 3.5 [Determinations] to agree or determine these matters.

195 Force Majeure Affecting Subcontractor

If any Subcontractor is entitled under any contract or agreement relating to the Works to relief from force majeure on terms additional to or broader than those specified in this Clause, such additional or broader force majeure events or circumstances shall not excuse the Contractor's non-performance or entitle him to relief under this Clause.

19.6 Optional Termination, Payment and Release

- 19.6.1 If the execution of substantially all the Works in progress is prevented for a continuous period of 84 days by reason of Force Majeure of which notice has been given under Sub-Clause 19.2 [Notice of Force Majeure], or for multiple periods which total more than 140 days due to the same notified Force Majeure, then either Party may give to the other Party a notice of termination of the Contract. In this event, the termination shall take effect 7 days after the notice is given, and the Contractor shall proceed in accordance with Sub-Clause 16.3 [Cessation of Work and Removal of Contractor's Equipment].
- 19.62 Upon such termination, the Architect shall determine the value of the work done and issue a Payment Certificate which shall include:
 - a) The amounts payable for any work carried out for which a price is stated in the Contract;
 - b) the Cost of Plant and Materials ordered for the Works which have been delivered to the Contractor, or of which the Contractor is liable to accept delivery: this Plant and Materials shall become the property of (and be at the risk of) the Procuring Entity when paid for by the Procuring Entity, and the Contractor shall place the same at the Procuring Entity's disposal;
 - c) other Cost or liabilities which in the circumstances were reasonably and necessarily incurred by the Contractor in the expectation of completing the Works;
 - d) the Cost of removal of Temporary Works and Contractor's Equipment from the Site and the return of these items to the Contractor's works in his country (or to any other destination at no greater cost); and
 - e) the Cost of repatriation of the Contractor's staff and lab or employed wholly in connection with the Works at the date of termination.

19.7 Release from Performance

Not withstanding any other provision of this Clause, if any event or circumstance outside the control of the Parties (including, but not limited to, Force Majeure) arises which makes it impossible or unlawful for either or both Parties to fulfil its or their contractual obligations or which, under the law governing the Contract, entitles the Parties to be released from further performance of the Contract, then upon notice by either Party to the other Partyofsucheventorcircumstance:

- a) The Parties shall be discharged from further performance, without prejudice to the rights of either Party in respect of any previous breach of the Contract, and
- b) The sum payable by the Procuring Entity to the Contractor shall be the same as would have been payable under Sub-Clause 19.6 [Optional Termination, Payment and Release] if the Contract had been terminated under Sub-Clause 19.6.

20. SETTLEMENT OF CLAIMS AND DISPUTES

20.1 Contractor's Claims

- 20.1.1 If the Contractor considers itself to be entitled to any extension of the Time for Completion and/or any additional payment, under any Clause of these Conditions or otherwise in connection with the Contract, the Contractor shall give Notice to the Engineer, describing the event or circumstance giving rise to the claim. The notice shall be given as soon as practicable, and not later than 30 days after the Contractor became aware, or should have become aware, of the event or circumstance.
- 20.12 If the Contractor fails to give notice of a claim within such period of 30 days, the Time for Completion shall not be extended, the Contractor shall not be entitled to additional payment, and the Procuring Entity shall be discharged from all liability in connection with the claim. Otherwise, the following provisions of this Sub-Clause shall apply.
- 20.13 The Contractor shall also submit any other notices which are required by the Contract, and supporting particulars for the claim, all as relevant to such event or circumstance.
- 20.1.4 The Contractor shall keep such contemporary records as may be necessary to substantiate any claim, either on the Site or at an other location acceptable to the Engineer. Without admitting the Procuring Entity's liability, the Architect may, after receiving any notice under this Sub-Clause, monitor the record-keeping and/or instruct the Contractor to keep further contemporary records. The Contractor shall permit the Architect to inspect all these records and shall (if instructed) submit copies to the Engineer.
- 20.15 Within 42days after the Contractor became aware (or should have become aware) of the event or circumstance giving rise to the claim, or within such other period as may be proposed by the Contractor and approved by the Engineer, the Contractor shall send to the Architect fully detailed claim which includes full supporting particulars of the basis of the claim and of the extension of time and/ or additional payment claimed. If the event or circumstance giving rise to the claim has a continuing effect:
 - a) This fully detailed claim shall be considered as interim;
 - b) The Contractor shall send further interim claims at monthly intervals, giving the accumulated delay and/ or amount claimed, and such further particulars as the Architect may reasonably require; and
 - c) The Contractor shall send a final claim within 30 days after the end of the effects resulting from the eventor circumstance, or within such other period as may be proposed by the Contractor and approved by the Engineer.
- 20.1.6 Within 42 days after receiving a Notice of a claim or any further particulars supporting a previous claim, or within such other period as may be proposed by the Architect and approved by the Contractor, the Architect shall respond with approval, or with disapproval and detailed comments. He may also request any necessary further particulars but shall nevertheless give his response on the principles of the claim within the above defined time period.
- 20.1.7 Within the above defined period of 42 days, the Architect shall proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) the extension (if any) of the Time for Completion (before or after its expiry) in accordance with Sub-Clause 8.4 [Extension of Time for Completion], and/or (ii) the additional payment (if any) to which the Contractor is entitled under the Contract.
- 20.1.8 Each Payment Certificate shall include such additional payment for any claim as has been reasonably substantiated as due under the relevant provision of the Contract. Unless and until the particulars supplied are sufficient to substantiate the whole of the claim, the Contractor shall only be entitled to payment for such part of the claim as he has been able to substantiate.
- 20.19 If the Architect does not respond within the time frame defined in this Clause, either Party may consider that the claim is rejected by the Architect and any of the Parties may refer the dispute for amicable settlement in accordance with Clause 20.3.
- 20.1.10 The requirements of this Sub-Clause are in addition to those of any other Sub-Clause which may apply to a claim. If the Contractor fails to comply with this or another Sub-Clause in relation to any claim, any extension of time and/ or additional payment shall take account of the extent (if any) to which the failure has prevented or prejudiced proper investigation of the claim, unless the claim is excluded under the second paragraph of this Sub-Clause 20.3.

20.2 Procuring Entity's Claims

- If the Procuring Entity considers itself to be entitled to any payment under any Clause of these Conditionsor otherwise in connection with the Contract, and/or to any extension of the Defects Notification Period, the Procuring Entity or the Architect shall give notice and particulars to the Contractor. However, notice is not required for payments due under Sub-Clause 4.19 [Electricity, Water and Gas], under Sub-Clause 4.20 [Procuring Entity's Equipment and Free-Issue Materials], or for other services requested by the Contractor.
- The notice shall be given as soon as practicable and no longer than 30 days after the Procuring Entity became aware, or should have become aware, of the event or circumstances giving rise to the claim. A notice relating to any extension of the Defects Notification Period shall be given before the expiry of such period.
- The particulars shall specify the Clause or other basis of the claim and shall include substantiation of the amount and/or extension to which the Procuring Entity considers itself to be entitled in connection with the Contract. The Architect shall then proceed in accordance with Sub-Clause 3.5 [Determinations] to agree or determine (i) the amount (if any) which the Procuring Entity is entitled to be paid by the Contractor, and/or (ii) the extension (if any) of the Defects Notification Period in accordance with Sub-Clause 11.3 [Extension of Defects Notification Period].
- This amount may be included as a deduction in the Contract Price and Payment Certificates. The Procuring Entity shall only be entitled to set off against or make any deduction from an amount certified in a Payment Certificate, or to otherwise claim against the Contractor, in accordance with this Sub-Clause.

203 Amicable Settlement

Where a notice of a claim has been given, both Parties shall attempt to settle the dispute amicably before the commencement of arbitration. However, unless both Parties agree otherwise, the Party giving a notice of a claim in accordance with Sub-Clause 20.1 above should move to commence arbitrationa fter 60 days from the day on which a notice of a claim was given, even if no attempt at an amicable settlement has been made.

20.4 Matters that may be referred to arbitration

Notwithstanding anything stated herein the following matters may be referred to arbitration before the practical completion of the Works or abandonment of the Works or termination of the Contract by either party:

- a) Whether or not the issue of an instruction by the Architect is empowered by these Conditions.
- b) Whether or not a certificate has been improperly withheld or is not in accordance with these Conditions.
- c) Any dispute arising in respect risks arising from matters referred to in Clause 17.3 and Clause 19.
- e) All other matters shall only be referred to arbitration after the completion or alleged completion of the Works or termination or alleged termination of the Contract, unless the Procuring Entity and the Contractor agree otherwise in writing.

205 Arbitration

- 205.1 Any claim or dispute between the Parties arising out of or in connection with the Contract not settled amicably in accordance with Sub-Clause 20.3 shall be finally settled by arbitration.
- No arbitration proceedings shall be commenced on any claim or dispute where notice of a claim or dispute has not been given by the applying party within ninety days of the occurrence or discovery of the matter or issue giving rise to the dispute.
- Not withstanding the issue of a notice as stated above, the arbitration of such a claim or dispute shall not commence unless an attempt has in the first instance been made by the parties to settle such claim or dispute amicably with or without the assistance of third parties. Proof of such attempt shall be required.
- 2054 The Arbitrator shall, without prejudice to the generality of his powers, have powers to direct such measurements, computations, tests or valuations as may in his opinion be desirable in order to determine the rights of the parties and assess and a ward any sums which ought to have been the subject of or included in any certificate.

- The Arbitrator shall, without prejudice to the generality of his powers, have powers to open up, review and revise any certificate, opinion, decision, requirement or notice and to determine all matters in dispute which shall be submitted to him in the same manner as if no such certificate, opinion, decision require mentor notice had been given.
- The arbitrators shall have full power to open up, review and revise any certificate, determination, instruction, opinion or valuation of the Engineer, relevant to the dispute. Nothing shall disqualify representatives of the Parties and the Architect from being called as a witness and giving evidence before the arbitrators on any matter whatsoever relevant to the dispute.
- Neither Party shall be limited in the proceedings before the arbitrators to the evidence, or to the reasons for dissatisfaction given in its Notice of Dissatisfaction.
- 205.7 Arbitration may be commenced prior to or after completion of the Works. The obligations of the Parties, and the Architect shall not be altered by reason of any arbitration being conducted during the progress of the Works.
- The terms of the muneration of each or all the members of Arbitration shall be mutually agreed upon by the Parties when agreeing the terms of appointment. Each Party shall be responsible for paying one-half of this remuneration.

20.6 Arbitration with National Contractors

- 20.6.1 If the Contractis with national contractors, arbitration proceedings will be conducted in accordance with the Arbitration Laws of Kenya. In case of any claim or dispute, such claim or dispute shall be notified in writing by either party to the other with a request to submit it to arbitration and to concur in the appointment of an Arbitrator within thirty days of the notice. The dispute shall be referred to the arbitration and final decision of a person to be agreed between the parties. Failing agreement to concur in the appointment of an Arbitrator, the Arbitrator shall be appointed, on the request of the applying party, by the Chairman or Vice Chairman of any of the following professional institutions;
 - i) Architectural Association of Kenya
 - ii) Institute of Quantity Surveyors of Kenya
 - iii) Association of Consulting Engineers of Kenya
 - iv) Chartered Institute of Arbitrators (Kenya Branch)
 - v) Institution of Engineers of Kenya
- 20.62 The institution written to first by the aggrieved party shall take precedence over all other institutions.

20.7 Arbitration with Foreign Contractors

- 207.1 Arbitration with foreign contractors shall be conducted in accordance with the arbitration rules of the United Nations Commission on International Trade Law (UNCITRAL); or with proceedings administered by the International Chamber of Commerce (ICC) and conducted under the ICC Rules of Arbitration; by one or more arbitrators appointed in accordance with said arbitration rules.
- The place of arbitration shall be a location specified in the SCC; and the arbitration shall be conducted in the language for communications defined in Sub-Clause 1.4 [Law and Language].

20.8 Alternative Arbitration Proceedings

Alternatively, the Parties may refer the matter to the Nairobi Centre for International Arbitration (NCIA) which offers a neutral venue for the conduct of national and international arbitration with commitment to providing institutional support to the arbitral process.

20.9 Failure to Comply with Arbitrator's Decision

- 209.1 The award of such Arbitrator shall be final and binding up on the parties.
- In the even that a Party fails to comply with a final and binding Arbitrator's decision, then the other Party may, without prejudice to any other rights it may have, refer the matter to a competent court of law.

20.10 Contract operations to continue

Notwithstanding any reference to arbitration herein,

- 1.1.1 the parties shall continue to perform their respective obligations under the Contract unless they otherwise agree; and
- 1.12 the Procuring Entity shall pay the Contractor any monies due the Contractor.

SECTION IX - SPECIAL CONDITIONS OF CONTRACT

The following Special Conditions shall supplement the GCC. Whenever there is a conflict, the provisions here in shall prevail over those in the GCC.

Part A - Contract Data

Conditions	Sub Clause	Data
Procuring Entity's name and address	1.1	THE PRINCIPAL SECRETARY— STATE DEPARTMENT FOR BLUE ECONOMY AND FISHERIES of P.O.BOX 58187 – 00200 NAIROBI
Name and Reference No. of the Contract	1.1	W.P ITEM NO. D1166 NB/NB/2401 JOB NO. 10225L MMBE&MA/SDBE&F/01/2024-2025
Engineer's Name and Address	1.1 and 3.1.1	The Works Secretary, State Department for Public Works of P.O.Box 30743-00100
Time for completion	1.1	16 weeks
Section	1.1	Not applicable
Defects Liability Period	1.1	26 weeks
Electronic transimission systems	1.3	To be agreed with the Engineer
Time for parties to enter into a contract agreement	1.6	Within 14 Days after receiving the contract agreement by the contractor and before expiry of the tender validity period.
Time for access to the site	2.1.1	To be agreed with the Engineer
Architect Duties and Responsibilities	3.1.6 (b) (ii)	Variations that exceed the accepted contract Amount shall require approval from the procurement entity
Performance Security	4.2.1	The performance security will be in the form of a performance bank guarantee in the amount of 5% of the accepted Amount in the same currency(ies) of the accepted contract amount
Contractor's Representative Name	4.3.1	To be agreed with the Engineer
Normal Working Hours	6.5	0800 Hrs to 1700 Hrs
Commencement date	8.1.1	To be agreed with the Engineer
Delay damages for the Works	8.7.1 & 14.15 (b)	0.025 % of the Contract price per day
Maximum amount for Delay Damages	8.7.1	5% of the final contract price

Conditions	Sub Clause	Data
Provisional Sums	13.6. (b)(ii)	As determined by the Engineer
Adjustments for Changes in Cost	13.9	Prices are fixed
Total advance payment	14.2.1	Not applicable
Repayment amortization rate of advance payment	14.2.5 (b)	Not applicable
Percentage of Retention	14.3.2 (c)	10%
Limit of Retention Money	14.3.2 (c)	5 % of the Accepted Contract Amount
Plant and Materials	14.5.3(b)(i)	If Sub-Clause 14.5 applies: Plant and Materials for payment Free on Board [Not Applicable].
	14.5.3(c)(i)	Plant and Materials for payment when delivered to the Site: Plant and materials to be incorporated into permanent works
Minimum Amount of Interim Payment Certificates	14.6	As per valuation of the work done and materials on site
Publishing source of commercial interest rates for financial charges in case of delayed payment	14.8	Central Bank of Kenya average rate for base lending prevailing plus 3%
Key Personnel names	6.9.1	To be agreed with the Engineer
Maximum total liability of the Contractor to the Procuring Entity	17.6.2	As per applicable laws
Periods for submission of insurance:	18.1.6	
a. evidence of insurance.b. Relevant policies		14 days <u>14</u> days
Maximum amount of deductibles for insurance of the Procuring Entity's risks	18.2.4 (d)	As per applicable laws
Minimum amount of third- party insurance	18.3.2	As per applicable laws
The place of arbitration	20.7.2	To be agreed upon

SECTION X - CONTRACT FORMS

FORM No. 1 - NOTIFICATION OF INTENTION TO AWARD

FORM NO. 2 – REQUEST FOR REVIEW

FORM No. 3-LETTEROF AWARD

FORM No. 4 - CONTRACT AGREEMENT

FORM No. 5 - PERFORMANCE SECURITY [Option 1 - Unconditional Demand Bank Guarantee]

FORM No. 6- PERFORMANCE SECURITY [Option 2– Performance Bond]

FORM No. 7 - ADVANCE PAYMENT SECURITY

FORM No. 8 - RETENTION MONEY SECURITY

FORM No. 9 - BENEFICIAL OWNERSHIP DISCLOSURE FORM

FORM No 1: NOTIFICATION OF INTENTION TO AWARD OF CONTRACT

For the attention of Tenderer's Authorized Representative

This Notification of Award shall be sent to each Tenderer that submitted a Tender and was not successful. Send this Notification to the Tenderer's Authorized Representative named in the Tender Information Form on the format below.

FORMAT

	i)	Name: [insert Authorized Representative's name]		
	ii)	Address: [insert Authorized Representative's Address]		
	iii)	Telephone: [insert Authorized Representative's telephone/fax numbers]		
	iv)	Email Address: [insert Authorized Representative's email address]		
		PORTANT: insert the date that this Notification is transmitted to Tenderers. The Notification must be sent [I Tenderers simultaneously. This means on the same date and as close to the same time as possible.]		
2.	Date	e of transmission: [email] on [date] (local time)		
	This	Notification is sent by (Name and designation)		
3.	<u>Noti</u>	fication of Award		
	i)	Procuring Entity: [insert the name of the ProcuringEntity]		
	ii)	Project: [insert name ofproject]		
	iii)	Contract title: [insert the name of thecontract]		
	iv)	ITT No: [insert ITT reference number from ProcurementPlan]		
		Notification of Intention to Award (Notification) notifies you of our decision to award the above contract. transmission of this Notification begins the Standstill Period. During the Standstill Period, you may:		
4.	Request a debriefing in relation to the evaluation of your tender by submitting a Procurement-related Complaint in relation to the decision to award the contracts.			
	a)	The successful tenderers		
	i)	Name of successful Tender		
	ii)	Address of the successful Tender		
	iii)	Contract price of the successful Tender Kenya Shillings		
		(in words)		
		b) The reasons for your tender being unsuccessful are as follows:		
		c) OtherTenderers		
		nes of all Tenderers that submitted a Tender. If the Tender's price was evaluated include the evaluated price as the Tender price as read out.		

SNo	Name of Tender	Tender Price as read out	Tender's evaluated price (Note a)	One Reason Why Not Evaluated
1				
2				
3				
4				
5				

(Note a) State NE if not evaluated

5. How to request a debriefing

- a) DEADLINE: The dead line to request a debriefing expires at midnight on [insert date] (local time).
- b) You may request a debriefing in relation to the results of the evaluation of your Tender. If you decide to request a debriefing your written request must be made within three (5) Business Days of receipt of this Notification of Intention to Award.
- c) Provide the contract name, reference number, name of the Tenderer, contact details; and address the request for debriefing as follows:
 - i) Attention: [insert full name of person, if applicable]
 - ii) Title/position: [insert title/position]
 - iii) Agency: [insert name of Procuring Entity]
 - iv) Email address: [insert email address]
- d) If your request for a debriefing is received within the 3 Days deadline, we will provide the debriefing within five (3) Business Days of receip tof your request. If we are unable to provide the debriefing within this period, the Standstill Period shall be extended by five (3) Days after the date that the debriefing is provided. If this happens, we will notify you and confirm the date that the extended Standstill Period will end.
- e) The debriefing may be in writing, by phone, video conference call or in person. We shall promptly advise you in writing how the debriefing will take place and confirm the date and time.
- f) If the deadline to request a debriefing has expired, you may still request a debriefing. In this case, we will provide the debriefing as soon as practicable, and normally no later than fifteen (15) Days from the date of publication of the Contract Award Notice.

6. How to make a complaint

- a) Period: Procurement-related Complaint challenging the decision to award shall be submitted by midnight, [insert date] (local time).
- b) Provide the contract name, reference number, name of the Tenderer, contact details; and address the Procurement-related Complaint as follows:
 - i) Attention: [insert full name of person, if applicable]
 - ii) Title/position: [insert title/position]
 - iii) Agency: [insert name of Procuring Entity]
 - iv) Email address: [insert email address]
- c) At this point in the procurement process, you may submit a Procurement-related Complaint challenging the decision to award the contract. You do not need to have requested, or received, a debriefing before making this complaint. Your complaint must be submitted within the Standstill Period and received by us before the Standstill Period ends.
- d) Further information: For more information refer to the Public Procurement and Disposals Act 2015 and its Regulations a vailable from the Website www.ppra.go.ke.

You should read these documents before preparing and submitting your complaint.

- e) There are four essential requirements:
 - i) You must be an 'interested party'. In this case, that means a Tenderer who submitted a Tender in this tendering process and is the recipient of a Notification of Intention to Award.
 - ii) The complaint can only challenge the decision to award the contract.
 - iii) You must submit the complaint within the period stated above.
 - iv) You must include, in your complaint, all of the information required to support your complaint.

7. Standstill Period

- i) DEADLINE: The Standstill Period is due to end at midnight on [insert date] (local time).
- ii) The Standstill Period lasts ten (14) Days after the date of transmission of this Notification of Intention to Award.
- iii) The Standstill Period may be extended as stated in paragraph Section 5(d) above.

If you have any questions regarding this Notification please do not hesitate to contact us. On behalf of the Procuring Entity:

Signature:						
Name:						
Title/position:						
Telephone:						

FORM NO. 2- REQUEST FOR REVIEW

FORM FOR REVIEW (r.203(1))

PUBLIC PROCUREMENT ADMINISTRATIVE REVIEW BOARD
APPLICATION NOOF20
BETWEEN
APPLICANT
AND
RESPONDENT (Procuring Entity)
Request for review of the decision of the
REQUEST FOR REVIEW
I/Wethe above named Applicant(s), of address: Physical addressP. O. Box No
1.
2.
By this memorandum, the Applicant requests the Board for an order/orders that:
1.
2.
SIGNED(Applicant) Dated onday of/20
FOR OFFICIAL USE ONLY Lodged with the Secretary Public Procurement Administrative Review Board onday of20
SIGNED

Board Secretary

FORM NO 3: LETTER OF AWARD

letterhead paper of the Procuring Entity]
[date]
To: [name and address of the Contractor]
This is to notify you that your Tender dated [date] for execution of the [name of the Contract and identification number, as given in the Contract Data] for the Accepted Contract Amount [amoun tin numbers and words] [name of currency], as corrected and modified in accordance with the Instructions to Tenderers, is here by accepted by
You are requested to furnish the Performance Security within in accordance with the Conditions of Contract, using for that purpose, one of the Performance Security Forms included in Section VIII, Contract Forms, of the Tender Document.
Authorized Signature:
Name and Title of Signatory:
Name of Procuring Entity:
Attachment: Contract Agreement:

FORM NO 4: CONTRACT AGREEMENT

		GREEMENT made the day ofof		
Enti	ty"),	of the one part, and		
the	Con	tractor"), of the other part:		
exec	uted	AS the Procuring Entity desires that the Work by the Contractor, and has accepted a Tende d the remedying of any defects there in,	xsknownas or by the Contractor for the exc	should be ecution and completion of these
Гhе	Proc	curing Entity and the Contractor agree as follo	ows:	
		nis Agreement words and expressions shall ha Contract documents referred to.	ave the same meanings as are	respectively assigned to them in
2.		following documents shall be deemed to for eement shall prevail over all other Contract do		as part of this Agreement. This
	a)	theNotification of Award		
	b)	the Form of Tender		
	c)	the addenda Nos(if any)		
	d)	the Special Conditions of Contract		
	e)	the General Conditions of Contract;		
	f)	the Specifications		
	g)	the Drawings; and		
	h)	the completed Schedules and any other doc	cuments forming part of the co	ntract.
3.	In consideration of the payments to be made by the Procuring Entity to the Contractor as specified in the Agreement, the Contractor here by covenants with the Procuring Entity to execute the Works and to remed defects therein in conformity in all respects with the provisions of the Contract.			
4.	of th	Procuring Entity here by covenants to pay the Works and the remedying of defects there is er the provisions of the Contract at the times a	n, the Contract Price or such ot	her sum as may become payable
	INW Law	VITNESS where of the parties here to have ca ys of Kenya on the day, month and year specif	nused this Agreement to be executed above.	ecuted in accordance with the
	Sign	neda nd sealed by		_(for the Procuring Entity)
	Sign	ned and sealed by		(for the Contractor).

FORM NO. 5 - PERFORMANCE SECURITY

[O _]	ion 1 - Unconditional Demand Bank Guarantee]	
[Gı	urantor letterhead]	
Bei	eficiary: [insert name and Address of Procuring Entity]	
Dat	:[Insert date of issue]	
Gu	rantor: [Insert name and address of place of issue, unless indicated in the letterhead]	
1.	We have been informedthat(hereinafter called "the	
	We have been informedthat (hereinafter called "the Contractor") has entered into Contract No dated with (name of	
	Procuring Entity)(the Procuring Entity as the Beneficiary), for the execution of(hereinafter called "the Contract").	
2.	Furthermore, we understand that, according to the conditions of the Contract, a performance guarantee is require	d.
3.	Atthe request of the Contractor, we as Guarantor, here by irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of(in words), such sum being payable in the types and proportions of currencies in which the Contract Price is payable, upon receipt by us of the Beneficiary's complying demand supported by the Beneficiary's statement, whether in the demand it self or in a separate signed document accompanying or identifying the demand, stating that the Applicant is in breach of its obligation(s) under the Contract, without the Beneficiary needing to prove or to show grounds for your demand or the sum specified therein.	
4.	This guarantee shall expire, no later than the	
5.	The Guarantor agrees to a one-time extension of this guarantee for a period not to exceed [six months] [one year], inresponse to the Beneficiary's written request for such extension, such request to be presented to the Guarantor before the expiry of the guarantee."	
	[Name of Authorized Official, signature(s) and seals/stamps]	
	Note: All italicized text (including footnotes) is for use in preparing this form and shall be deleted from the final product.	

¹The Guarantor shall insert an amount representing the percentage of the Accepted Contract Amount specified in the Letter of Acceptance, less provisional sums, if any, and denominated either in the currency of the Contract or a freely convertible currency acceptable to the Beneficiary.

²Insert the date twenty-eight days after the expected completion date as described in GC Clause 11.9. The Procuring Entity should note that in the event of an extension of this date for completion of the Contract, the Procuring Entity would need to request an extension of this guarantee from the Guarantor. Such request must be in writing and must be made prior to the expiration date established in the guarantee.

FORM No. 6- PERFORMANCE SECURITY

[Option 2– Performance Bond]

[Note: Procuring Entities a readvised to use Performance Security – Unconditiona lDemand Bank Guarantee in stead of Performance Bond due to difficulties involved in calling Bond holder to action]

[G	uara	ntor letterhead or SWIFT identifier code]
Be	nefic	iary: [insertnameandAddressofProcuringEntity]
Da	te:	[Insert date of issue]
PE	RFC	DRMANCE BONDNo.:
Gt	ıaraı	ntor: [Insert name and address of place of issue, unless indicated in the letterhead]
1.	Ву	this Bond as Principal (hereinafter called "the Contractor") and as Surety (hereinafter called
	amo typo the	as Surety (hereinafter called e Surety"), are held and firmly bound unto_] as Obligee (hereinafter called "the Procuring Entity") in the bount of for the payment of which sum well and truly to be made in the es and proportions of currencies in which the Contract Price is payable, the Contractor and the Surety bind mselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these sents.
2.	of_ spe	IEREAS the Contractor has entered into a written Agreement with the Procuring Entity dated theday, for in accordance with the documents, plans cifications, and amendments there to, which to the extent here in provided for, are by reference made part here and are here in after referred to as the Contract.
3.	per oth Ent	W, THEREFORE, the Condition of this Obligation is such that, if the Contractor shall promptly and faithfully form the said Contract (including any amendments thereto), then this obligation shall be null and void; erwise, it shall remain in full force and effect. Whenever the Contractor shall be, and declared by the Procuring ity to be, in default under the Contract, the Procuring Entity having performed the Procuring Entity's igations there under, the Surety may promptly remedy the default, or shall promptly:
	a)	Complete the Contract in accordance with its terms and conditions; or
	b)	Obtain a tender or tenders from qualified tenderers for submission to the Procuring Entity for completing the Contract in accordance with its terms and conditions, and upon determination by the Procuring Entity and the Surety of the lowest responsive Tenderers, arrange for a Contract between such Tenderer, and Procuring Entity and make a vailable as work progresses (even though there should be a default or a succession of defaults under the Contract or Contracts of completion arranged under this paragraph) sufficient funds to pay the cost of completion less the Balance of the Contract Price; but not exceeding including other costs and damages for which the Surety may be liable hereunder, the amount set forth in the first paragraph hereof. The term "Balance of the Contract Price," as used in this paragraph, shall mean the total amount payable by Procuring Entity to Contractor under the Contract, less the amount properly paid by Procuring Entity to Contractor; or
	c)	Pay the Procuring Entity the amount required by Procuring Entity to complete the Contract in accordance with its terms and conditions upto a total not exceeding the amount of this Bond.
4.	The	Surety shall not be liable for a greater sum than the specified penalty of this Bond.
5.	Tak oth	v suit under this Bond must be instituted before the expiration of one year from the date of the issuing of the ting-Over Certificate. No right of action shall accrue on this Bond to or for the use of any person or corporation er than the Procuring Entity named here in or the heirs, executors, administrators, successors, and assigns of Procuring Entity.
6.	thes	estimony whereof, the Contractor has here unto set his hand and affixed his seal, and the Surety has caused se presents to be sealed with his corporate seal duly at tested by the signature of his legal representative, this

SIGNED ON	on behalf of	
By	in the capacity of	
Inthepresenceof		
SIGNED ON	on behalf of	
	in the capacity of	

FORM NO. 7 - ADVANCE PAYMENT SECURITY

	[Demand Bank Guarantee] [Guarantor letterhead]		
Beneficiary:		[Insert name and Address of ProcuringEntity]	
		ARANTEE No.: [Insert guarantee reference number]	
Gu	Guarantor: [Insert name and	address of place of issue, unless indicated in the letterhead]	
1.	We have been informed the No		into Contract
2.		nd that, according to the conditions of the Contract, an advance payment is to be made against an advance payment	
3.	or sums not exceeding in receipt by us of the Benedemand itself or in a separate Applicant:	cractor, we as Guarantor, here by irrevocably undertake to pay the Benefic total an amount of(in words	vhether in the either that the
	b) Has failed to repay th	e payment for purposes other than the costs of mobilization in respect of the advance payment in accordance with the Contract conditions, specifying oplicant has failed to repay.	
4.	the Beneficiary's bank sta	rantee may be presented as from the presentation to the Guarantor of a cetting that the advance payment referred to above has been credited to the at	
5.	repaid by the Contractor presented to us. This gua certificate indicating that certified for payment, oro	this guarantee shall be progressively reduced by the amount of the advance as specified in copies of interim statements or payment certificates we wrantee shall expire, at the latest, upon our receipt of a copy of the interiment (90) percent of the Accepted Contract Amount, less provisional sunthe dayof, 2, whiche ad for payment under this guarantee must be received by us at this office	which shall be erim payment ums, has been ever is earlier.
6.		a one-time extension of this guarantee for a period not to exceed [six Beneficiary's written request for such extension, such request to be prery of the guarantee.	
	[Name of Authorized Offic	cial, signature(s) and seals/stamps]	_
	Note: All italicized text (in final product.	ncluding footnotes) is for use in preparing this form and shall be deleted	from the

¹The Guarantor shall insert an amount representing the amount of the advance payment and denominated either in the currency of the advance paymen tas specified in the Contract.

²Insert the expected expiration date of the Time for Completion. The Procuring Entity should note that in the event of an extension of the time for completion of the Contract, the Procuring Entity would need to request an extension of this guarantee from the Guarantor. Such request must be in writing and must be made prior to the expiration date established in the guarantee.

FORM NO. 8 - RETENTION MONEY SECURITY

[Demand Bank Guarantee] [Guarantor letterhead]	
Date:[Insert date of issue]	
Advance payment guarantee no. [Insert guarantee reference number]	
Guarantor: [Insert name and address of place of issue, unless indicated in the letterhead]	
1.	We have been informed that
2.	Furthermore, we understand that, according to the conditions of the Contract, the Beneficiary retains moneys upto the limit set forth in the Contract ("the Retention Money"), and that when the Taking-Over Certificate has been issued under the Contract and the first half of the Retention Money has been certified for payment, and payment of [insert the second half of the Retention Money] is to be made against a Retention Money guarantee.
3.	At the request of the Contractor, we, as Guarantor, hereby irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of <code>[insert amount in figures] ([insert amount in words])^l upon receipt by us of the Beneficiary's complying demands upported by the Beneficiary's statement, whether in the demand itself or in a separate signed document accompanying or identifyingthedemand, stating that the Contractor is in breach of its obligation(s) under the Contract, without your needing to prove or showgrounds for your demand or the sum specified there in.</code>
4.	A demand under this guarantee may be presented as from the presentation to the Guarantor of a certificate from the Beneficiary's bank stating that the second half of the Retention Money as referred to above has been credited to the Contractor on its account numberat[insert name and address of Applicant's bank].
5.	This guarantee shall expire no later than the
6.	The Guarantor agrees to a one-time extension of this guarantee for a period not to exceed [six months] [one year], in response to the Beneficiary's written request for such extension, such request to be presented to the Guarantor before the expiry of the guarantee.
	[Name of Authorized Official, signature(s) and seals/stamps]
	<i>Note:</i> All italicized text (including footnotes) is for use in preparing this form and shall be deleted from the final product.

¹The Guarantor shall insert an amount representing the amount of the second half of the Retention Money.

²Insert a date that is twenty-eight days after the expiry of retention period after the actua lcompletion date of the contract. The Procuring Entity should note that in the event of an extension of this date for completion of the Contract, the Procuring Entity would need to request an extension of this guarantee from the Guarantor. Such request must be in writing and must be made prior to the expiration date established in the guarantee.

FORM NO. 9 BENEFICIAL OWNERSHIP DISCLOSURE FORM

(Amended and issued pursuant to PPRA CIRCULAR No. 02/2022)

INSTRUCTIONS TO TENDERERS: DELETE THIS BOX ONCE YOU HAVE COMPLETED THE FORM

This Beneficial Ownership Disclosure Form ("Form") is to be completed by the successful tenderer pursuant to Regulation 13 (2A) and 13 (6) of the Companies (Beneficial Ownership Information) Regulations, 2020. In case of joint venture, the tenderer must submit a separate Form for each member. The beneficial ownership information to be submitted in this Form shall be current as of the date of its submission.

For the purposes of this Form, a Beneficial Owner of a Tenderer is any natural person who ultimately owns or controls the legal person (tenderer) or arrangements or a natural person on whose behalf a transaction is conducted, and includes those persons who exercise ultimate effective control over a legal person (Tenderer) or arrangement.

Tandan Dafananaa Na	[insert identification no]
Tender Reference No.:	[insert identification no]
Name of the Tender Title/Description:	[insert name of the assignment] to:
[insert comp	plete name of Procuring Entity]
In response to the requirement in your notification additional information on beneficial ownership:options that are not applicable]	of award dated[insert date of notification of award] to furnish[select one option as applicable and delete the

I) We here by provide the following beneficial ownership information.

Details of Beneficial ownership


	Details of all Benefici	al Owners	% of shares a person holds in the company Directly or indirectly	% of voting rights a person holds in the company	Whether a person directly or indirectly holds a right to appoint or remove a member of the board of directors of the company or an equivalent governing body of the Tenderer (Yes / No)	Whether a person directly or indirectly exercises significant influence or control over the Company (tenderer) (Yes / No)
	Full Name		Directly %	Directly	1. Having the right to appoint a majority of	influence or control
1.	National identity card number or Passport number		of shares	rights	the board of the directors or an equivalent governing	over the Company body of the Company (tenderer)
	Personal Identification Number (where applicable)		Indirectly % of shares	Indirectly % of voting rights	body of the Tenderer: YesNo 2. Is this right held directly or indirectly?:	YesNo 2. Is this influence or
	Nationality					control exercised directly or
	Date of birth [dd/mm/yyyy]				Direct	indirectly?
	Postal address				T 1'	
	Residential address				Indirect	Indirect
	Telephone number					
	Email address					
	Occupation or profession					

	Details of all Beneficial Owners	% of shares a person holds in the company Directly or indirectly	% of voting rights a person holds in the company	Whether a person directly or indirectly holds a right to appoint or remove a member of the board of directors of the company or an equivalent governing body of the Tenderer (Yes / No)	Whether a person directly or indirectly exercises significant influence or control over the Company (tenderer) (Yes / No)
2.	Full Name National identity card number or Passport number Personal Identification Number (where applicable) Nationality(ies) Date of birth [dd/mm/yyyy] Postal address Residential address Telephone number Email address Occupation or profession	Directly % of shares Indirectly % of shares	Directly% of voting rights Indirectly% of voting rights	1. Having the right to appoint a majority of the board of the directors or an equivalent governing body of the Tenderer: YesNo 2. Is this right held directly or indirectly?: Direct	1. Exercises significant influence or control over the Company body of the Company (tenderer) YesNo 2. Is this influence or control exercised directly or indirectly? Direct
3. e.t					

- II) Am fully aware that beneficial ownership information above shall be reported to the Public Procurement Regulatory Authority together with other details in relation to contract awards and shall be maintained in the Government Portal, published and made publicly available pursuant to Regulation 13(5) of the Companies (Beneficial Ownership Information) Regulations, 2020.(Notwithstanding this paragraph Personally Identifiable Information in line with the Data Protection Act shall not be published or made public). Note that Personally Identifiable Information (PII) is defined as any information that can be used to distinguish one person from another and can be used to deanonymize previously anonymous data. This information includes National identity card number or Passport number, Personal Identification Number, Date of birth, Residential address, email address and Telephone number.
- III) In determining who meets the threshold of who a beneficial owner is, the Tenderer must consider a natural person who in relation to the company:
 - (a) holds at least ten percent of the issued shares in the company either directly or indirectly;
 - (b) exercises at least ten percent of the voting rights in the company either directly or indirectly;
 - (c) holds a right, directly or indirectly, to appoint or remove a director of the company; or
 - (d) exercises significant influence or control, directly or indirectly, over the company.
- IV) What is stated to herein above is true to the best of my knowledge, information and belief.

Name of the Tenderer:
Name of the person duly authorized to sign the Tender on behalf of the Tenderer: ** [insert complete name of person
duly authorized to sign the Tender]
Designation of the person signing the Tender:[insert complete title of the person signing the Tender]
Signature of the person named above:[insert signature of person whose name and capacity are shown
above]
Date this[insert date of signing] day of[Insert month], [insert year]

Bidder Official Stamp



NOTES

1 The tenderer to note the sensitive nature and security of the works.

The works are to be carried out in a Premise which is OPERATIONAL and in USE.

The Contractor must take steps and exercise such care and diligence as to minimise nuisance from dust, noise or any other cause to the occupiers of the existing and adjacent property. The program of works shall be done after consultation with the Client

2 The tenderer to note that care should be taken to all the existing services, finishes and fittings. Any damage or disturbance caused to any services shall be reported immediately to the Architect and the relevant Client Representative and shall be made good to their satisfaction at the Contractor's expense.

All the furniture and fittings including but not limited to Floor finishes including carpets, wall finishes, lights, AC, grilles, smoke detectors, sprinklers, etc should be covered up, protected and handed over to their original state. The tenderer shall allow for such costs accordingly either in the preliminaries on in his rates

- 3 Job to include cost of labour, materials, scaffolding if any, carting off debris from site, loading, unloading, cleaning, etc
- 4 Care should be taken to ensure that no surfaces of boards are damaged. Incase of any damage, the contractor will bear the cost of replacement
- 5 Any holes to the gypsum to screws are to be duly filled & skimmed with gypsum filler/putty making it ready to receive undercoats for paint.
- 6 These works have been measured gross and over light fittings, AC grilles, smoke detectors, sprinklers, etc
- 7 The measurement includes all the decorative mouldings and curved edges
- 8 The colour to match the existing paint and to be approved by the Project Manager

PREAMBLES AND PRICING NOTES

A. GENERALLY

All work to be carried out in accordance with the Ministry of Roads, Housing & Urban Development and Public Works General Specifications for Building Works issued in 1976 or as qualified or amended below.

B. MANUFACTURERS' NAMES

Where manufacturers' names and catalogue references are given for guidance to quality and standard only, alternative manufacturer of equal quality will be accepted at the discretion of the Project Manager.

C. WALLING

All precast concrete blocks shall be manufactured by the methods and to the sizes specified in the Ministry of Roads, Housing & Urban Development and Public Works "Specification for Metric Sized Concrete Blocks for Building (1972)"

Walling of 100 mm thickness or under shall be reinforced with hoop iron every alternate course.

Prices for walling must allow for all costs in preparing, packing and sending sample blocks for testing as and when required by the Project Manager.

D. CARPENTRY

The grading rules for cypress shall be the same for podocarpus and all timber used for structural work shall be select (second grade).

All structural timber must conform to the minimum requirements for moisture content and preservative treatment and timber prices must allow for preparing, packing and sending samples for testing when required.

Prices must also include for all nails and fasteners.

E. JOINERY

Cypress for joinery shall be second grade in accordance with the latest grading rules of the Kenya Government.

Where Mahogany is specified, this refers to prime grade only. The Contractor may with the approval of the Project Manager; use either Msharagi or Mvuli in lieu of Mahogany but such approval will be given only in the case of shortages of the hardwoods specified.

Plugging shall be carried out by drilling walling or concrete with masonry drill and filling with propriety plugs of the correct sizes. Cutting with hammer and chisel will not be allowed.

Prices for joinery must include for pencil rounded arises, protection against damage, nails, screws, framing and bedding in cement mortar as required.

Sizes given for joinery items are nominal sizes and exact dimensions of doors, etc, must be ascertained on site.

A. IRONMONGERY

Ironmongery shall be specified in the Bills of Quantities or equal and approved.

Prices must include for removing and re-fixing during and after painting, labeling all keys, and for fixing to hardwood, softwood, concrete or blockwork.

Catalogue references given for ironmongery are for purposes of indicating quality and size of item(s). Should the Contractor wish to substitute the specified item(s) with others of equal manufacture, he must inform the Project Manager and obtain approval in writing.

B. STRUCTURAL STEELWORK

All structural steelwork shall comply with the Ministry of Roads, Housing & Urban Development and Public Works "Structural Steelwork Specification (1973) and shall be executed by an approved Sub-contractor.

C. PLASTERWORK AND OTHER FINISHES

All finishing shall be as described in the general specifications and in these Bills of Quantities.

Prices for paving are to include for brushing concrete clean, wetting and coating with cement and sand grout 1:1.

Rates for glazed wall tiling are to include for a 12 mm cement and sand (1:4) backing screed unless otherwise specified in these Bills of Quantities.

D. GLAZING

Where polished plate glass is specified, this refers to general glazing quality.

Prices for glazing shall include for priming of rebates before placing putty.

The Contractor will be responsible for replacing any broken or scratched glass and handing over in perfect condition.

E. PAINTING

Painting shall be applied in accordance with the manufacturers' instructions.

Prices for painting are to include for scaffolding, preparatory work, priming coats, protection of other works and for cleaning up on completion. Prices for painting on galvanized metal are to include for mordant solution as necessary.

F. TILES - CERAMIC, PORCELEIN, GRANITO ETC

No tiles shall be fitted/installed without sample approvals.


No claim shall be allowed on the grounds that the bidder priced an inferior quality

G. CURTAINS & COVERS ETC

The bidder shall be deemed to have priced the best materials

No curtains & covers shall be fitted/installed without sample approvals.

No claim shall be allowed on the grounds that the bidder priced an inferior quality



BILL NO. 1 - PARTICULAR PRELIMINARIES

ITEM	DESCRIPTION	AMOUNT (KSH)
	BILL NO.1:	
	PARTICULAR PRELIMINARIES	
Α	EMPLOYER	
	The Employer is STATE DEPARTMENT FOR FISHERIES. The term "Employer" and "Government" wherever used in the contract document shall be synonymous.	
В	PROJECT MANAGER	
	The term "PM" wherever used in these Bills of Quantities shall be deemed to mean the "The Engineer" as per Condition 1 of the Conditions of Contract or such person or persons as may be duly authorised to represent him on behalf of the Government.	
C	ARCHITECT	
	The term "Architect" shall be deemed to mean "The P.M " as defined above whose address unless otherwise notified is Ministry of Lands, Public Works, Housing and Urban Development. P.O Box 30743 -00100, NAIROBI.	
D	QUANTITY SURVEYOR	
	The term "Quantity Surveyor" shall be deemed to mean "The P.M " as defined above whose address unless otherwise notified is Ministry of Lands, Public Works, Housing and Urban Development, P.O Box 30743-00100, NAIROBI.	
Е	ELECTRICAL ENGINEER	
	The term "Electrical Engineer" shall be deemed to mean "The P.M " as defined above whose address unless otherwise notified is Ministry of Lands, Public Works, Housing and Urban Development, P.O Box 30743-00100, NAIROBI.	
F	MECHANICAL ENGINEER	
	The term "Mechanical Engineer" shall be deemed to mean "The P.M " as defined above whose address unless otherwise notified is Ministry of Lands, Public Works, Housing and Urban Development, P.O Box 30743-00100, NAIROBI.	
G	STRUCTURAL ENGINEER	
	The term "Structural Engineer" shall be deemed to mean "The P.M " as defined above whose address unless otherwise notified is Ministry of Lands, Public Works, Housing and Urban Development, Directorate of Public Works, P.O Box 30743 - 00100, NAIROBI.	
Н	CHIEF DESIGNER	
	The term "Chief Designer" shall be deemed to mean "The P.M " as defined above whose address unless otherwise notified is Ministry of Lands, Public Works, Housing and Urban Development, Directorate of Public Works, P.O Box 30743 - 00100, NAIROBI.	

Carried to Particular Preliminaries collection

ITEM	DESCRIPTION	AMOUNT (KSH)
Α	PRICING ITEMS OF PRELIMINARIES	
	Prices SHALL BE INSERTED against items of "preliminaries" in the tenderer's priced Bills of Quantities. The contractor is advised to read and understand all preliminary items.	
В	SCOPE OF CONTRACT	
	The works to be carried out comprise of REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY .	
C	DESCRIPTION OF THE WORKS	
	The Works consist of: Demolition of Existing Floor Finishes, Partitions and Ceiling Works, Construction of new framed partitions, Floor Finishes, Ceiling Finishes, Painting and Decorating, Branding Works, Electrical Services and Mechanical Services.	
	Approx. Floor Area = 600 SM	
D	MEASUREMENTS	
	In the event of any discrepancies arising between the Bills of Quantities and the actual works, the site measurements shall generally take precedence. However, such discrepancies between any contract documents shall immediately be referred to the PROJECT MANAGER in accordance with the Conditions of Contract. The discrepancies shall then be treated as a variation and be dealt with in accordance with the said Conditions.	
	All measurements shall be as per Standard Method of Measurements (SMM) - 2008 Edition	
	Carried to Particular Preliminaries collection	

ITEM	DESCRIPTION	AMOUNT (KSH)
Α	LOCATION OF SITE	
	The site of the proposed works is 4.1 Kilometres from the Nairobi Central Business District ON 3RD FLOOR, WORKS BUILDING ALONG NGONG ROAD, NAIROBI COUNTY, KENYA. The Contractor is advised to visit the site to familiarize with the nature and position of the site. No claims arising from the Contractor's failure to do so will be entertained.	
В	SIGNING OF THE TENDER DOCUMENTS	
	The bidder shall append his / her signature and / or company's rubberstamp on each and every page of tender document.	
С	DEMOLITIONS AND ALTERATIONS	
	The Contractor is to allow for all temporary protection required during the works including ordinary and special dust screens, hoardings, barriers, warning signs, etc as directed by the Project Manager and as necessary for the adequate propping and protection of existing property, finishes, workmen employed on the site, employer's agents and the public. Any damage or loss incurred due to the insufficiency of such protection must be made good by the Contractor. All protective devices are to be removed on completion of the works and any necessary making good consequent upon this is to be excecuted to the satisfaction of the Project Manager.	
	The works shall be propped, strutted and supported as necessary before any alteration or demolition work commences. Prices shall include for all cleaning and preparatory work to structure and finishes and for making good to all finishes on completion whether or not specifically described.	
	Unless described as set aside for re-use all arising debris and surplus materials shall be carefully removed from building and carterd away from site.	
	The Contractor shall be entirely responsible for any breakage or damage which may occur to materials required for re-use during their removal unless it is certified by the Project Manager that such damage or breakage was inevitable as a result of the condition of the item concerned.	
	Carried to Particular Preliminaries collection	

ITEM	DESCRIPTION	AMOUNT (KSH)
Α	CLEARING AWAY	
	The Contractor shall remove all temporary works, rubbish, debris and surplus materials from the site as they accumulate and upon completion of the works, remove and clear away all plant, equipment, rubbish, unused materials and stains and leave in a clean and tidy state to the reasonable satisfaction of the Project Manager.	
	The whole of the works shall be delivered up clean, complete and in perfect condition in every respect to the satisfaction of the Project Manager.	
В	CLAIMS It shall be a condition of this contract that upon it becoming reasonably apparent to the Contractor that he has incurred losses and / or expenses due to any of the contract conditions, or by any other reason whatsoever, he shall present such a claim or intent to claim notice to the PROJECT MANAGER within the contract period. No claim shall be entertained upon the expiry of the said contract period.	
С	PAYMENTS	
	The tenderer's attention is drawn to the fact that the GOVERNMENT DOES NOT MAKE ADVANCE PAYMENTS but pays for work done and materials delivered to sit: Refer with Special Conditions of Contract. In order to facilitate this, a list of the general component elements for the works is given at the summary page of these specifications and the tenderer is requested to break down his tender sum commensurate to the said elements.	
D	PREVENTION OF ACCIDENT, DAMAGE OR LOSS	
	The Contractor is notified that these works are to be carried out on a restricted site where the client is going on with other nomal activities. The Contractor is thus instructed to take reasonable care in the execution of the works as to prevent accidents, damage or loss and disruption of activities being carried out by the Client. The Contractor shall allow in his rates any expense he deemed necessary by taking such care within the site.	
Е	WORKING CONDITIONS	
	The Contractor shall allow in his rates for any interferance that he may encounter in the course of the works for the Client may in some cases ask the Contractor not to proceed with the works until some activities within the site are completed, as the facility will be operating as usual during the course of the contract.	
F	SIGNBOARD	
	Allow for providing, erecting, maintaining throughout the course of the Contract and afterwards clearing away a signboard as designed, specified and approved by the Project Manager.	
	The signboard shall give a brief title of the project and image	
	The Signboard and lettering on same for the display of the General and Sub-Contractors' names shall be of an approved size with the Employer's name painted thereon. The Project Manager, and other Consultants' names shall be printed in 50 mm letters all to the Architect's approved design.	
	No other signboard or advertising will be permitted without prior permission from the Architect.	
G	LABOUR CAMPS The Contractor shall not be allowed to house labour on site. Allow for transporting workers to and from the site during the tenure of the contract.	
	Carried to Particular Proliminaries collection	
	Carried to Particular Preliminaries collection	

	DESCRIPTION	AMOUNT (KSH)
Α	MATERIALS FROM DEMOLITIONS	
	Any materials arising from demolitions and not re-used shall become the property of the client. The Contractor shall allow in his rates the cost of disposing the demolished materials as directed.	
В	PRICING RATES	
	The tenderer shall include for all costs in executing the whole of the works, including transport, replacing damaged items, fixing, all to comply with the said Conditions of Contract.	
C	SECURITY	
	The Contractor shall allow for providing adequate security for the works and the workers in the course of execution of this contract. No claim will be entertained from the Contractor for not maintaining adequate security for both the works and workers.	
D	URGENCY OF THE WORKS	
	The Contractor is notified that these "works are urgent" and should be completed within the period stated in these Particular Preliminaries. The Contractor shall allow in his rates for any costs he/ she deems that he/she may incur by having to complete these works within the stipulated contract period.	
Е	PAYMENT FOR MATERIALS ON SITE	
	All materials for incorporation in the works must be stored on site before payment is effected, unless specifically exempted by the Project Manager. This is to include materials of the Contractor, nominated sub-Contractors and nominated suppliers.	
F	EXISTING SERVICES	
	Prior to the commencement of any work, the Contractor is to ascertain from the relevant authority the exact position, depth and level of all existing services in the area and he/she shall make whatever provisions may be required by the authorities concerned for the support, maintenance and protection of such services.	
G	CONTRACT COMPLETION PERIOD	
	The contract completion period in accordance with the Conditions of contract must be adhered to.	
	The 'PROJECT MANAGER' shall strictly monitor the Contractors progress in relation to the progress chart and should it be found necessary the 'PROJECT MANAGER' shall inform the Contractor in writing that his actual performance on site is not satisfactory. In all such cases the Contractor shall accelerate his rate of performance production and progress by all means such as additional labour, plant, e.t.c and working overtime all at his cost.	

ITEM	DESCRIPTION	AMOUNT (KSH)
Α	PERFORMANCE BOND	
	A bond of 5% of the contract sum will be required in accordance with the Special Conditions of Contract on award of contract. No payment on account for the works executed will be made to the contractor until he has submitted the Performance Bond to the Project Manager duly signed, sealed and stamped from an approved Bank.	
В	TENDER DOCUMENTS	
	Tender documents are as listed in Page (i) of the Tender Document.	
С	DELIVERY OF TENDER	
	Tenders and all documents in connection therewith, as specified above must be delivered in the addressed envelope which should be properly sealed and deposited at the offices as specified in the letter accompanying these documents or as indicated in the advertisement. Tenders will be opened at the time specified in the letter accompanying these Tender Documents or as indicated in the advertisement. Tenders delivered/received later than the above time will not be opened.	
D	VALUE ADDED TAX	
	The Contractor's attention is drawn to the Legal Notice in the Finance Act part 3 Section 21(b) operative from 1 st September, 1993 which requires payment of VAT on all contracts. The Contractor should therefore include allowance in his rates and prices for prices for VAT and any other Government taxes currently in force.	
	The tenderer is advised that in accordance with Government public notice No. 35 & 36 Dated 11 th September 2003 operational from 1 st October 2003, VAT will be deducted against the contract sum at the prevailing rate by the Employer and remitted directly to the Commissioner of VAT through all interim certificates. It should however be noted that this is not additional tax but a new mode of payment for VAT, any excess payment will be refundable once the Contractor has submitted monthly returns to the Commissioner of VAT who will do the refunds when satisfied that the VAT regulations have been complied with.	
	NB : The Contractor should therefore include the VAT tax within the rates.	
	Carried to Particular Preliminaries collection	

PROPOSED REORGANISATION OF 3RD FLOOR WORKS BUILDING, NAIROBI COUNTY.

ITEM	DESCRIPTION	AMOUNT (KSH)
	SPECIAL PRELIMINARIES	
	PROJECT MANAGEMENT EXPENSES	
Α	Allow a sum of Kenya Shillings One Million Five Hundred Thousand (KShs.1,500,000.00)	1,500,000.00
	only for Project Management Expenses for the duration of the contract period.	, ,
В	Allow for Contractor's profit and overheads (%)	
b	Allow for Contractor's profit and overficads (70)	
	Carried to Particular Preliminaries collection	

М	DESCRIPTION	AMOUNT (KSH)
PARTICULARS OF INSERTIONS AGREEMENT	S TO BE MADE IN APPENDIX TO CONTRACT	
The following are the insertions	to be made in the appendix to the Contract Agreement: -	
Period of Final Measurement	3 Months From Practical completion	
Defects Liability Period	6 Months from Practical completion	
Date for Possession	To be agreed with the Project Manager	
Working Hours	24 Hours	
Date for Completion	As Stated in the Special Conditions of Contract	
Liquidated and Ascertained Da	mages - As Stated in Special Conditions of Contract	
Period of Interim Certificates	Monthly	
Period of Honouring Certificate	60 days as per Conditions of contract [14.7.1]	
Percentage of Certified Value R	etained 10%	
Limt of Retention Fund	5%	
Carried to Particular Preliminar	ies collection	

ITEM	DESCRIPTION	AMOUNT (KSH)
	COLLECTION	
	Brought forward from page PP/1	
	D 116 DD0	
	Brought forward from page PP/2	
	Brought forward from page PP/3	
	Brought forward from page PP/4	
	Brought forward from page PP/5	
	Brought forward from page PP/6	
	Brought forward from page PP/7	
	broaght forward from page 1177	
	Brought forward from page PP/8	
	TOTAL FOR PARTICULAR PRELIMINARIES CARRIED TO GRAND SUMMARY	

BILL NO. 2 - GENERAL PRELIMINARIES

ITEM		DESCRIPTION	AMOUNT (KSH)			
	BILL NO. 2					
	GENERAL PR	ELIMINARIES				
A.	PRICING OF	ITEMS OF PRELIMINARIES AND PREAMBLES				
	Prices will be Specification.	inserted against items of Preliminaries in the Contractor's priced Bills of Quantities and				
	The Contractor shall be deemed to have included in his prices or rates for the various items in the Bills of Quantities or Specification for all costs involved in complying with all the requirements for the proper execution of the whole of the works in the Contract.					
В.	ABBREVIATIO	ONS				
	Throughout the follows:-	hese Bills, units of measurement and terms are abbreviated and shall be interpreted as				
	с.м.	Shall mean cubic metre				
	S.M.	Shall mean square metre				
	L.M.	Shall mean linear metre				
	мм	Shall mean Millimetre				
	Kg.	Shall mean Kilogramme				
	No.	Shall mean Number				
	Prs.	Shall mean Pairs				
	B.S. Standards	Shall mean the British Standard specification Published by the British Institution, 2 Park Street, London W.I., England.				
	Ditto the description	Shall mean the whole of the preceding description except as qualified in n in which it occurs.				
	m.s.	Shall mean measured separately.				
	a.b.d	Shall mean as before described.				
	Carried to Co	eneral Preliminaries collection				
<u> </u>	Sairieu lo Ot	eneral i rediffiliaries conection				

ITEM	DESCRIPTION	AMOUNT (KSH)
Α.	EXCEPTION TO THE STANDARD METHOD OF MEASUREMENT Attendance; Clause B19(a) of the Standard Method of Measurement is deleted and the following clause is substituted:-	
	Attendance on nominated Sub-Contractors shall be given as an item in each case shall be deemed to include: allowing use of standing scaffolding, mess rooms, sanitary accommodation and welfare facilities; provision of special scaffolding where necessary; providing space for office accommodation and for storage of plant and materials; providing light and water for their work: clearing away rubbish; unloading checking and hoisting: providing electric power and removing and replacing duct covers, pipe casings and the like necessary for the execution and testing of Sub-Contractors' work and being responsible for the accuracy of the same.	
	Fix Only:- "Fix Only" shall mean take delivery at nearest railway station (Unless otherwise stated), pay all demurrage charges, load and transport to site where necessary, unload, store, unpack, assemble as necessary, distribute to position, hoist and fix only.	
	FORM OF CONTRACT The Form of Contract shall be as stipulated in the Republic of Kenya's Standard Tender Document - Tender Documents for Small Works (2021 Edition) included herein:	
С	PLANT, TOOLS AND VEHICLES	
	Allow for providing all scaffolding, plant, tools and vehicles required for the works except in so far as may be stated otherwise herein and except for such items specifically and only required for the use of nominated Sub-Contractors as described herein. No timber used for scaffolding, formwork or temporary works of any kind shall be used afterwards in the permanent work.	
	The Contractor shall provide all necessary hoists, tackle, plant, vehicles, tools and appliances of every description for the due and satisfactory completion of the Works and shall remove same on completion.	
	All materials and workmanship used in the execution of the works shall be of the best quality and description for the due and satisfatory completion of the works and shall remove the same on completion.	
	The Contractor shall provide, erect and maintain all temporary scaffolding, sufficiently strong and efficient for the due performance of the Works, including Sub-contract Works, provide special scaffolding as and when required during the Works including all sub-contracted works and remove on completion and make good.	
	Such scaffolding shall be constructed of tubular steel or timber of sufficient scantlings and be provided with planked footways and guard-rails to approval. No timber used for scaffolding formwork or similar temporary works shall be used afterwards in the permanent work.	
	All such plant, tools and scaffolding shall comply with all regulations whether general or local, in force throughout the period of the Contract and shall be altered or adapted during the Contract as may be necessary to comply with any amendments in or additions to such regulations.	
	Scaffolding is not measured hereinafter, and the Contractor must allow here or in his rates for the above.	
D	TRANSPORT.	
	Do not allow for transport of workmen, materials, etc., to and from the site at such hours and by such routes as may be permitted by the competent authorities.	
	Carried to General Preliminaries collection	

ITEM DESCRIPTION AMOUNT (KSH) MATERIALS AND WORKMANSHIP. All materials and workmanship used in the execution of the work shall be of the best quality and description unless otherwise stated. The Contractor shall order all materials to be obtained from overseas immediately after the Contract is signed and shall also order materials to be obtained from local sources as early as necessary to ensure that they are onsite when required for use in the works. The Bills of Quantities shall not be used for the purpose of ordering materials. SIGN FOR MATERIALS SUPPLIED. The Contractor will be required to sign a receipt for all articles and materials supplied by the PROJECT MANAGER at the time of taking deliver thereof, as having received them in good order and condition, and will thereafter be responsible for any loss or damage and for replacements of any such loss or damage with articles and/or materials which will be supplied by the PROJECT MANAGER at the current market prices including Customs Duty and V.A.T., all at the Contractor's own cost and expense, to the satisfaction of the PROJECT MANAGER. C STORAGE OF MATERIALS The Contractor shall provide at his own risk and cost where directed on the site weather proof lock-up sheds and make good damaged or disturbed surfaces upon completion to proof lock-up sheds and make good damaged or disturbed surfaces upon completion to the satisfaction of the PROJECT MANAGER Nominated Sub-Contractors are to be made liable for the cost of any storage accommodation provided especially for their use. D SAMPLES The Contractor shall furnish at his own cost any samples of materials or workmanship including concrete test cubes required for the works that may be called for by the PROJECT MANAGER for his approval until such samples are approved by the PROJECT MANAGER and the PROJECT MANAGER, may reject any materials or workmanship not in his opinion to be up to approved samples. The PROJECT MANAGER shall arrange for the testing of such materials as he may at his discretion deem desirable, but the testing shall be made at the expense of the Contractor and not at the expense of the PROJECT MANAGER. The Contractor shall pay for the testing in accordance with the current scale of testing charges laid down by the Ministry of Public Works. The procedure for submitting samples of materials for testing and the method of marking for identification shall be as laid down by the PROJECT MANAGER The Contractor shall allow in his tender for such samples and tests except those in connection with nominated sub-contractors' work. No alternte rate shall be offered on account that the employer has chosen a superior finish unless the bidder had attached the sample he priced. SETTING OUT Ε The contractor shall set out the works according to drawings and shall be responsible for its correctness and shall be required to amend any errors arising from inaccurate settting out at his own cost and expense. Any discrepancies on the dimensions or levels marked on the drawingsshould be reported to the architect for their immediate attention and the contractor shall only proceed after the architect's instructions to adjust the same. No claim for extra time, expense or relief fom provisions of the conditions of the contract may be made there after Before any works are commenced by sub-contractors or specialist, dimensions must be checked by and agreed with the contractor. The contractor shall be responsible for the accuracy of such dimensions. Carried to General Preliminaries collection

ITEM	DESCRIPTION	AMOUNT (KSH)
A	GOVERNMENT ACTS REGARDING WORK, PEOPLE ETC.	
	Allow for complying with all Government Acts, Orders and Regulations in connection with the employment of Labour and other matters related to the execution of the works. In particular the Contractor's attention is drawn to the provisions of the Factory Act 1950 and his tender must include for all costs arising or resulting from compliance with any Act, Order or Regulation relating to Insurances, pensions and holidays for workpeople or so the safety, health and welfare of the work people.	
	The Contractor must make himself fully acquainted with current Acts and Regulations, including Police Regulations regarding the movement, housing, security and control of labour, labour camps, passes for transport, etc. It is most important that the Contractor, before tendering, shall obtain from the relevant Authority the fullest information regarding all such regulations and/or restrictions which may affect the organisation of the works, supply and control of labour, etc., and allow accordingly in his tender. No claim in respect of want of knowledge in this connection will be entertained.	
В	SECURITY OF WORKS ETC.	
	The Contractor shall be entirely responsible for the security of all the works stores, materials, plant, personnel, etc., both his own and sub-contractors' and must provide all necessary watching, lighting and other precautions as necessary to ensure securityagainst theft, loss or damage and the protection of the public.	
С	PUBLIC AND PRIVATE ROADS.	
	Maintain as required throughout the execution of the works and make good any damage to public or private roads arising from or consequent upon the execution of the works to the satisfaction of the local and other competent authority and the PROJECT MANAGER.	
D	EXISTING AND ADJACENT PROPERTY	
	The Contractor shall take every precaution to avoid damage to all existing property including roads, cables, drains and other services and he will be held responsible for and shall make good all such damage arising from the execution of this contract at his own expense to the satisfaction of the PROJECT MANAGER	
	The Contractor will be held fully responsible for the safety of the existing and adjacent buildings and for any damage caused in consequence of these Works. They must reinstate all damages at his own expense and indemnify the Employer against any loss. There are exisiting paving blocks that may be damaged in course of the works and as such the contractor is adviced to include in their rates the cost of making good such	
	The Contractor must take such steps and exercise such care and diligence as to minimise nuisance from dust, noise or any other cause to the occupiers of the existing and adjacent property.	
	Carried to General Preliminaries collection	

	A TO BE OCCUPIED BY THE CONTRACTOR	
The a	area of the site which may be occupied by the Contractor for use of storage and for the ose of erecting workshops, etc., shall be defined on site by the PROJECT MANAGER	
The dinspe	contractor to allow for provision of snacks and soft drinks to participants during site actions and meetings	
The e	entire site is a non-smoking area.	
Carri	ied to General Preliminaries collection	

ITEM	DESCRIPTION	AMOUNT (KSH)
A	WATER AND ELECTRICITY SUPPLY FOR THE WORKS	l
	The Contractor shall provide at his own risk and cost all necessary water, electric light and power required for use in the works. The Contractor must make his own arrangements for connection to the nearest suitable water main and for metering the water used. He must also provide temporary tanks and meters as required at his own cost and clear away when no longer required and make good on completion to the entire satisfaction of the PROJECT MANAGER. The Contractor shall pay all charges in connection herewith. No guarantee is given or implied that sufficient water will be available from mains and the Contractor must make his own arrangements for augmenting this supply at his own cost. Nominated Subcontractors are to be made liable for the cost of any water or electric current used and for any installation provided especially for their own use.	
В	SUPERVISION AND WORKING HOURS The works shall be executed under the direction and to the entire satisfaction in all respects of the PROJECT MANAGER who shall at all times during normal working hours have access to the works and to the yards and workshops of the Contractor and sub-Contractors or other places where work is being prepared for the contract.	
С	PROVISIONAL SUMS. The term "Provisional Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7(i) of the Standard Method of Measurement. Such sums are net and no addition shall be made to them for profit.	
D	PRIME COST (OR P.C.) SUMS.	l
	The term "Prime Cost Sum" or "P.C. Sum" wherever used in these Bills of Quantities shall have the meaning stated in Section A item A7 (ii) of the Standard Method of Measurement. Persons or firms nominated by the PROJECT MANAGER to execute work or to provide and fix materials or goods as stated in the Conditions of Contract are described herein as Nominated Sub-Contractors. Persons or firms so nominated to supply goods or materials are described herein as Nominated Suppliers.	
Е	PROGRESS CHART.	l
	The Contractor shall provide within two weeks of Possession of Site and in agreement with the PROJECT MANAGER a Progress Chart for the whole of the works including the works of Nominated Sub-Contractors; one copy to be handed to the PROJECT MANAGER and a further copy to be retained on Site. Progress to be recorded and chart to be amended as necessary as the work proceeds.	
	At the end of each month, the contractor shall incorporate actual start and finish dates into the time schedule and produce an update on the programme. The update is to show actual start and finish dates, identify out sequence of activities, critical acivities and any constraints which may have or may affect the progress of the works.	
F	ADJUSTMENT OF P.C. SUMS.	l
	In the final account all P.C. Sums shall be deducted and the amount properly expended upon the PROJECT MANAGER'S order in respect of each of them added to the Contract sum. The Contractor shall produce to the PROJECT MANAGER such quotations, invoices or bills, properly receipted, as may be necessary to show the actual details of the sums paid by the Contractor. Items of profit upon P.C. Sums shall be adjusted in the final account pro-rata to the amount paid. Items of "attendance" (as previously described) following P.C. Sums shall be adjusted pro-rata to the physical extent of the work executed (not pro-rata to the amount paid) and this shall apply even though the Contractor's priced Bill shows a percentage in the rate column in respect of them.	
	Should the Contractor be permitted to tender and his tender be accepted of any work for which a P.C. Sum is included in these Bill of Quantities profit and attendance will be allowed at the same rate as it would be if the work were executed by a Nominated Sub-Contractor.	
	Carried to General Preliminaries collection	

ITEM	DESCRIPTION	AMOUNT (KSH)
Α	NOMINATED SUB-CONTRACTORS	
	When any work is ordered by the PROJECT MANAGER to be executed by nominated sub-contractors, the Contractor shall enter into sub-contracts as described in the Conditions of Contract and shall thereafter be responsible for such sub-contractors in every respect. Unless otherwise described the Contractor is to provide for such Sub-Contractors any or all of the facilities described in these Preliminaries. The Contractor should price for these with the nominated Sub-contract Contractor's work concerned in the P.C. Sums under the description "add for Attendance".	
В	DIRECT CONTRACTS	
	Notwithstanding the foregoing conditions, the Government reserves the right to place a "Direct Contract" for any goods or services required in the works which are covered by a P.C. Sum in the Bills of Quantities and to pay for the same direct. In any such instances, profit relative to the P.C. Sum the priced Bills of Quantities will be adjusted as described for P.C. Sums and allowed.	
С	ATTENDANCE UPON OTHER TRADESMEN, ETC.	
	The Contractor shall allow for the attendance of trade upon trade and shall afford any tradesmen or other persons employed for the execution of any work not included in this Contract every facility for carrying out their work and also for use of his ordinary scaffolding. The Contractor, however, shall not be required to erect any special scaffolding for them. The Contractor shall perform such cutting away for and making good after the work of such tradesmen or persons as may be ordered by the PROJECT MANAGER and the work will be measured and paid for to the extent executed at rates provided in these Bills.	
D	REMOVAL OF RUBBISH	
	Removal of rubbish and debris from the Building and the site as it accumulates and at he completion of the works and removal all plant, scaffolding and unused materials at completion.	
Е	INSURANCE	
	The Contractor shall insure as required in the Conditions of Contract. No payment on account of the work executed will be made to the Contractor until he has satisfied the PROJECT MANAGER either by production of an Insurance Policy or and Insurance Certificate that the provision of the foregoing Insurance Clauses have been complied with in all respects. Thereafter the PROJECT MANAGER shall from time to time ascertain that premiums are duly paid up by the Contractor who shall if called upon to do so, produce the receipted premium renewals for the PROJECT MANAGER's inspection.	
F	PROVISIONAL WORK	
	All work described as "Provisional" in these Bills of Quantities is subject to remeasurement in order to ascertain the actual quantity executed for which payment will be made. All "Provisional" and other work liable to adjustment under this Contract shall left uncovered for a reasonable time to allow all measurements needed for such adjustment to be taken by the PROJECT MANAGER Immediately the work is ready for measuring, the Contractor shall give notice to the PROJECT MANAGER so directs uncover the work to enable all measurements to be taken and afterwards reinstate at his own expense.	
	Carried to General Preliminaries collection	

ITEM	DESCRIPTION	AMOUNT (KSH)
	ALTERATIONS TO DUIS DRIGING TO	
Α	ALTERATIONS TO BILLS, PRICING, ETC.	
	Any unauthorised alteration or qualification made to the text of the Bills of Quantities may cause the Tender to be disqualified and will in any case be ignored. The Contractor shall be deemed to have made allowance in his prices generally to cover any items against which no price has been inserted in the priced Bills of Quantities. All items of measured work shall be priced in detail and the Tenders containing Lump Sums to cover trades or groups of work must be broken down to show the price of each item before they will be accepted.	
В	PROTECTION OF THE WORKS.	
	Provide protection of the whole of the works contained in the Bills of Quantities, including casing, casing up, covering or such other means as may be necessary to avoid damage to the satisfaction of the PROJECT MANAGER and remove such protection when no longer required and make good any damage which may nevertheless have been done at completion free of cost to the Government.	
C	WORKS TO BE DELIVERED UP CLEAN	
	Clean and flush all gutters, rainwater and waste pipes, manholes and drains, wash (except where such treatment might cause damage) and clean all floors, sanitary fittings, glass inside and outside and any other parts of the works and remove all marks, blemishes, stains and defects from joinery, fittings and decorated surfaces generally, polish door furniture and bright parts of metalwork and leave the whole of the buildings watertight, clean, perfect and fit for occupation to the approval of the PROJECT MANAGER.	
D	GENERAL SPECIFICATION.	
	For the full description of materials and workmanship, method of execution of the work and notes for pricing, the Contractor is referred to the Ministry of Roads and Public Works and Housing General Specification dated 1976 or any subsequent revision thereof which is issued as a separate document, and which shall be allowed in all respects unless it conflicts with the General Preliminaries, Trade Preambles or other items in these Bills of Quantities.	
	Carried to General Preliminaries collection	

ITEM	DESCRIPTION	AMOUNT (KSH)
A	TRAINING LEVY	
	The Contractor's attention is drawn to the legal notice which requires payment by the Contractor of a Training Levy at the rate of 1/4 % of the Contract sum on all contracts of more than KShs. 1,000,000.00 in value.	
В	MATERIALS ON SITE	
	All materials for incorporation in the works must be stored on or adjacent to the site before payment is effected unless specifically exempted by the PROJECT MANAGER. This includes the materials of the Main Contractor, Nominated Sub-Contractors and Nominated Suppliers.	
С	CONTRACTOR'S SUPERINTENDENCE/SITE AGENT	
	The Contractor shall constantly keep on the works a literate English speaking Agent or Representative, competent and experienced in the kind of work involved who shall give his whole experience in the kind of work involved and shall give his whole time to the superintendence of the works. Such Agent or Representative shall receive on behalf of the Contractor all directions and instructions from the Project Manager and such directions shall be deemed to have been given to the Contractor in accordance with the Conditions of Contract.	
D	PROTECTIVE CLOTHING	
	The Contractor shall provide all protective or any other special clothing or equipment for their employees that may be necessary.	
	These shall include, inter-alia, safety helmets, gloves, goggles, earmuffs, gumboots, steel toed boots,. overalls, etc according to the type of work. The Contractor shall ensure that all safety and protective gear are worn by all staff on site at all times	
	Carried to General Preliminaries collection	
<u> </u>	Carried to Control of Community Controllors	

DESCRIPTION	AMOUNT (KSH)
COLLECTION	
Brought Forward From Page GP/1	
Brought Forward From Page GP/2	
Brought Forward From Page GP/3	
Brought Forward From Page GP/4	
Brought Forward From Page GP/5	
Prought Forward From Page C.D/6	
brought forward from rage Gr/o	
D 115 15 D 607	
Brought Forward From Page GP/7	
Brought Forward From Page GP/8	
Brought Forward From Page GP/9	
GENERAL PRELIMINARIES CARRIED TO GRAND SUMMARY	
	COLLECTION Brought Forward From Page GP/1 Brought Forward From Page GP/2 Brought Forward From Page GP/3 Brought Forward From Page GP/4 Brought Forward From Page GP/5 Brought Forward From Page GP/6 Brought Forward From Page GP/7 Brought Forward From Page GP/7



ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT ((SH)
	BILL NO.3: BUILDER'S WORKS					
	Element No.1: Demolitions and Alterations All demolitions must be carried out with utmost care to avoid damage					
	to adjoining works. All salvaged materials shall become the property of the Client and must not be removed from site without their express permission in writing.					
	Existing Drywall Partitions					
Α	Carefully demolish existing 3000mm high drywall partition complete with frames, boards and all associated accessories fixed to existing wall and floor slab, make good disturbed areas to receive new works and cart away arising debris (Approximately 165sm.)	ITEM				
В	Existing Masonry Walling Carefully demolish existing 2700mm high Masonry walling complete with plaster, paint and all associated accessories fixed to existing wall and floor slab, make good disturbed areas to receive new works and cart away arising debris (Approximately 120sm.)	ITEM				
	Existing Doors					
С	Carefully remove existing 900 x 2100mm high single leaf Timber door complete with frame including iron mongery and fixed to plastered and painted masonry wall, make good disturbed areas to receive new works and cart away arising debris (Approximately 12no.)	ITEM				
D	Carefully remove existing 1200 x 2100mm high single leaf Timber door complete with frame including iron mongery and fixed to plastered and painted masonry wall, make good disturbed areas to receive new works and cart away arising debris (Approximately 5no.)	ITEM				
	Total Carried to Demolitions and Alterations Collection Page					

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Demolitions and Alterations Cont'd				
А	Existing Wall Finishes Carefully demolish existing wall tiles/wall finish on and including cement/sand backing and prepare wall, make good disturbed areas to receive new works and cart away arising debris (Approximately 310sm.)	ITEM			
	Existing Floor Finishes				
В	Carefully demolish existing Floor finish on and including cement/sand screed and prepare floor make good disturbed areas to receive another finish and cart away arising debris (Approximately 545sm.)	ITEM			
С	Carefully demolish existing Floor Skirting on and including cement/sand screed and prepare surface, make good disturbed areas to receive another finish and cart away arising debris (Approximately 340lm.)	ITEM			
	Existing Ceiling Finishes				
D	Carefully demolish existing ceiling finish on and including structural framework and prepare concrete soffittes to receive another ceiling finish and cart away arising debris (Approximately 545sm.)	ITEM			
E	Allow a provision of Ten Thousand only (Kshs.50,000.00) for making good disturbed ceiling surfaces to be expended at the discretion of the Project Manager.	ITEM			
F	Existing Concrete Countertops Carefully demolish existing 100mm thick Existing concerete Worktops including structural framework, Finishes and associated accessories and prepare surface to receive another new works and cart away arising debris (Approximately 12sm.)	ITEM			
G	Existing Joinery Cabinets Carefully demolish existing 600mm high Joinery Fixtures with all the accessories including all supports and all plugging and screwing to walls and surfaces of slab, make good disturbed areas to receive new works and cart away arising debris (Approximately 24Lm.)	ITEM			
н	Existing Electrical Fittings & Fixtures Carefully remove existing faulty Electrical Fittings and Fixtures i.e Conduiting, Surface mounted bulbs, switches and Sockets with all the accessories including all supports and all plugging and screwing to walls and soffittes of slab, make good disturbed areas and cart away arising debris to receive new works (Approximately 100no.)	ITEM			
	Total Carried to Demolitions and Alterations Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Demolitions and Alterations Cont'd				
	Existing Sanitary Fittings				
А	Carefully remove existing Sanitary Fittings i.e Water Closet, Urinals, Hand Dryer, Tissue Dispenser, Soap Dispenser, Wash Hand Basins, Taps, Pipers and Mirrors with all the accessories including all connections to the services, waste, jointing to water supply overflow, supports and all plugging and screwing to walls and floors and cart away arising debris (Approximately 50no.)	ITEM			
В	Allow a sum of Ten Thousand only (Kshs.10,000.00) for cleaning out of the service duct shafts	ITEM			
С	Allow a sum of Fifty Thousand only (Kshs.50,000.00) for making good disturbed surfaces	ITEM			
	Total Carried to Demolitions and Alterations Collection Page				
	Demolitions and Alterations Collection Page				
	Brought Forward from Page BW/1				
	Brought Forward from Page BW/2				
	Brought Forward from Above				
	Total Demolitions and Alterations Carried to Summary Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Element No.2: Walling & Partitioning. Machine Cut walling machine cut with a crushing strength of 7.5 N/mm²; walling bedded and jointed in cement and sand (1:4) mortar, reinforcement with and including 25mm wide x 20 gauge hoop iron at every alternate course as described in:				
А	200mm Thick walling	SM	84		
В	100mm Thick walling	SM	66		
С	<u>Damp Proofing</u> 200mm Wide; B.S. 743 Type A bitumen hessian base 150 mm laps (no allowance made for laps); horizontal, 1 no. layer, bedded in cement sand (1:3) mortar	LM	210		
D	Ditto but to 100mm wide	LM	22		
E	Double Skinned Cement FibreBoard Partitions 12mm Thick quality Cement Fibreboard to both sides in 2400 x 1200mm panels screwed on to Galvanised Iron Sections (m.s), with taped and filled joints with acoustic foam insulation all to manufacturer's instructions.	SM	306		
F	Ditto but 12mm thick Gypsum board.	SM	204		
G	12mm Thick quality Cement Fibreboard to both sides in 2400 \times 1200mm panels screwed on to Galvanised Iron Sections (m.s), all to manufacturer's instructions.	SM	20		
Н	Ditto but to 12mm thick Gypsum board.	SM	24		
J	Frameless Glass Partition 12mm Thick fixed, straight frameless laminated glass panel partition with acoustic features: butt-glazed dry joint: equipped with swinging doors where indicated on plan including all ironmongery, and Clippings and Fixing Accessories to Interior designer detail: with filming as Llumar SRC from window plus (K) Ltd to approved pattern to glazing	SM	84		
К	Wainscoting Wall Panels 25mm Thick quality wooden wainscoting panels to Existing Wall Surfaces in 2400 x 600mm panels screwed on to partitions (m.s), all to manufacturer's instructions, Interior Designer's specification and Approval.	SM	255		
	Total Carried to Walling and Partitioning Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Walling & Partitioning Cont'd				
	Galzanised Iron sections (Studs) Structural steel sections drilled, welded and bolted as necessary complete with plates, bolts, cleats etc with and including one coat zinc chromate primer, two undercoats and one coat oil paint full gloss; including all necessary cutting; to Project Manager's satisfaction and approval				
А	$75 \times 50 \times 4$ mm Thick Galzanised Iron sections (horizontal bottom members) screwed to existing floor and screwed to receive Insulated Cement FibreBoard Panels (m/s)	LM	220		
В	Ditto horizontal top pieces grooved to approval at bottom to receive Insulated Cement FibreBoard Panels (m/s) screwed to ceiling (m/s)	LM	220		
С	Ditto horizontal middle members grooved at both sides to approval to receive Insulated Cement FibreBoard Panels (m/s).	LM	825		
D	Ditto vertical piece grooved to approval at both sides to receive Insulated Cement FibreBoard Panels(m/s) fixed to bottom and top piece (m/s).	LM	1100		
	Satin Stainless Steel Beading				
E	100mm High beading member to Framework (m/s) and Glazing (m/s)	LM	478		
	Rubber Gasket				
F	25 x 12mm Thick approved rubber lining to framing (m/s)	LM	478		
	<u>Sillicon Filler</u>				
G	45×25 mm sillicon filler applied as directed and to the approval of the architect at the joints between existing concrete ceiling, Concrete Floors and Lightweight Steel top and Bottom rail	LM	440		
	<u>Vents</u>				
н	18mm thick Anodized clear High performance Flush Minimalist Aria Wall vent fixed to frames (m/s) to architects approval	NO	50		
	<u>Decorative Film</u>				
J	Branded decorative film to glazings (m/s) with corporate colours and logo as per the Interior Designers'/ Clients' specifications	SM	84		
	Total Carried to Walling and Partitioning Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Walling & Partitioning Cont'd				
	<u>Partitioning Sundries</u>				
A	Supply and apply and sand drywall filler as Rhinoglide or equal and approved	SM	510		
В	Polymer based Glass Sealant to surfaces of glass	SM	168		
С	Gypsum Fibre Tape to drywall Joints	LM	540		
D	25 x 3.5mm Dry wall Screws hold drywall in place	PKT	100		
E	Top, Side and Bottom Mount Glass Clamps equipped with rubber inserts, Adjustment Screws and Locking Mechanism to hold glass panels in place	NO	250		
	Total Carried to Walling and Partitioning Collection Page				
	Walling & Partitioning Collection Page				
	Brought Forward from Page BW/4				
	Brought Forward from Page BW/5				
	Brought Forward from Above				
	Total Walling & Partitioning Carried to Summary Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Element No.3: Doors				
	Frameless glass doors				
	12mm thick toughened frameless glass doors complete with locks, handles, and all necessary ironmongery.				
Α	Double Leafed Door size 1400mm x 3000mm high	NO	2		
В	Single Leafed Door size 900mm x 3000mm high	NO	7		
	Timber Doors Supply and fix hardwood Frames with and including supply of low expansion polyurethane foam; in Prime Grade Wrot Mahogany or equivalent softwood and approved (stained to match the colour of veneer):				
С	Ex $50 \times 200 \text{mm}$ Frame with one labour and 10mm groove to detail; plugged	LM	97		
D	Ex 50 x 150mm Frame with one labour and 10mm groove to detail; plugged	LM	20		
Е	Ditto Transome	LM	20		
F	Ex 75 x 25mm Architrave with 10mm groove to detail; plugged	LM	134		
G	Ex 25 x 25mm quadrant	LM	134		
	Total Carried to Doors Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Doors Cont'd				
	Solid Panelled Door				
	50mm thick mahogany pannelled double door, comprising 150 x 50mm top, middle and bottom rails infilled with 50mm thick solid moulded timber panels in 6 No. per leave with moulded beading around panels; edges bevelled and grooved into frames; all framed, clamped and grooved together as per Architects Doors Schedule				
А	Single Leaf Door size 900mm x 2100mm high	NO	14		
В	Ditto but Door size 800mm x 2100mm high	NO	4		
С	Single Leaf Swing Door size 1100mm x 2100mm high	NO	3		
	Solid Flush doors to B.S. 459				
	45mm thick solid core flush door to B.S 459 faced both sides with embossed plywood finished for painting and lipped on all edges in hardwood				
D	Ditto but Door size 600mm x 2400mm high (Duct Doors)	NO	2		
	Painting and decorating				
	Aluminium primer or other equal and approved wood primer before fixing: -				
Е	Frames; over 100mm but not exceeding 200mm girth	LM	134		
F	Surfaces over 300mm girth	LM	134		
	Glazing to Fanlights				
G	4mm Glass and glazing to metal with putty in panes, girth - 0.10 to 0.50 square meters	SM	6		
	Prepare and apply approved stain, sanding sealer and three coats of 'Crown Paints Solo' or other equal and approved varnish to :				
н	General timber surfaces	SM	103		
J	Frames; over 100mm but not exceeding 200mm girth	LM	134		
К	Surfaces over 300mm girth	LM	134		
	Total Carried to Doors Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Doors Cont'd				
	<u>Ironmongery</u>				
	Supply and fix the following ironmongery as per "Union" or other				
	equal and approved with matching screws:-				
	NOTE; Tenderer to refer to the drawing & schedule for iron				
	mongery - All iron mongery to be per Architect's Approval [Tenderer to Provide a Sample board]				
	To softwood, hardwood or the like fixing with screw:				
Α	Brass ball bearing hinges; 150 mm	PRS.	30		
В	Brass ball bearing hinges; 150 mm - Double Hinged	PRS.	5		
С	Three lever mortice lock complete with furniture	NO	17		
D	Heavy Duty Delay Action Door Closure	NO	17		
Е	Door Signage; Material-both Gold & Silver Aluco bond sheet engraved door name Size 400 x 150mm	NO	32		
F	150mm high stainless steel kick plates	NO	16		
G	Supply and fix heavy duty SS wall hook to Architect's Approval	NO	30		
Н	Pressed steel Indicator bolts (vacant/Engaged) ref 8094SS	NO	4		
J	Stainless steel push and pull handles	NO	17		
K	To concrete or blockwork; fixing with bolts; plugging Rubber door stop	NO	31		
	Number door stop	110			
	Total Carried to Doors Collection Page				
	Doors Collection Page				
	Brought Forward from Page BW/7				
	Brought Forward from Page BW/8				
	Brought Forward from Above				
	Total Doors Carried to Summary Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Element No.4: Windows Rehabilitation of Existing Windows				
	Scrap off the worn out Paint, Prepare and apply one coat etching primer two undercoatsand one coat oil paint full gloss furnish to:-				
Α	General surfaces of metal windows	SM	153		
	In wrot Mahogany				
В	300 x 25 mm window board; bullnosed edge, plugged, screwed and pelleted	LM	85		
С	20 x 20 mm quadrant beading	LM	340		
	Prepare and apply 3 coats of approved clear polyuranthane varnish to:				
D	Timber surfaces girth exceeding 100mm but not exceeding 200mm	LM	85		
Е	Timber surfaces not exceeding 100mm girth	LM	340		
F	Curtain Blinds Supply and Fix, 2700mm high Zebra roller blind fabric Made out of polyester with 3% openness factor/ Light filtering, held in place with an aluminium Headrail cassette and Bottom Rail, Blinds to be chain driven inclusive of Weights, screws and crackets all to come with a one year warranty period on both the fabric and operating mechanism (as per manufacturer's warranty) the Fabrics to be BS EN 13501-1 Fire safety certified all to Interior Designer's and Architect's Approval	SM	153		
	Total Windows Carried to Summary Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Element No.5: Finishes				
	Wall Finishes				
	Cement and sand (1:4) backings etc				
Α	15mm Backing finished to receive ceramic wall tiles (m.s)	SM	216		
	Wall Tiles Supply & Fix Approved Glazed Ceramic tiles to Architect's selection & approval to Walls on prepared backing (m.s) in approved patterns as directed by the Architect; with proprietary adhesive; jointed and pointed in matching coloured proprietary anti - fungal waterproof grouting: aluminium threshold & corner strips ,including pvc spacers and expansion joint as necessary: all to Architect's approval.				
В	Wall tiles size 200 x 400 x 10mm thick to Architect's detail	SM	216		
	Tile Edge Strip				
С	25mm Satin stainless steel Tile edge strip	LM	242		
	Painting and decorating				
	Scrap off the worn out Paint, fill in any holes and cracks, sand and clean the surfaces; Skim, Prepare and apply one undercoat and three coats of First Class Quality Matt Emulsion paint with teflon: colour to approval by application strictly in accordance with suppliers printed instructions to surfaces of				
D	Plastered Surfaces	SM	375		
	Skim, Prepare and apply three coats silicon based internal antifungal paint(including skimming): colour to approval by application strictly in accordance with suppliers printed instructions				
Е	Cement Fibre Board and Gypsum Surfaces	SM	554		
	Total Carried to Finishes Collection Page				

	Finishes Cont'd			
	CNC Wall Partition			
А	Provide, fabricate, and install 50mm thick CNC wall partitions. The partitions shall be precision-machined from MDF and Alucobond, incorporating intricate patterns/designs; securely fixed to walls, ceilings, or supporting frames using appropriate fasteners and mounting systems. All cutting, finishing, and installation works shall ensure smooth edges, dimensional accuracy, and a seamless finish. Include all necessary accessories, fittings, surface treatments, and onsite adjustments to complete the works to the required standard; all details and finishes as per Interior Designer's drawings and specifications	SM	30	
.	MDF Wall panelling			Ì
В	50×50 mm mahogany timber frames vertically plugged to wall	432	LM	
С	75 x 25 mm mahogany architrave; top side grooved	144	LM	
D	25 x 25 mm mahogany quadrant	144	LM	
E	18 mm Thick MDF panel, mahogany veneered one side and lipped	387	SM	
F	16 mm Thick plywood	387	SM	
G	Prepare and apply one undercoat, two finishing coats of first grade polyurethane clear varnish to wood surfaces	387	SM	
	Total Carried to Finishes Collection Page			

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Finishes Cont'd				
	Floor Finishes				
	Floor Tiles				
	Waterproofed Cement and sand (1:3) screeding smooth trowelled laid on concrete bed (m.s)				
А	40 mm Thick cement and sand screed with Penetron integral capillary system water proofing additive or any other approved by the project manager (1:3) to receive tiles (measured separately)	SM	165		
	Supply & Fix tiles (To Architect's Approval) in regular or other approved pattern; to floor on prepared screed (m.s); with proprietary adhesive; jointed and pointed in matching coloured proprietary grouting: aluminium threshold ,including pvc spacers and expansion joint as necessary: all to Architect's approval.				
В	300 x 300 x 10mm thick Non - Slip Ceramic Tiles	SM	43		
С	600 x 600 x 10mm Porcelain tiles	SM	122		
	Carpet Tiles				
	Cement and sand (1:3) screeding smooth trowelled laid on concrete bed (m.s)				
D	40mm thick bed finished to receive Carpet Tiles (m.s)	SM	139		
	Supply and fix high quality carpet tiles with dense yarn: including bitumen high fade resistance with 100% solution dyed nylon suitable for heavy commercial usage: yarn weight with minimum 1.2kg/m2 and total weight equal or above 2.5 kg/m2: electrostatic propensity less than 2.0kv: prepare surface and lay complete with underlay as per manufacturers printed instructions allow for and brass knaplocks as necessary or as directed:				
Е	600 x 600 x 10mm thick Carpet Tiles	SM	139		
F	Provide underfelt and fix with approved adhesive as 'Pattex' or other equal and approved	SM	139		
	Total Carried to Finishes Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Finishes Cont'd				
	Wall to Wall Executive Carpet				
	Cement and sand (1:3) screeding smooth trowelled laid on concrete bed (m.s)				
A	40mm thick bed finished to receive Wall to Wall Executive Carpet (m.s)	SM	275		
В	Supply and fix 10mm thick approved jute-backed carpet to KS 08 179: 1998 comprising of 80% wol; 20% synthetic fused in woven textile backing, stai resitant, fade resistant, soiling treated permanently anti-static standard carper with and including standard underfelt complete with aluminium fixing clips metal grippers, approved adhesive; all fixed in accordance with manufacturer's instructions:	SM	275		
С	Provide underfelt and fix with approved adhesive as 'Pattex' or other equal and approved	SM	275		
	Satin Stainless Steel				
D	100mm High skirtings to all partitions	LM	564		
	Wrot Hardwood				
Е	100 x 25mm mahogany skirting	LM	564		
	Floor Separator				
F	50mm T - Bar mounted Transition strip on the floor to match corresponding floor finishes	LM	100		
	Total Carried to Finishes Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Finishes Cont'd				
	Ceiling Finishes				
	Gypsum Ceiling				
	FALSE CEILING (9mm Thick Gypsum Board) as Gyproc: Providing and fixing suspended false ceiling, which includes providing and				
	fixing G.I. Perimeter channels of size 0.55mm thick with adequate flange and a web to secure anchorage along perimeter of ceiling.				
	screw fixed to wall/partition with the help of nylon sleeves and				
	screw at 610 mm centres. Suspended using G.I. Intermediate channels of size 50mm from the soffit at 1.2 mts c/c with ceiling				
	angle fixed to soffit G.I. clean and steel expansion fasteners. Ceiling section of 0.55mm thickness having knurled web of 50mm and two				
	flanges 26mm each with clips of 10.5mm to be fixed to the intermediate channel with connecting clips in direction				
	perpendicular to intermediate channel at 500mm c/c. 12.5mm				
	tapered edge Gypsum board (conforming to KS 2647:2016) to be screw fixed to ceiling sections with 25mm dry wall screws at				
	230mm centres. Boards to be properly finished with topcoat. Instalation to be completed as per Interior designer's				
	direction.(Inclusive of Suspension)				
А	To General Ceiling Surfaces as indicated on plan	SM	210		
В	Ditto but water resistant gypsum ceiling	SM	23		
С	Ditto but fire resistant gypsum ceiling	SM	15		
D	Ditto but with shadow gap	SM	25		
E	Extra over for forming gypsum bulkhead ceiling avg 600mm wide, with a depth of 100mm, running continuously as per approved design and layout.	SM	76		
F	Ditto but water resistant	SM	5		
G	Ditto but fire resistant	SM	4		
н	Ditto but with shadow gap	SM	7		
	Total Carried to Finishes Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Finishes Cont'd				
А	Acoustic Baffle Ceiling Providing and fixing Aluminium Baffle ceiling system with timber finish, Baffle width of 50mm x 100mm height x 0.5mm thick and gap between baffles to be 100mm c/c. The baffles shall be fixed to suspennsion system by means of 6mm threaded rod at 1200 mm c/c. Rate to include for acoustical Fleece of porous material of 2-3mm thickness, over 2mm thick MDF fixed to the aluminium baffle as per the Manufacture's recommendation; complete with color as per ID's details and approval. Contractor to furnish the sample for ID's approval.	SM	39		
В	Wooden Veneer Ceiling Providing and Fixing 1200 X 600mm wooden ceiling panels of 4mm thick magogany veneer of archid/century/truwood make pasted over 12mm thick; flexiply screwed to 25x25mm chrome plated MS pipe frame of 18-gauge thickness in required curvature using stainless steel studs & fixed to the concrete ceiling using plugs and height adjustable G.I suspension wires; including finishing in matt melamine polish (ICI/MRF poly coats only) complete in all respects. Rate should include cutting of holes for lights etc. for concealing conduits/wiring, nothing extra will be paid for this, all to ID's approval.	SM	35		
С	<u>Vents</u> 18mm thick Anodized clear High performance Flush Minimalist Aria Ceiling vents fixed to frames (m/s) to architects approval	NO	50		
	Painting and decorating Skim, Prepare and apply three coats exterior quality silicon based external antifungal paint(including skimming): colour to approval by application strictly in accordance with suppliers printed instructions				
D	Cement Fibre Board surfaces	SM	349		
E	Gypsum Surfaces	SM	210		
	Total Carried to Finishes Collection Page				


ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Finishes Cont'd				
	Ceiling Sundries				
A	Supply and apply and sand ceiling board filler as Rhinoglide or equal and approved	SM	559		
В	Gypsum Fibre Tape to Ceiling Joints	LM	1,398		
С	52mm Floor Tracks for Framing	LM	1,314		
D	51mm Dry wall studs for Framing	LM	1,314		
Е	25 x 3.5mm Dry wall Screws hold drywall in place	PKT	100		
	Total Carried to Finishes Collection Page				
	Finishes Collection Page				
	Brought forward from Page BW/11				
	Brought forward from Page BW/11				
	Brought forward from Page BW/12				
	Brought forward from Page BW/13				
	Brought forward from Page BW/14				
	Brought forward from Page BW/15				
	Brought forward from Page BW/16				
	Brought forward from above				
	Total Finishes Carried to Summary Page				
	Total Finishes Carried to Summary Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Element No.6: Joinery Fittings				
	PS: All Fixtures are as per Schedule Provided by the Architect & Interior Designer				
	Plinths The following in 100mm thick benching concrete class 15 with 12mm cement sand plaster to top and edges; including all necessary formwork and BRC A142 mesh reinforcement weighing 2.22 kg per square metre				
А	100mm thick benching	SM	12		
В	Mesh reinforcement No A98 weighing 1.54 kg per square metre in work top including all necessary supports	SM	12		
	Wrot Formwork				
С	Edges of 100 mm plinth	LM	20		
	20mm Thick approved first quality granite top with rounded edge. Allow for bedding and jointing in cement mortar 1:4 grouting joints with matching cements				
D	Worktop	SM	12		
Е	150mm High granite fascia fixed on concrete surface	LM	20		
F	Extra over ditto for making hole size 2000 x 600mm for sink	NO	1		
G	Extra over ditto for making hole size 600 x 1200mm for cooker	NO	1		
	The following in Laminated blockboard shelf, sides dividers, back etc stained moulded oak veneered blockboard drawers and doors, complete with malpha hinges viro make cylinder lock, handles and eggshell paint				
н	Low level cupboard size 10000 x 600 x 900mm high	NO	1		
J	High level cupboard size 10000 x 600 x 600mm high	NO	1		
К	Executive Full height Joinery (cabinetry)	LM	35		
	Total Carried to Collection Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Joinery Cont'd				
	Concrete flower pots				
L	14" Hexagonal Flower pots filled with red soil mixed with manure in the appropriate ratio with a 1200mm high live flower plant subject to the Arhcitect's Approval	NO	10		
	Reception Counter				
М	Customized Reception desk with counteriser L3200xW950xH1100mm in laminated particle board, melawood supagloss, 25mm thick corian top, 100mm bottom stainless steel kick plate, and 2no. mobile pedestals to match; All to Project Manager's Specification and Approval	NO	1		
N	Ditto for CS's Secretary	NO	1		
	Total Carried to Joinery Collection Page				
	Finishes Collection Page				
	Brought forward from Page BW/18				
	Brought forward from above				
	Total Joinery Fittings Carried to Summary Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	Element No.7: Builder's works in connection to services				
	Inspect all architectural, mechanical, electrical and structural drawings as provided; allow for all builders work assocciated with all the specialist works				
A	Form all holes, chases, etc and make good after the plumber, electrician and all other specialist works	ITEM			
	Total Builders works in connection to services Carried to Summary Page				

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (KSH)
	BUILDER'S WORKS SUMMARY				
	Element No.1 - Demolitions & Alterations		BW/3		
	Element No.2 - Walling and Partitioning		BW/6		
	Element No.3 - Doors		BW/9		
	Element No.4 - Windows		BW/10		
	Element No. 5 - Finishes		BW/17		
	Element No. 6 - Joinery Fittings		BW/19		
	Element No. 7 - Builders work in Connection to services		BW/20		
	TOTAL FOR BUILDER'S WORKS CARRIED TO GRAND SUMMARY				



PROPOSED REORGANIZATION OF THIRD FLOOR WORKS BUILDING
TENDER SPECIFICATIONS AND BILLS OF QUANTITIES FOR SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF ELECTRICAL ENGINEERING SERVICES WORKS

TABLE OF CONTENTS

<u>TITLE</u>	<u>PAGE</u>
SECTION A: Tender Evaluation Criteria	Elect-A/1 - A/4
SECTION B: General Specifications of Materials and Works	Elect-B/1 - B/17
SECTION C: Particular Specifications of Materials and Works	Elect-C/1 - C/13
SECTION D: Schedule of Contract Drawings	Elect- D/1
SECTION E: Technical Schedule	Elect-E/1 - E/2
SECTION F: Schedule of Unit Rates	Elect-F/1 - F/2
SECTION G: Bills of Quantities	Elect-G/1 – G/13

SECTION A TENDER EVALUATION CRITERIA

Note.

This criterion shall be used to evaluate the bidders proposed to carry out the specialized works who shall be domestic subcontractors to the main bidder on award of the contract.

TENDER EVALUATION CRITERIA

After tender opening, the tenders will be evaluated in 2 stages, namely:

- 1. Preliminary Evaluation;
- 2. Technical Evaluation;

Note: This criterion shall be used to evaluate sub contracts

STAGE 1: PRELIMINARY EVALUATION

This stage of evaluation shall involve examination of the mandatory requirements as set out in the Tender Advertisement Notice or Letter of Invitation to Tender and any other conditions stated in the bid document.

These conditions shall include the following:

S/No	MANDATORY REQUIREMENTS(MR)	Remarks (Yes/No
MR1	Valid Copy of certificate of incorporation/ Registration;	
MR2	Valid Current Tax Compliance Certificate from Bidding Company, and if Consortium, from each member of the consortium;	
MR3	Submission of valid CR12 form showing the list of directors /shareholding (issued within the last 12 months) or National Identity Card(s) for Sole Proprietorship / Partnership;	
MR4	Valid copy of NCA Registration Certificate for the following works: a) CCTV – NCA 7 and above b) Structured Cabling/ Telecommunication – NCA 7 and above c) Electrical Installations – NCA 7 and above	
MR5	Current annual contractors practicing license from NCA for works listed in items MR4, MR5 and MR6;	
MR6	Copy of current License in Electrical installation works with EPRA- Class B and above;	
MR7	Copy of valid Registration License from Communication Authority of Kenya (CA);	
MR8	Copy of Valid Annual Compliance Certificate from Communication Authority of Kenya (CA)	
MR9	Manufacturer's authorization for active components in CCTV and structured cabling works;	
MR10	Domestic sub-contractors must sign and stamp the summary page of their respective specialist works on the tender document.	
	Domestic sub-contractor must submit a signed Memorandum of Understanding with their Main Contractor	

The tenderers who do not satisfy any of the above mandatory requirements shall be considered non-Responsive and their tenders will not be evaluated further.

STAGE 2: TECHNICAL EVALUATION

The subcontractor shall be evaluated as follows:

PARAMETER

- (i) Key personnel
- (ii) Contract Completed in the last Five (5) years
- (iii) Schedules of on-going projects
- (iv) Schedules of Contractor's equipment
- (v) Litigation History

The detailed assessment for eligibility as shown in table 1.

TABLE 1: Assessment for Eligibility

Item	Description	Remarks (Yes/No)
1.	Compliance with Key Technical Specifications	
	Key Personnel (Attach evidence)	
	Director of the firm Holder of a minimum diploma in relevant Engineering field with at least 5 years' ExperienceY	
	At least 1No. key personnel with a minimum of a diploma in relevant field Has at least 1 years of relevant experience	
2,	At least 1No certificate holder of key personnel in relevant field Has at least 1 years of relevant experience	
	At least 2No artisan (trade test certificate in relevant field) Artisans with at least 1 years of relevant experience	
	Contracts completed in the last five (5) years (Min of 3No. Projects) - Provide Evidence	
3.	Project of similar nature, complexity or magnitude	

ltem	Description	Remarks
4.	On-going projects [] Five and below Projects of similar, nature complexity and magnitude	
5.	Schedule of contractor's equipment and transport (proof or evidence of ownership/Lease) a) Relevant Transport [] Means of transport (1 No. Vehicle)	
	b) Relevant Equipment Has relevant equipment for work being tendered	
6.	Litigation History Duly Filled	

NB

Y - Compliant

N - non -compliant

The tenderers who do not satisfy any of the above requirements shall be considered non-Responsive and their tenders will not be evaluated further.

NOTES ON COMPLIANCE WITH KEY TECHNICAL SPECIFICATIONS (CRITERIA No.1)

Tenderers shall submit offers that comply with the requirements of the tendering documents, including the basic technical design as indicated in the Drawings and Specifications.

Tenderers shall be required;

- a) On compliance with Technical Specifications, bidders shall supply equipment/items that comply with the technical specifications set out in the bid document. In this regard, the bidders will be required to submit relevant technical brochures/catalogues with the tender document, highlighting (using a mark-pen or highlighter) the Catalogue Number/model of the proposed items. Such brochures/catalogues should indicate comprehensive relevant data of the proposed equipment/items which should include but not limited to the following:
 - (i) Standards of manufacture;
 - (ii) Performance ratings/characteristics/ features;
 - (iii) Material of manufacture;
 - (iv) Electrical power ratings; and
 - (v) All other requirements as indicated in the technical specifications of the bid.

The bid will then be analyzed, using the information in the technical brochures, to determine compliance with <u>key technical specifications</u> for the works/items as indicated in the tender document.

The tenderer shall fill in the Technical Schedule as specified in the tender document for Equipment and Items indicating the Model/Make/Manufacturer and catalogue numbers of the Items/Equipment they propose to supply.

Bidders not complying with any of the <u>key technical specifications</u> shall be considered noncompliant to the technical specifications while those meeting all the key technical specifications shall be considered compliant.

Compliance in this section shall be as shown below:

Descr	iption	COMPLIANT / NON-COMPLIANT
Comr	oliance with Technical Specifications	NON-COMILIANI
(Note:	•	
1)	Tender Evaluation Committee to evaluate compliance to all technical specifications (Electrical, Data, and CCTV Installation Works) as detailed in the Section C (Particular specs) of this document	
2)	Bidders who do not highlight catalogue number and model of the proposed items shall be considered non-compliant.	
3)	Non-compliance to any of the specifications shall render the whole system non-compliant	

Any bidder who is compliant shall be considered for further evaluation.

SECTION B

GENERAL SPECIFICATIONS

OF

MATERIALS AND WORKS

PART 1. GENERAL SPECIFICATIONS OF WORKS

	1.1	General
	1.2	Standard of Materials
	1.3	Workmanship
	1.4	Procurement of Materials
	1.5	Shop Drawings
	1.6	Record Drawings
	1.7	Regulations and Standards
	1.8	Setting out Works
PA	RT 2. <u>GEN</u>	IERAL SPECIFICATIONS OF ELECTRICAL WORKS
	2.1	Position of Electrical Plant and Apparatus
	2.2	M.C.B Distribution Panels and Consumer Units
	2.3	Fused Switchgear and Isolators
	2.4	Conduits and Conduit Runs
	2.5	Conduit Boxes and Accessories
	2.6	Labels
	2.7	Earthing
	2.8	Cables and Flexible Cords
	2.9	Armoured PVC Insulated and Sheathed Cables
	2.10	Cable Supports; Markers and Tiles
	2.11	PVC Insulated Cables
	2.12	Heat Resisting Cables
	2.13	Flexible Cords
	2.14	Cable Ends and phase Colours
	2.15	Cable Insulation Colours
	2.16	Sub-circuit Wiring
	2.17	Space Factor
	2.18	Insulation

2.19	Lighting Switches
2.20	Sockets and Switched sockets
2.21	Fused Spur Boxes
2.22	Cooker Outlets
2.23	Connectors
2.24	Lamp holders
2.25	LED Lamps
2.26	lighting Fittings Street lighting Lanterns
2.27	Position of Points and Switches
2.28	Current Operated Earth leakage circuit breaker
2.29	MV Switchboard
2.30	Steel Conduits and Steel Trunking
2.31	Testing on Site

PART 1. GENERAL SPECIFICATIONS OF WORKS

1.1 GENERAL

This specification is to be read in conjunction with the drawings which are issued with it. Bills of quantities shall be the basis of all additions and omissions during the progress of the works.

1.2 STANDARD OF MATERIALS

Where the material and equipment are specifically described and named in the Specification followed by approved equal, they are so named or described for the purpose of establishing a standard to which the sub-contractor shall adhere.

Should the Sub-contractor install any material not specified herein before receiving approval from the proper authorities, the Engineer shall direct the Sub-contractor to remove the material in question immediately. The fact that this material has been installed shall have no bearing or influence on the decision by the Engineer.

All materials condemned by the Engineer as not approved for use, are to be removed from the premises and suitable materials delivered and installed in their place at the expense of the Subcontractor. All materials required for the works shall be new and the best of the respective kind and shall be of a uniform pattern.

1.3 WORKMANSHIP

The workmanship and method of installation shall conform to the best standard practice. All work shall be performed by a skilled tradesman and to the satisfaction of the Engineer. Helpers shall have qualified supervision.

Any work that does not in the opinion of the Engineer conform to the best standard practice will be removed and reinstated at the Sub-contractors expense.

Permits, Certificates or Licenses must be held by all tradesmen for the type of work; in which they are involved where such permits, certificates or licenses exist under Government legislation.

1.4 PROCUREMENT OF MATERIALS

The sub-contractor is advised that no assistance can be given in the procurement or allotment of any materials or products to be used in and necessary for the construction and completion of the work.

Sub-contractors are warned that they must make their own arrangements for the supply of materials and/or products specified or required.

1.5 SHOP DRAWINGS

Before manufacture or Fabrication is commenced the sub-contractor shall submit Two copies of detailed drawings of all control pillars, meter cubicles, medium voltage switchboards including their components showing all pertinent information including sizes, capacities, construction details, etc, as may be required to determine the suitability of the equipment for the approval of the Engineer.

Approval of the detailed drawings shall not relieve the sub-contractor of the full responsibility of errors or the necessity of checking the drawings himself or of furnishing the materials and equipment and performing the work required by the plans and specifications.

1.6 RECORD DRAWINGS

These diagrams and drawings shall show the completed installation including sizes, runs and arrangements of the installation. The drawings shall be to scale not less than 1:50 and shall include plan views and section.

The drawings shall include all the details which may be useful in the operation, maintenance or subsequent modifications or extensions to the installation.

Three sets of diagrams and drawings shall be provided, all to the approval of the Engineer.

One coloured set of line diagrams relating to operating and maintenance instructions shall be framed and, mounted in a suitable location.

1.7 REGULATIONS AND STANDARDS

All work executed by the Sub-contractor shall comply with the current edition of the "Regulations" for the Electrical Equipment of Buildings, issued by the Institution of Electrical Engineers, and with the Regulations of the Local Electricity Authority.

Where the two sets of regulations appear to conflict, they shall be clarified with the Engineers. All materials used shall comply with relevant Kenya Bureau of Standards Specification.

1.8 SETTING OUT WORK

The sub-contractor at his own expenses; is to set out works and take all measurements and dimensions required for the erection of his materials on site; making any modifications in details as may be found necessary during the progress of the works, submitting any such modifications or alterations in detail to the Engineer before proceeding and must allow in his Tender for all such modifications and for the provision of any such sketches or drawings related thereto.

PART 2. GENERAL SPECIFICATIONS OF ELECTRICAL WORKS

2.1 POSITIONS OF ELECTRICAL PLANT AND APPARATUS

The routes of cables and approximate positions of switchboards etc., as shown on the drawings shall be assumed to be correct for purpose of Tendering, but exact positions of all electrical Equipment and routes of cables must be agreed on site with the Engineer before any work is carried out.

2.2 MCB DISTRIBUTION PANELS AND CONSUMER UNITS

All cases of MCB Panels and consumer units shall be constructed in heavy gauge sheet with hinged covers.

Removable undrilled gland plates shall be provided on the top and bottom of the cases. Miniature circuit breakers shall be enclosed in moulded plastic with the tripping mechanism and arc chambers separated and sealed from the cable terminals.

The operating dolly shall be tripfree with a positive movement in both make and break position. Clear indication of the position of the handle shall be incorporated.

The tripping mechanism shall be on inverse characteristic to prevent tripping in temporary overloads and shall not be affected by normal variation in ambient temperature.

A locking plate shall be provided for each size of breaker; A complete list of circuit details on typed cartridge paper glued to stiff cardboards and covered with a sheet of perspex, and held in position

with four suitable fixings, shall be fitted to the inner face of the lids of each distribution panel. The appropriate MCB ratings shall be stated on the circuit chart against each circuit in use: Ivorine labels shall be secured to the insulation barriers in such a manner as to indicate the number of the circuits shown on the circuit chart.

Insulated barriers shall be fitted between phases, and neutrals in all boards, and to shroud live parts.

Neutral cables shall be connected to the neutral bar in the same sequence as the phase cables are connected to the MCB's. This shall also apply to earth bars when installed.

2.3 FUSED SWITCHGEAR AND ISOLATORS

All fused switchgear and isolators whether mounted on machinery, walls or industrial panels shall conform to the requirements of KS 04 – 226 PART: 1: 1985.

All contacts are to be fully shrouded and are to have a breaking capacity on manual operations as required by KS 04 - 182: 1980.

Fuse links for fused switches are to be of high rupturing capacity cartridge type, conforming to KS 04 – 183: 1978.

Isolators shall be load breaking/fault making isolators.

Fused switches and isolators are to have separate metal enclosures. Mechanical interlocks are to be provided between the door and main switch operating mechanism so arranged that the door may not be opened with the switch in the 'ON' position. Similarly; it shall not be possible to close the switch with the door open except that provision to defeat the mechanical interlock and close the switch with the door in the open position for test purposes. The 'ON' and 'OFF' positions of all switches and isolators shall be clearly indicated by a mechanical flag indicator or similar device. In T.P & N fused switch units, bolted neutral links are to be fitted.

2.4 CONDUITS AND CONDUIT RUNS

Conduit systems are to be installed so as to allow the loop-in system of wiring:

All conduits shall be black rigid super high impact heavy gauge class 'A' PVC in accordance with KS 04 – 179: 1988 and IEE Regulations. No conduit less than 20mm in diameter shall be used anywhere in this installation.

Conduit shall be installed buried in plaster work and floor screed except when run on wooden or metal surface when they will be installed surface supported with saddles every 600mm. Conduit run in chases shall be firmly held in position by means of substantial pipe hooks driven into wooden plugs.

The Sub-contractor's attention is drawn to the necessity of keeping all conduits entirely separate from other piping services such as water and no circuit connections will be permitted between conduits and such pipes.

All conduits systems shall be arranged wherever possible to be self-draining to switch boxes and conduit outlet points for fittings:

The systems, when installed and before wiring shall be kept plugged with well-fitting plugs and when short conduit pieces are used as plugs, they shall be doubled over and tied firmly together with steel wire; before wiring all conduit systems shall be carried out until the particular section of the conduit installation is complete in every respect.

The sets and bends in conduit runs are to be formed on site using appropriate size bending springs and all radii of bends must not be less than 2.5 times the outside diameter of the conduit. No solid or inspection bends, tees or elbows will be used.

Conduit connections shall either be by a demountable (screwed up) assembly or adhesive fixed and water tight by solution. The tube and fittings must be clean and free of all grease before applying the adhesive. When connections are made between the conduit and switch boxes, circular or non-screwed boxes, care shall be taken that no rough edges of conduit stick out into the boxes.

Runs between draw in boxes are not to have more than two right angle bends or their equivalent. The sub-contractor may be required to demonstrate to the Engineers that wiring in any particular run is easily withdrawable and the sub-contractor may, at no extra cost to the contract; be required to install additional draw-in boxes required. If conduit is installed in straight runs in excess of 6000mm, expansion couplings as manufactured by Egatube shall be used at intervals of 6000mm.

Where conduit runs are to be concealed in pillars and beams, the approval of the Structural Engineer, shall be obtained. The sub-contractor shall be responsible for marking the accurate position of all holes chases etc., on site, or if the Engineer so directs, shall provide the Main Contractor with dimensional drawings to enable him to mark out and form all holes and chases. Should the sub-contractor fail to inform the main contractor of any inaccuracies in this respect they shall be rectified at the sub-contractor's expense.

It will be the Sub-contractor's responsibility to ascertain from site, the details of reinforced concrete or structural steelwork and check from the builder's drawings the positions of walls, structural concrete and finishes. No reinforced concrete or steelwork may be drilled without first obtaining the written permission of the Structural Engineer.

The drawings provided with these specifications indicate the appropriate positions only of points and switches, and it shall be the Sub-Contractors responsibility to mark out and centre on site the accurate positions where necessary in consultation with the Architect and the Engineer. The sub-contractor alone shall be responsible for the accuracy of the final position.

2.5 CONDUIT BOXES AND ACCESSORIES

All conduit outlets and junction boxes are to be either malleable iron and of standard circular pattern of the appropriate type to suit saddles being used or super high impact PVC manufactured to KS 04 – 179: 1983.

Small circular pattern boxes are to be used with conduits up to and including 25mm outside diameter. Rectangular pattern adaptable boxes are to be used for conduits of 32mm outside diameter and larger. For drawing in of cables in exposed runs of conduit, standard pattern through boxes are to be used:

Boxes are to be not less than 50mm deep and of such dimensions as will enable the largest appropriate number of cables for the conduit sizes to be drawn in without excessive bending.

Outlet boxes for lighting fittings are to be of the loop-in type where conduit installation is concealed and the sub-contractor shall allow one such box per fitting, except where fluorescent fittings are specified when two such boxes per fitting shall be fitted flush with ceiling and if necessary fitted with break joint rings. Pattresses shall be fitted where required to outlets on surface conduit runs.

Adaptable boxes are to of PVC or mild steel (of not less than 12swg) and black enamelled or galvanised finish according to location. They shall be of square or oblong shape location. They shall be of square or oblong shape complete with lids secured by four 2 BA brass roundhead screws; No adaptable box shall be less than 75mm x 75mm x 50mm or larger than 300mm x 300mm x 75mm

and shall be adequate in depth in relation to the size of conduit entering it. Conduits shall only enter boxes by means of conduit bushes.

2.6 LABELS

Labels fitted to switches and fuse boards; -

- (i) Shall be Ivorine engraved black on white.
- (ii) Shall be secured by R.H brass screws of same manufacturing throughout.
- (iii) Shall be indicated on switches:
 - a) Reference number of switches
 - **b)** Special current rating
 - c) Item of equipment controlled
- (iv) Shall indicate on MCB panels
 - d) Reference number
 - e) Type of board, i.e;, lighting, sockets, etc,.
 - f) Size of cable supplying panel
 - g) where to isolate feeder cable
- (v) Shall be generally not less than 75mm x 50mm.

2.7 EARTHING

The earthing of the installation shall comply with the following requirements; -

- (i) It shall be carried out in accordance with the appropriate sections of the current edition of the Regulations, for the Electrical Equipment of Buildings issued by Institute of Electrical Engineers of Great Britain.
- (ii) At all main distribution panels and main service positions a 25mm x 3mm minimum cross-sectional area Copper tape shall be provided and all equipment including the lead sheath and armouring of cables, distribution boards and metal frames shall be bonded thereto.
- (iii) The earth tape in Sub-clause (ii) shall be connected by means of a copper tape or cable of suitable cross-sectional area to an earth electrode which shall be a copper earth rod (see later sub-clause).
- (iv) All tapes to be soft high conductivity copper, untinned except where otherwise specified and where run underground on or through walls, floors, etc., it shall be served with corrosion resisting tape or coated with corrosion compound and braided
- (v) Where the earth electrode is located outside the building a removable test link shall be provided inside the building as near as possible to the point of entry to the tape, for isolating the earth electrode for testing purposes.
- (vi) Earthing of sub-main equipment shall be deemed to be satisfactory where the sub-main cables are M.I.C.S. or conduit with separate earth wire, and installation is carried out in accordance with the figures stated in the current edition of the I.E.E Regulations.
- (vii) Where an earth rod is specified (see Sub-clause (iii) it shall be proprietary manufacture, solid hand drawn copper of 15mm diameter driven into the ground to a minimum depth of 3.6M. It shall be made up to 1.2m sections with internal screw and socket joints and fitted with hardened steel tip and driving cap.

- (viii) Earth plates will not be permitted
- (ix) Where an earth rod is used the earth resistance shall be tested in the manner described in the current edition of the IEE Regulations, by the Sub-Contractor in the presence of the Engineer and the Sub-Contractor shall be responsible for the supply of all test equipment.
- (x) Where copper tape is fixed to the building structure it shall be by means of purpose made non-ferrous saddles which space the conductor away from the structure a minimum distance of 20mm. Fixings, shall be made using purpose made plugs; No fixings requiring holes to be drilled through the tape will be accepted.
- (xi) Joints in copper tape shall be tinned before assembly riveted with a minimum of two copper rivets and seated solid.
- (xii) Where holes are drilled in the earth tape for connection to items of equipment the effective cross-sectional area must not be less than required to comply with the IEE regulations.
- (xiii) Bolts, nuts and washers for any fixing to the earth tape must be of non-ferrous material.
- (xiv) Attention is drawn to the need for the earthing metal parts of lighting fittings and for bonding ball joint suspension in lighting fittings.

2.8 CABLES AND FLEXIBLE CORDS

All cables used in this Sub-Contract shall be manufactured in accordance with the current appropriate Kenya standard Specification which are as follows: -

P.V.C. Insulated Cables and Flexible Cords --- Ks 04-192:1988

P.V.C Insulated Armoured Cables --- Ks 04-194:1990

Armouring of Electric cables --- Ks 04-290:1987

The successful Sub-Contractor will, at the Engineers discretion be required to submit samples of cables for the Engineers approval; the Engineer reserves the right to call for the cables of an alternative manufacture without any extra cost being incurred.

P.V.C. insulated cables shall be 500/1000-volt grade. No cables smaller than 1.5mm² shall be used unless otherwise specified. The installation and the finish of cables shall be as detailed in later clauses. The colour of cables shall conform to the details stated in the "Cable Braid and insulation Colours" Clause.

2.9 ARMOURED P.V.C. INSULATED AND SHEATHED CABLES:

Shall be 600/1000-volt grade manufactured to Ks 04-194:1988 and Ks 04-187/188 with copper stranded conductors.

The wire armour of the cable shall be used wholly as an earth continuity conductor and the resistance of the wire armour shall have a resistance not more than twice of the largest current carrying conductor of the cable.

P.V.C./S.W.A./P.V.C. cables shall be terminated using "Telecom" "B" type or approved equal or approved equal glands and a P.V.C. tapered sleeve shall be provided to shroud each gland.

2.10 CABLE SUPPORTS, MARKERS AND TILES

All PVC/SWA/PVC cables run inside the building shall be fixed in rising ducts or on ceilings by means of die cast cable hooks or clamps, of appropriate size to suit cables, fixed by studs and back nuts to their channel sections.

Alternatively, fixing shall be by BICC claw type cleating system with die-cast cleats and galvanized mild steel back straps or similar approved equal method. For one or two cables run together the cleats shall be fixed a special channel section supports or backstraps described above which shall in turn be secured to walls or ceilings of ducts by rawbolts.

In excessively damp or corrosive atmospheric conditions special finishes may be required and the Sub-contractor shall apply to the Engineer for further instructions before ordering cleats and channels for such areas.

The above type of hooks and clamps and channels or cleats and blackstraps shall also be used for securing cables in vertical ducts.

Cables supports shall be fixed at 600mm maximum intervals, the supports being supplied and erected under this Sub-contract. Saddles shall not be used for supporting cables nor any other type of fixing other than one of the two methods described above or other system which has received prior approval of the Engineer;

Cables are to be kept clear of all pipe work and the Sub-contractor shall work in close liaison with other services Sub-contractors.

The Sub-Contractor shall include for the provision of fixing of approved type coloured slip on cables end markers to indicate permanently the correct phase and neutral colours on all ends.

Provision shall be made for supplying and fixing approved non-corrosive metal cable markers to be attached to the outside of all PVC/SWA/PVC cables at 15mm intervals indicating cable size and distinction.

Where PVC/SWA/PVC cables are outside the building they shall be laid underground 750mm deep with protecting concrete interlocking cover tiles laid over which shall be provided and laid under this Sub-contract.

All necessary excavations and reinstatement of ground including sanding or trenches will be carried out by the Sub-Contractor, unless otherwise stated.

2.11 PVC INSULATED CABLES

Shall be of non-braided type as CMA reference $6491 \times 600/1000/1000$ -volt grade cables, or equal approved.

PVC cables shall conform to the details of the "Cables and Flexible cords" and "Cable Braid and Insulation Colours" clauses.

2.12 HEAT RESISTING CABLES

Final connections to cookers, water heaters, etc., shall be made using butyl rubber insulated cable as CMA reference 610 butyl (Single core 600/1000 Volt).

This type of cable shall be used in all instances where a temperature exceeding 100°F, but not exceeding 150°F is likely to be experienced. Final connections to all lighting fittings (and other equipment where a temperature in excess of 150°c likely to be experienced) shall be made using silicon rubber insulated cable or equal and approved.

2.13 FLEXIBLE CORDS

Shall be in accordance with the "Cable and Flexible Cords" clause. No cord shall be less than 24/0.2mm in size unless otherwise specified.

Circular white twin TRS flex shall be used for plain pendant fittings up to 100 watts. For all other types of lighting fittings the flexible cable shall be silicone rubber insulated.

No polythene insulated flexible cable shall be used in any lighting fitting or other appliance (see "Heat Resisting Cables" Clause 30).

2.14 CABLE ENDS AND PHASE COLOURS

All cable ends connected up in switchgear, MCB panels etc., shall have the insulation carefully cut back and the ends sealed with Hellerman rubber slip on cable end markers.

The markers shall be of appropriate phase colour for switch and all other live feeds to the details of the "Cable Insulation Colours" clause. Black cable with black end markers shall only be used for neutral cables.

2.15 CABLE INSULATION COLOURS

Unless otherwise stated in later clauses the insulation colours shall be in accordance with the following table.

Where other systems are installed the cable colours shall be in accordance with the details stated in the appropriate clause.

<u>SYSTEM</u>			INSULATION COLOUR	CABLE END
1)	Main and Sub-Main			<u>MARKER</u>
	a)	Phase	Red	Red
	b)	Neutral	Black	Black
2)	Sub	-Circuits Single Phase		
	a)	Phase	Red	Red
	b)	Neutral	Black	Black

2.16 SUB-CIRCUIT WIRING

For all lighting and sockets wiring shall be carried out in the "looping in" system and there shall be no joints whatsoever. No lighting circuits shall comprise more than 20 points when protected by 10A MCB. Cables with different cross-section area of copper shall not be used in combination.

Lighting circuits P.V.C. cable.

(i) 1.5mm² for all lighting circuits indicated on the drawing.

Power circuits P.V.C cable (minimum sizes).

- (i) 2.5mm² for one, two or three 5Amp sockets wired in parallel.
- (ii) 2.5mm² for one 15Amp socket.
- (iii) 2.5mm² for maximum of ten switched 13 Amp sockets wired from 30 Amp MCB.

The wiring sizes for lighting circuits and sockets are shown on the drawings. In such cases, the sizes shown on the drawings shall prevail over the sizes specified.

Wiring sizes for other appliances shall be shown on the drawing or specified in later clauses of this specification.

2.17 SPACE FACTOR

The maximum number of cables that may be accommodated in a given size of conduit or trunking or duct is not to exceed the number in Tables B.5 and B.6 or as stated in Regulation B.91, B.117 and B.118 of the I.E.E Regulations whichever is appropriate.

2.18 INSULATION

The insulation resistance to earth and between poles of the whole wiring system, fittings and lumps, shall not be less than the requirements of the latest edition of the I.E.E Regulations. Complete tests shall be made on all circuits by the Sub-contractor before the installations are handed over.

A report of all tests shall be furnished by the Sub-Contractor to the Engineer. The Engineer will then check test with his own instruments if necessary.

2.19 LIGHTING SWITCHES

These shall be mounted flush with the walls, shall be contained in steel or alloy boxes and shall be of the gangs' ratings and type shown in the drawings. They shall be as manufactured by M.K. Electrical Ltd., or other equal and approved to KS 04 – 247: 1988

2.20 SOCKETS AND SWITCHED SOCKETS

These shall be flush pattern in steel/pvc box and shall be of the gangs and type specified in the drawings.

They shall be 13- Amp, 3-pin, shuttered, switched and as manufactured by "M.K. Electrical Co. Ltd.", or other approved equal to KS 04 – 246: 1987

2.21 FUSED SPUR BOXES

These shall be flush, D.P switched as in steel/pvc box and of type and make specified in the drawings complete with pilot light and as manufactured by "M. K. Electrical Company Ltd", or other approved equal. KS 04 – 247: 1988

2.22 COOKER OUTLETS

These shall be flush mounted with 13-A switched socket outlet and neon indicator Lamps.

The cooker control units shall be as manufactured by "M.K. Electrical Company Ltd", or other approved equal KS 04 - 247: 1988

2.23 CONNECTORS

Shall be specified in the drawings and appropriate rating. These shall be fitted at all conduit box lighting point outlets for jointing of looped P.V.C cables with flexible cables of specified quality.

2.24 LAMPHOLDERS

Shall be of extra heavy H.O skirted and shall be provided for every specified lighting fitting and shall be B.C;, E.S;, or G.E.S as required. All E.S. and G.E.S. holders shall be heavy brass type (except for plain pendants where the reinforced bakelite type shall be used). The screwed cap of the E.S and G.E.S. holders shall be connected to the neutral.

Where lampholders are supported by flexible cable, the holders shall have "cord grip" arrangements and in the case of metal shades earthing screws shall be provided on each of the holders.

The Sub-Contractor must order the appropriate type of holder when ordering lighting fittings, to ensure that the correct types of holders are provided irrespective of the type normally supplied by the manufacturers.

2.25 **LAMPS**

All lamps shall be suitable for normal stated supply voltage and the number and sizes of lamps detailed on the drawings shall be supplied and fixed. The Sub-Contractor must verify the actual supply voltage with the supply authority before ordering the lamps.

Tungsten filament lamps shall be manufactured in accordance with KS 04 - 112:1978 for general service lamps and KS 04 - 307:1985 for lamps other than general services. Tubular fluorescent lamps shall comply with KS 04 - 464:1982

Pearl lamps shall be used in all fittings unless otherwise specified.

2.26 LIGHTING FITTINGS AND STREET LIGHTING LANTERNS

This Sub-Contract shall include for the provision, handling charges, taking the delivery, safe storage, wiring (including internal wiring) assembling and erecting of all lighting fittings shown on the drawings.

All fittings and pendants shall be fixed to the conduit boxes with brass R/H screws. These to be in line with metal finish of fittings. The lighting fittings are detailed for the purpose of establishing a high standard of finish and under no circumstances will substitute fittings be permitted.

In case of rectangular shaped ceiling fittings, the extreme ends of the fittings shall be secured to suitable support in addition to the central conduit box fittings. Supports shall be provided and fixed by the Sub-Contractor.

The whole of the metal work of each lighting fittings shall be effectively bonded to earth. In the case of ball and/or knuckle joints short lengths of flexible cable shall be provided, bonded to the metal work on either side of the joints. If the above provisions are not made by the manufacturers -, the Sub-contractor shall include cost of additional work necessary in his tender. See "Flexible Cords" clause for details of internal wiring of lighting fittings.

Minimum size of internal wiring shall be 20/0.20mm (23/0067). Each lighting fitting shall be provided with number type and size of lamps as detailed on the drawings. It is to be noted that some fittings are suspended as shown on the drawings.

Where two or more points are shown adjacent to each other on the drawings, e.g. socket outlet and telephone outlet, they shall be lined up vertically or horizontally on the centre lines of the units concerned.

Normally, the units shall be lined up on vertical centre lines, but where it is necessary to mount units at low level, they shall be lined up horizontally.

2.27 POSITIONS OF POINTS AND SWITCHES

Although the approximate positions of all points are shown on the drawings, enquiry shall be made as to the exact positions of all M.C.B panels, lighting points, socket outlets etc., before work is actually commenced. The Sub-contractor must approach the Architect with regard to the final layout of all lights on the ceiling and walls.

The Sub-contractor must consult with the Engineer in liaison with the Clerk of Works, or the General Foreman on site regarding the positions of all points before fixing any conduit etc. The Sub-Contractor shall be responsible for all alterations made necessary by the non-compliance with the clause.

2.28 CURRENT OPERATED EARTH LEAKAGE CIRCUIT BREAKER

Current operated earth leakage circuit breaker shall conform to B.S.S. 4293:68 rated at 240 volts D.P. 50 cycles A.C. Mains.

The breaker shall be provided with test switch and fitted in weather proof enclosure for surface mounting. The rated load current and earth fault operating current shall be as specified in the drawings. These shall be as manufactured by Crabtree, Siemens or other equal and approved. When switches are arranged in their formation all necessary horizontal and vertical barriers shall be provided to ensure segregation from adjacent units. Means of locking the switch in the "OFF" position shall be provided.

2.29 M.V. SWITCHBOARD AND SWITCHGEAR

The switchboard shall be manufactured in accordance with KSO4-226 which co-ordinates the requirements for electrical power switchgear and associated apparatus. It is not intended that this K.S. should cover the requirements for specified apparatus for which separate Kenyan Standard exist. All equipment and material used in the switchboard shall be in accordance with the appropriate Kenya Standard.

The switchboard shall comprise the equipment shown on the drawings together with all current transformers, auxiliary fuses, labels, small wiring and interconnections necessary for the satisfactory operation of the switchboard.

The Switchboard shall be of the flush fronted, enclosed, metal clad type with full front or rear access as called for in the particular specifications, suitable for indoor use, sectionalized as necessary to facilitate transport and erection. The maximum height of the switchboard is to be approximately 2.0 metres. A suitable connection chamber containing all field terminals shall be provided at the top or bottom of the switchboard as appropriate.

Before manufacture, the Sub-Contractor shall submit to the consulting Engineer for approval of detailed drawings showing the layout, construction and connection of the switchboard.

All bus-bars and bus-bar connections shall consist of high conductivity copper and be provided in accordance with KS 04-226: 1985. The bus-bars shall be clearly marked with the appropriate phase and neutral colours which should be red, yellow, blue for the phases and black for neutral. The bus-bars shall be so arranged in the switchboard that the extensions to the left and right may be made in the future with ease should the need arise.

Small wiring, which will be neatly arranged and cleated, shall be executed in accordance with B.S. 158 and the insulation of the wiring shall be coloured according to the phase or neutral connection. Switches and fuse switches, shall be in strict accordance with KSO4-183:1978 Class 2 switches. Means of locking the switch in the "OFF" position shall be provided.

All fuse switches shall comply with KS04-183:1978, PARTS 2 and 3 a fault rating at least equal to the fault rating of the switchboard in which they are installed. Cartridge fuse links to KS 04-183:1978 category A.C. 46, class Q1 and fusing factor not exceeding 1.5 shall be supplied with each fused switch.

Mounting arrangements shall be such that individual complete fuse switches may be disconnected and withdrawn, when necessary, without extensive dismantling work.

When switches are arranged in their formation all necessary horizontal and vertical barriers shall be provided to ensure segregation from adjacent units. Means of locking the switch in the "OFF" position shall be provided.

2.30 STEEL CONDUITS AND STEEL TRUNKING

Conduits shall be of heavy gauge class "B" welded to Standard specification KS 04-180:1985. In no case will conduit smaller than 20mm diameter be used on the works. Conduits installed within buildings shall be black enameled finish except where specified otherwise. Where installed externally or in damp conditions they shall be galvanised. Conduit fittings, accessories or equipment used in conjunction with galvanised conduits shall also be galvanised or otherwise as approved by the service engineer.

Metal trunking shall be fabricated from mild steel of not less than 18 swg. All sections of trunking shall be rigidly fixed together and attached to the framework or fabric or the building at intervals of not less than 1.2m. Joint trunking shall not overhang fixing points by more than 0.5m.

All trunking shall be made electrically continuous by means of 25 x 3mm copper links across each joint and where the trunking is galvanised, the links shall be made by galvanised flat iron strips.

All trunking fittings (i.e. Bends, tees, etc.) shall leave the main through completely clear of obstructions and continuously open except through walls and floors at which points suitable fire resisting barriers shall be provided as may be necessary. The inner edge of bends and tees shall be chamfered where cables larger than 35mm² are employed.

Where trunking passes through ceilings and walls the cover shall be solidly fixed to 150mm either side of ceilings and floors and 50mm either side of walls.

Screws and bolts securing covers to trunking or sections of covers together shall be arranged so that damage to cables cannot occur either when fixing covers or when installing cables in the trough.

Where trunking is used to connect switchgear of fuseboards, such connections shall be made by trunking fittings manufactured for this purpose and not by multiple conduit couplings.

Where vertical sections of trunking are used which exceed 4.5m in length, staggered tie off points shall be provided at 4.5m intervals to support the weight of cables.

Unless otherwise stated, all trunking systems shall be painted as for conduit.

Where a wiring system incorporates galvanised conduit and trunking, the trunking shall be deemed to be galvanised unless specified otherwise.

The number of cables to be installed in trunking shall be such as to permit easy drawing in without damage to the cables, and shall in no circumstances be such that a space factor of 45% is exceeded.

Conduit and trunking shall be mechanically and electrically continuous. Conduit shall be tightly screwed between the various lengths so that they butt at the socketed joints. The internal edges of conduit and all fittings shall be smooth, free from burrs and other defects.

Oil and any other insulating substance shall be removed from the screw threads; where conduits terminate in fuse-gear, distribution boards, adaptable boxes, non-spouted switchboxes, etc., they shall, unless otherwise stated, be connected thereto by means of smooth bore male brass bushes, compression washers and sockets. All exposed threads and abrasions shall be painted using an oil paint for black enameled tubing and galvanizing paint for galvanised tubing immediately after the conduits are erected. All bends and sets shall be made cold without altering the section of the conduit.

The inner radius of the bed shall not be less than four (4) times the outside diameter of the conduit. Not more than two right angle bends will be permitted without the inter-position of a draw-in-box. Where straight runs of conduit are installed, draw-in-boxes shall be provided at distances not exceeding 15mm. No tees, elbows, sleeves, either of inspection or solid type, will be permitted.

Conduit shall be swabbed out prior to drawing in cables, and they shall be laid so as to drain of all condensed moisture without injury to end connections.

Conduits and trunking shall be run at least 150mm clear of hot water and steam pipes, and at least 75mm clear of cold water and other services unless otherwise approved by the services engineer.

All boxes shall conform to KS 04 - 668: 1986, to be of malleable iron, and black enameled or galvanised according to the type of conduit specified. All accessory boxes shall have threaded brass inserts.

Box lids where required shall be heavy gauge metal, secured by means of zinc plated or cadmium plated steel screws.

All adaptable boxes and lids of the same size shall be interchangeable.

Boxes used on surface work are to be tapped or drilled to line up with the conduit fixed in distance type saddles allowing clearance between the conduit and wall without the need for setting the conduit.

Where used in conjunction with mineral insulated copper sheathed cable, galvanized boxes shall be used and painted after erection.

Draw-in boxes in the floors are generally to be avoided but where they are essential, they must be grouped in positions approved by the services engineer and covered and by the suitable floor traps, with non-ferrous trays and covers.

The floor trap covers are to be recessed and filled in with a material to match the floor surface.

The Sub-contractor must take full responsibility for the filling in of all covers, but the filling in material will be supplied and the filling carried out by the main building contractor.

Where buried in the ground outside the building the whole of the buried conduit is to be painted with two coats of approved bitumastic composition before covering up.

Where run on the surface, unpainted fittings and joints shall be painted with two coats of oil bound enamel applied to rust and grease free metalwork.

2.31 TESTING ON SITE

The Sub-contractor shall conduct during and at the completion of the installation and, if required, again at the expiration of the maintenance period, tests in accordance with the relevant section of the

current edition of the Regulations for the electrical equipment of buildings issued by the I.E.E of Great Britain, the Government Electrical Specification and the Electric Supply Company's By-Laws.

- (a) Tests shall be carried out to prove that all single pole switches are installed in the 'live' conductor.
- (b) Tests shall be carried out to prove that all socket outlets and switched socket outlets are connected to the 'live' conductor in the terminal marked as such, and that each earth pin is effectively bonded to the earth continuity system. Tests shall be carried out to verify the continuity of all conductors of each 'ring' circuit.
- (c) Phase tests shall be carried out on completion of the installation to ensure that correct phase sequence is maintained throughout the installation. Triplicate copies of the results of the above tests shall be provided within 14 days of the witnessed tests and the Sub-contractor will be required to issue to the service engineer the requisite certificate upon completion as required by the regulations referred to above.
- (d) Any faults, defects or omissions or faulty workmanship, incorrectly positioned or installed parts of the installation made apparently by such inspections or tests shall be rectified by the Subcontractor at his own expense.
- (e) The Sub-contractor shall provide accurate instruments and apparatus and all labour required to carry out the above tests. The instruments and apparatus shall be made available to the services engineer to enable him to carry out such tests as he may require.
- (f) The Sub-contractor shall generally attend on other contractors employed on the project and carry out such electrical tests as may be necessary.
- (g) The Sub-contractor shall test to the services engineer's approval and as specified elsewhere in this specification or in standards and regulations already referred to, all equipment, plant and apparatus forming part of the works and before connecting to any power or other supply and setting to work.
- (h) Where such equipment, etc., forms part of or is connected to a system whether primarily or of an electrical nature or otherwise (e.g. air conditioning system) the Sub-contractor shall attend on and assist in balancing, regulating testing and commissioning, or if primarily an electrical or other system forming part of works, shall balance, regulate, test and commission the system to the service engineer's approval.

APPENDIX TO GENERAL SPECIFICATIONS OF MATERIALS AND WORKS

The electrical sub-contractor shall comply with the following: -

- 1. Government Electrical Specifications No. 1 and No. 2.
- 2. All requirements of Kenya Power Company Limited

SECTION C

PARTICULAR SPECIFICATIONS

OF

MATERIALS AND WORKS

ITEM	CONTENTS
1.1	LOCATION OF SITE
1.2	EXTENT OF WORKS
1.3	REGULATION AND STANDARDS
1.4	ELECTRICAL REQUIREMENTS
1.5	MANDATORY REQUIREMENTS
1.6	PART A – ELECTRICAL INSTALLATION WORKS
1.7	PART B - STRUCTURED CABLING, CCTV, AND AUDIO-VISUAL
	Installation works

PARTICULAR AND TECHNICAL SPECIFICATIONS FOR ELECTRICAL, STRUCTURED CABLING, AND STANDBY GENERATOR INSTALLATION.

PART A – ELECTRICAL INSTALLATION WORKS

1. Location of site

The site is located in Works Building - Nairobi County

2. SCOPE OF WORKS

The works to be carried out under this sub-contract comprise supply, installation, testing and commissioning of the following: -

a) Electrical Works

This shall include Conduiting, Cabling, Trunking, fittings and accessories.

b) Structured cabling works

This shall include cabling, fittings and telephone/data outlet plates.

c) CCTV Installation works

This shall include cameras, NVR, Switch, and associated cabling.

3. MATERIALS FOR THE WORKS

Materials shall be as specified in Section C and in the Bills of Quantities of this document which shall be read in conjunction with contract drawings. Alternative materials shall be accepted only after approval by the Project Manager.

4. Extent of The Works

The works to be carried out include the supply, delivery, installation, testing, commissioning and leaving in servicing condition the Electrical, Structured Cabling and Solar systems in the proposed Site as herein described in this specification. The works shall include, but not limited to the supply and installation of the following:

- Electrical cabling and fittings;
- Structured Cabling;
- > Switches; and
- ➤ CCTV

5. Regulation and Standard

The works shall comply with the provisions of the following as necessary and relevant:

- > ISO/IEC, CA, ATM CENELEC 11801
- > ANSI/EIA/TIA 56
- Latest Edition of IEE Regulation
- Kenya Bureau of Standards (KEBS)
- Institution of Electrical Engineers (I.E.E) Wiring Regulations
- Current recommendation of CCITT and CC1R
- Electric Power Act and Rules made there under.

6. ELECTRICAL REQUIREMENTS

The equipment to be supplied shall be capable of being operated from 240V AC 50Hz power supply.

7. MANDATORY REQUIREMENTS

- **A.** All equipment and materials used shall be standard components that are regularly manufactured and used in the manufacturer's system.
- **B.** All systems and components shall have been thoroughly tested and proven in actual use.
- C. All systems and components shall be provided with the availability of a, 24-hour technical assistance program (TAP) from the manufacturer. The TAP shall allow for immediate technical assistance for either the dealer/installer or the end user at no charge.
- **D.** All systems and components shall be provided with a one-day turn around repair express and 24-hour parts replacement. The repair and parts express shall be guaranteed by the manufacturer on warranty and non-warranty items.
- **E.** The supplier shall be the manufacturer, or the manufacturer appointed agent (proof to be submitted).
- **F.** The Offered system has been installed and commissioned by the supplier in other locations.

PART A: PARTICULAR SPECIFICATIONS FOR ELECTRICAL INSTALLATION WORKS

MINIMUM TECHNICAL SPECIFICATIONS FOR LED LAMPS/ LIGHTING FITTINGS

LED TUBES, PA	NELS & BULBS LIGHT FITTING							
TECHNICAL SI	TECHNICAL SPECIFICATIONS							
IEC Compliant								
Item	Minimum Specifications	Proposed solution						
Brand	State the brand, model and attach Technical Brochure (Mandatory)							
Operating	Voltage range: 240 (+/- 5%) V ac							
	Frequency range: 50-60Hz							
	Power factor 0.9 lagging							
	Total Harmonic Distortion (THD)<15%							
	 Ambient temperature range -10 to +35 Operating 							
	➤ Colour Consistency ≥ 5SDCM							
Performance	System efficacy ≥= 100lm/W							
	Lamp colour temperature: 4000K - 6500K							
	Colour Rendering Index >=80							
	Median useful life >= 30000 hrs.							
Standards Compliance	CB/EMC/CE							
	Driver/power unit/transformer - PSU-E							
General	 Optical cover/lens type - Polystyrene bowl/cover prismatic 							
	Protection class IEC - Safety class II (II)							

PART B: PARTICULAR SPECIFICATIONS FOR ICT WORKS

1. DESCRIPTION OF THE PROJECT

The works to be carried out comprise the following;

- i) Proposed supply, installation, testing and commissioning of a structured cabling system to cater for computer data points and telephone points.
- ii) Configure and set up the structured cabling system to be used on LAN,
- iii) Produce test result, warranty certification, reports and as installed drawings. The Network will be capable of supporting approximately 150 data/voice points.
- iv) Supply, install telephone cables to interconnect the data cabinets to the IP-PBX to be located in the Server Room. The works shall include inter-wiring, programming and activating all voice points.

2. REGULATIONS

The contractor shall, in execution and completion of the works in the detailed design for which he is responsible, comply with the provisions of the following as necessary and relevant:

- a) ISO/IEC, CA, ATM CENELEC 11801
- b) ANSI/EIA/TIA 56
- c) Latest Edition of IEE Regulation
- d) Kenya Bureau of Standards
- e) Electric Power Act and Rules made there under.

3. WORKING DRAWINGS

The Contractor shall submit to the Project Manager working drawings for the proposed system for approval. The drawings will show the locations of and identifiers for all cable routing and terminations, telecommunication outlets/connectors. Location of core switch and Edge switches.

4. ACTIVE DEVICES

SWITCH

Active control equipment at the LAN Edge should have the following features

- Active control equipment at the LAN Edge should support 10/100/1000 MBPS on all ports (RJ45) and Gigabit to the desktop connectivity
- The equipment should have at least two 1000BaseXGigabit uplink ports for terminating backbone Fiber.
- The equipment should support layer 3 routing.
- Should support IEEE 802.1, SSH, SNMP.
- Switch Fabric forwarding Bandwidth of 64GBPS or more.
- More than 12,000MAC addresses should be available on each switch.
- The switches should have 8/12/24/48 ports of 10/100/1000 MBPS.
- Each stack on the edge will have two links of Fiber to the core switch, totaling two fiber terminations from the core switch to the stack.
- Should support Jumbo frames.
- Total stack throughput bandwidth of 64 GBPS or more.
- Active Edge switches should be quoted with a minimum of One year of warranty covering free replacement of parts and units.
- The switches to be PoE plus

(State make and type, and enclose catalogues)

5. MINIMUM REQUIREMENTS FOR THE PROPOSED IP CCTV SYSTEM

The cameras shall have the following minimum specifications but cameras with higher specifications shall be accepted:

a) IP Bullet camera – 4MP

- 4 Mega Pixel Full HD Outdoor IP Bullet Camera with Infrared
- Built in Infrared 30 meters minimum
- imaging sensor with Wide Dynamic Range
- Motorized
- Varifocal Auto Iris lens (3-11mm)
- Minimum illumination 0.01lux (colour)
- IP network capable
- PoE capability
- H.265 video compression
- Accessible edge storage with internal MicroSD card slot
- True day and night vision capability
- I/O 1 Alarm in / 1 Alarm out
- 2 Way Audio
- Tampering detection, Face detection, Audio Detection, Motion detection & Privacy Masking and event triggered alarm processing
- Vandal proof IK-10 rating housing
- Weather proof IP66 rating
- ONVIF Compliant

(State make and type, and enclose brochures/catalogues)

b) IP Dome CCTV Camera

- 4 Mega Pixel Full HD IP Dome Camera with Infrared
- Built in Infrared 30 meters minimum

- imaging sensor with Wide Dynamic Range
- Motorized Varifocal Auto Iris lens (3-11mm)
- Minimum illumination 0.01lux (colour)
- IP network capable
- PoE capability
- H.265+ video compression
- 3D Noise reduction
- Accessible edge storage with internal MicroSD card slot
- Local Storage
- True day and night vision capability
- I/O 1 Alarm in / 1 Alarm out
- 2 Way Audio
- Tampering detection, Face detection, Audio Detection, Motion detection & Privacy Masking and event triggered alarm processing
- Vandal proof IK-10 rating housing
- Weather proof IP66 rating
- ONVIF Compliant

(State make and type, and enclose brochures/catalogues)

c. COLOR VIDEO MONITORS

The monitor should be capable of providing high levels of picture quality 10MHz bars visible at low brightness and reliability stable synchronization, black level clamping, low sensitivity and high stability.

The monitors shall be high performance color video monitors for monitoring scenes from the above cameras and viewing playback scenes from the video cassette recorders. The monitors shall be located at places to be shown on site by the project manager.

The monitor shall give stable and interference free pictures of scenes being viewed. It shall also conform to the following specifications:

Type : LED; 50,000hours panel life

System : NTSC/PAL

Screen size : 48"

: 1,920 x 1, 080 Resolution Display Colour : 16.0 million Brightness : 350cd/m² Contrast Ratio : 5,000:1 Video input signal
Power consumption : 1.0 V pk-pk

: Not more than 120W

Power input : 240V 50HZ

Interface : VGA, DVI, HDMI, RGB, Audio, Video

(State make and type, and enclose catalogues)

d. E. NETWORK VIDEO RECORDER

The network video recorder shall have the following minimum requirements:

- 16 Channels
- Recording speeds of at least 100Mbps Gigabit Ethernet connection
- Multi-screen Display: Full/4/9/16 way or as appropriate.
- 4 Hot swap HDDs (RAID 5) at 6TB each
- external storage support capability
- VGA/HDMI local monitor
- Redundant hot swap power supply
- Network management/viewer software

- In built intelligent video analysis
- H.265+ Compression
- ONVIF compatibility
- Web viewer supported
- PoE enabled ports
- Storage capacity: continuous storage for at least six (6) months and back up storage for at least one year
- Smart Video Search Feature for streamlined Investigations
- Recording resolution of 5MP minimum
- IP address filtering, user access log, authentication and encryption
- Auto Launch of Video on specified Alarms/Events
- LED status indicator
- CE, UL certification

(State make and type, and enclose catalogues)

e. <u>UNINTERRUPTIBLE POWER SUPPLY (UPS)</u>

This shall be an on-line Un-interruptible power supply with output rating able to provide power to the security surveillance system a minimum of 8 hours in case of power failure.

It shall be microprocessor- based so that both output voltage and frequency are closely regulated and continuously monitored and also provide system diagnostic and shut down protection functions. It shall feature a maintenance by-pass to enable normal routine maintenance operations to be performed without interruptions to the system.

It shall be fitted with both visual and audible alarms to indicate any change in equipment status such as:

- input power problems
- ups faults
- ups overload
- battery discharging

The UPS shall have the following characteristics:

- Lightning and Surge Protection: In accordance with ANSI/IEEE C62.41categories A and B;
- Spike Attenuation: 2000 to 1;
- Galvanic Isolation: Complete from line. Output neutral bonded to ground;
- Noise (RF) Isolation: 120 dB common-mode, 60 dB normal-mode;
- Input Voltage: 240 VAC (± 20%), 47-63 Hz;
- Output Voltage: 240 VAC;
- Regulation: Better than +3%;
- Output Waveform: Pure sine-wave, less than 5% THD;
- Efficiency: 85% to 92% on line;
- Operating Environment:
- Temperature Range –30°C to +60° C
- Humidity EIA: 90% @ 50° C.
- 3000VA, Rack mountable/free standing depending on adopted configuration with ½ hour back up time

(State make and type, and enclose catalogues)

4.0 ACCESS CONTROL INSTALLATION

a) Fingerprint and Card verification modes Biometric Reader

ltem		Minimum Specifications			
Brand		State the brand, model and attach Technical Brochure (Mandatory)			
CPU	*	400MHz DSP			
,	*	Memory 4MB flash + 8MB RAM Fingerprint sensor 500 dpi optical sensor			
Identification speed	*	2,000 match in 1 second			
•	*	10,000 templates (5,000 users)			
•	*	Log capacity 50,000 events			
RF card	*	EM, HID Prox, Mifare/Desfire, iCLASS, Felica			
Operation modes	*	Fingerprint, RF card, RF card + fingerprint			
Network interface	*	TCP/IP, RS485			
Wiegand output	*	Configurable up to 64 bits			
Internal relay	*	Deadbolt, EM lock, door strike, automatic door			
	*	Anti-passback door zones supporting 32 readers			
	*	Tamper switch and duress finger option			
	*	Support Live Fingerprint Detection Ingress Protection (IP): IP65			
Warranty		Comprehensive Manufacturer's Warranty (Attach Manufacturer's Warranty Statement)			

b) Door Module Control

c)

ltem	Minimum Specifications
Brand	State the brand, model and attach Technical Brochure (Mandatory)
	Product Features
	Wiegand readers
	 Wiegand Input 2 ch
	4 relays
	 128 KB Flash, 20 KB SRAM Memory
	Supports various connections RS-
	485 x1 - TTL input x4 - TTL output
	x6 - Wiegand x2 - Relay x4 -
	Supervised Input x4
	Comprehensive Manufacturer's Warranty
Warranty	(Attach Manufacturer's Warranty Statement)
	Minimum 1 Years

d) Finger Print Authentication Scanner

ltem	Minimum Specifications					
Brand	State the brand, model and attach Technical Brochure (Mandatory)					
Sensor Type	 Optical 					
Resolution	❖ 500dpi / 256 gray					
Support	 Live Fingerprint Detection 					
Support	 Latent Detection 					
IP65	 Supported (Sensor Surface), Scratch free 					
USB	❖ 2.0 High-speed					
Operating System	Windows/Linux (32/64bit) / Android4.1 & above					
Warranty	Comprehensive Manufacturer's Warranty (Attach Manufacturer's Warranty Statement) Minimum 1 Years					

e) Smartcard Reader/Writer

Minimum Specifications
ate the brand, model and attach echnical Brochure (Mandatory) ARM 32-bit Cortex-M3(48MHz)
128KBytes Flash / 20KBytes SRAM USB Full Speed (12Mbps)
13.56 Mhz ± 7Khz 2~5cm
Windows 2000, Windows Vista, Windows 7/ Linux (CCID driver) Omprehensive Manufacturer's Warranty Attach Manufacturer's Warranty Statement) Minimum 1 Years

e. CABLING

- a) All cables must pass through conduits or trunking.
- b) All cables and connectors shall be labeled.
- c) No distortion due to kinks, sharp bends or excessive hauling tension shall be allowed.
- d) Cables shall be run in a manner eliminating any possibility of strain on the cable itself or on the terminations.
- e) Cables shall have no joints or splices.
- f) Cables shall be kept at a minimum distance of 150mm from items liable to become hot or cold.
- g) Bending radii shall be not less than eight times the overall cable diameter.
- h) The manufacturers hauling tension shall not be exceeded.
- i) All cable ties and fixings shall be tightened to support the cable loom without distortion of the cable sheath.
- j) The STP 4 pair shall be of cat 6A grade and exceed ANSI/TIA/EIA-568-Aj and ISO/IEC 11001standards. Cat 6A structured cabling shall be used throughout the entire installation.

(State make and type, and enclose catalogues)

i. PATCH PANELS

a) Shall conform to ANSI/TIA/EIA-568A and rack mounted.

- b) Shall be equipped with RJ45 contacts of Cat 6A sockets with capacity of 12, 24 or 48 ports.
- c) Shall be earthed.
- d) Except for patch cords used to connect NICs to the RJ45 sockets, all patch cords shall be labeled at each extremity with PVC support and intelligible marking. For other components the label shall be of stiff plastic PVC type.

(State make and type, and enclose catalogues)

j. LABELING

- a) Horizontal and backbone cables shall be labeled at each end. The cable or its label shall be marked with its identifier.
- b) A unique identifier shall be marked on each faceplate to identify it as connecting hardware.
- c) Each port on the face plate shall be labeled with its identifier.
- d) A unique identifier shall be marked on each piece of connecting hardware to identify it as a connecting hardware.
- e) Each port on the connecting hardware shall be labeled with its identifier.
- f) A unique identifier shall be marked on each **port** on the connecting faceplate to identify it as a connecting hardware.

6. ADDITIONAL NOTES

Tenderers should take note of the following

- **a.** The network should be capable of carrying data, voice and video. QOS should be considered as part of installation and configuration of the network.
- **b.** All active LAN equipment should be from the same manufacturer for seamless integration, management and maintenance.
- **c.** Each floor should have a telecommunication Closet to house the necessary structured cabling components and active equipment if necessary.

7. FIELD QUALITY CONTROL

Installation personnel shall meet manufacturer's training and education requirements for implementation of extended warranty program.

8. LABELING

Use 6d if the type of termination block permits labels. Otherwise use 6e.

Use 6g if the owner does not have a standard for outlet numbering. Use 6h if required. Alter time as requested.

Labeling shall conform to ANSI/TIA/EIA-606(A) standards. In addition, provide the following:

- **a.** Label each outlet with permanent self-adhesive label with minimum 3/16 in. high characters.
 - **b.** Label each cable with permanent self-adhesive label with minimum, 1/8 in. high characters, in the following locations:
 - 1. Inside receptacle box at the work area.
 - 2. Behind the communication closet patch panel or punch block.
 - c. Use labels on face of data patch panels. Provide facility assignment records in a protective cover at each telecommunications closet location that is specific to the facilities terminated therein.
 - **d.** Use color-coded labels for each termination field that conforms to ANSI/TIA/EIA-606(A) standard color codes for termination blocks.
 - e. Mount termination blocks on color-coded backboards.

- **f.** Labels shall be machine-printed. Hand-lettered labels shall not be acceptable.
- g. Label cables, outlets, patch panels, and punch blocks with room number in which outlet is located, followed by a single letter suffix to indicate particular outlet within room, i.e., \$2107A, \$2107B. Indicate riser cables by an R then pair or cable number.
- h. Mark up floor plans showing outlet locations, type, and cable marking of cables. Turn these drawings over to the owner two (2) weeks prior to move in to allow the owner's personnel to connect and test owner-provided equipment in a timely fashion.
- i. Three (3) sets of as-built drawing shall be delivered to the owner within four (4) weeks of acceptance of project by the owner. A set of as-built drawings shall be provided to the owner in magnetic media form and utilizing CAD software that is acceptable to the owner. The magnetic media shall be delivered to the owner within six (6) weeks of acceptance of project by owner.

9. TESTING

- a. Testing shall conform to ANSI/TIA/EIA-568-B.1 standard. Testing shall be accomplished using level IIe or higher field testers.
- b. Test each pair and shield of each cable for opens, shorts, grounds, and pair reversal. Correct grounded, and reversed pairs. Examine open and shorted pairs to determine if problem is caused by improper termination. If termination is proper, tag bad pairs at both ends and note on termination sheets.
 - 1. Perform testing of copper cables with tester meeting ANSI/TIA/EIA-568-B.1 requirements.
 - 2. If copper backbone cable contains more than one (1) percent bad pairs, remove and replace entire cable.

Use 2 or 3 as required.

3. If copper cables contain more than the following quantity of bad pairs, or if outer sheath damage is cause of bad pairs, remove and replace the entire cable:

CABLE SIZE	MAXIMUM BAD PAIRS				
<100	1				
101 to 300	1 – 3				
301 to 600	3 – 6				
>601	6				

c. If horizontal cable contains bad conductors or shield, remove and replace cable.

Initially test optical cable with a light source and power meter utilizing procedures as stated in ANSI/TIA/EIA-526-14A: OFSTP-14A Optical Power Loss Measurements of Installed Multimode Fiber Cable Plant and ANSI/TIA/EIA-526-7 Measurement of Optical Power Loss of Installed Single Mode Fiber Cable Plant. Measured results shall be plus/minus 1 dB of submitted loss budget calculations. If loss figures are outside this range, test cable with optical time domain reflectometer to determine cause of variation. Correct improper splices and replace damaged cables at no charge to the owner.

- 1) Cables shall be tested at 850 and 1300 nm for multimode optical fiber cables.
- 2) Cables shall be tested at 1310 and 1550 nm for single mode optical fibers.
- 3) Testing procedures shall utilize "Method B" One jumper reference.

- 4) Bi-directional testing of optical fibers is required.
- **d.** Perform optical time domain reflectometer (OTDR) testing on each fiber optic conductor.

Measured results shall be plus/minus 1 dB of submitted loss budget calculations.

- i Submit printout for each cable tested.
- ii Submit 3.5 in. disks with test results and program to view results.
- **e.** Where any portion of system does not meet the specifications, correct deviation and repeat applicable testing at no additional cost.

10. BROCHURES AND TECHNICAL LITERATURE

Tenderers <u>must</u> enclose together with their submitted bids brochures detailing technical Literature and specifications of all the components of the structured cabling system. The brochures shall be used to evaluate the suitability of these components.

Any bid submitted without the brochures shall be considered **technically non-responsive**, and may subsequently be disqualified.

11. DEVIATIONS FROM THE SPECIFICATION

The tenderer shall give details of any equipment which does not meet the specification, or any other deviations, omissions, additions or alternatives in respect of the set which he is offering.

If none, write none.

SCHEDULE OF CONTRACT DRAWINGS

SCHEDULE OF CONTRACT DRAWINGS

DRAWING NO.	DRAWING TITLE
As shall be issued by the Engineer	

NOTE:

Tenderers are advised to inspect the electrical drawings at the office of the **Chief Engineer** (Electrical) – State Department for Public Works, at Chief Engineer's (Electrical) Office, Hill Plaza Building, Community area, Nairobi along Ngong road, during normal working hours.

SECTION E TECHNICAL SCHEDULE

TECHNICAL SCHEDULE

- 1. The technical schedule shall be submitted by tenderers to facilitate and enable the Project Manager to evaluate the tenders, especially where the tenderer intends to supply or has based his tender sum on equipment, which differs in manufacture, type or performance from the specifications indicated by the Project Manager.
- 2. This schedule shall form part of the technical evaluation criterion, and tenderers are therefore advised to complete the schedule as they shall be considered non-responsive.

NB. The tenderer must complete in full the technical schedule. Apart from the information required in the technical schedule, the tenderer **MUST SUBMIT LEGIBLE** comprehensive manufacturer's technical brochures and performance details for all items listed in this schedule and **CLEARLY HIGHLIGHT THE SPECIFIC REQUIRED ITEM ONLY**.

Technical Schedule

	DESCRIPTION	MAKE	MODEL NO
1.	MCBs and MCCBs		
2.	Socket outlets		
3.	Trunking		
4	SC copper cable		
5	Light Switches		
6. 7. 8. 9. 10. 11. 12. 13. 14. 15.	Lighting fittings a) Mirror Light b) Waterproof circular fitting c) 600 x 600 LED Panel d) Chandelier e) Pendant Light 48 port switch 48 port patch panel Patch code. Data outlets Data Cabinet UPS CCTV Cameras NVR LED Screen		

SECTION F SCHEDULE OF UNIT RATES

SCHEDULE OF UNIT RATES

- 1. The tenderer shall insert unit rates against the items in the following schedules and may add such other items as he considers appropriate.
- 2. The unit rates shall include for supply, transport, insurance, delivery to site, storage as necessary, assembling, cleaning, installing, connecting, profit and maintenance in defects liability and any other obligation under this contract.
- 3. The unit rates will be used to assess the value of additions or omissions arising from authorized variations to the contract works.
- 4. Where trade names or manufacturer's catalogue numbers are mentioned in the specification, the reference is intended as a guide to the type of article or quality of material required. Alternative brands of **equal** and **approved** quality will be accepted.
- 5. The prices quoted shall be deemed to include for all obligations under the sub-contract including but not limited to supply of materials, labour, delivery to site, storage on site, installation, testing, commissioning and all taxes (including V.A.T and all taxes applicable at the time of tender.

SCHEDULE OF UNIT RATES

ITEM	DESCRIPTION	QTY/UNIT	RATE(KSHS)
1.	Cables PVC SWA PVC Câbles:- a) 6 mm sq. 4 core b) 4.0 mm sq 4 core c) 10.0 mm sq 4 core	LM LM LM	
2.	100A 4-way TPN Distribution Board.	No.	
3.	Blanking Cover for Twin socket outlet points.	No.	
4.	2500VA UPS	No.	
5.	12 port edge switch POE capabilities	No.	
6.	18 U Wall Mounted cabinet	No.	
7.	55" LED Screen	No.	
8.	48 port Edge Switch	No.	

SECTION G BILLS OF QUANTITIES

BILLS OF QUANTITIES

A) PRICING OF PRELIMINARIES ITEMS.

Prices will be inserted against item of preliminaries in the sub-contractor's Bills of Quantities and specification. These Bills are designated as Bill No.1 in this Section. Where the sub-contractor fails to insert his price in any item he shall be deemed to have made adequate provision for this on various items in the Bills of Quantities. The preliminaries form part of this contract and together with other Bills of Quantities covers for the costs involved in complying with all the requirements for the proper execution of the whole of the works in the contract.

The Bills of Quantities are divided generally into three sections: -

a) Preliminaries - Bill 1

Sub-contractor's preliminaries are as per those described in section C – sub-contractor preliminaries and conditions of contract. The sub-contractor shall study the conditions and make provision to cover their cost in this Bill. The number of preliminary items to be priced by the Tenderer has been limited to tangible items such as site office, temporary works and others. However, the Tenderer is free to include and price any other items he deems necessary taking into consideration conditions he is likely to encounter on site.

b) Installation Items and Other Bills

The brief description of the items in these Bills of Quantities should in no way modify or supersede the detailed descriptions in the contract Drawings, conditions of contract and specifications.

The unit of measurements and observations are as per those described in clause 1.05 of the section C.

c) Summary

The summary contains tabulation of the separate parts of the Bills of Quantities carried forward with provisional sum, contingencies and any prime cost sums included. The sub-contractor shall insert his totals and enter his grand total tender sum in the space provided below the summary.

This grand total tender sum shall be entered in the Form of Tender provided elsewhere in this document

B) NOTES FOR BILLS OF QUANTITIES

- 1. The Bills of Quantities form part of the contract documents and are to be read in conjunction with the contract drawings and general specifications of materials and works.
- 2. The prices quoted shall be deemed to include for all obligations under the sub-contract including but not limited to supply of materials, labour, delivery to site, storage on site, installation, testing, commissioning and all taxes (including V.A.T and all taxes applicable at the time of tender.
- 3 All prices omitted from any item, section or part of the Bills of Quantities shall be deemed to have been included to another item, section or part.
- 4. The brief description of the items given in the Bills of Quantities are for the purpose of establishing a standard to which the sub-contractor shall adhere to. Otherwise, alternative brands of equal and approved quality will be accepted.
 - Should the sub-contractor install any material not specified here in before receiving approval from the Project Manager, the sub-contractor shall remove the material in question and, at his own cost, install the proper material.
- 5. The grand total of prices in the price summary page must be carried forward to the **Form of Tender**.
- 6. Tenderers must enclose, together with their submitted tenders, **detailed manufacturer's Brochure**s detailing Technical Literature and specifications on the items they intend to offer.

This shall be used in the tender evaluation to determine the first line aesthetics and quality of fittings offered.

BILL NO. 1 ELECTRICAL INSTALLATION

Item	Description	Qty	Unit	Rate Kshs	Cost Kshs
	SUPPLY, DELIVER, INSTALL, TEST AND COMMISSION THE FOLLOWING:-				
	LIGHTING POINTS AND SWITCHES				
1.01	Lighting points wired in 3 x 1.5mm ² PVC/SC CU cables drawn in 20mmØ surface mounted HG/PVC conduits complete with all necessary accessories but excluding switches for:-				
	I) One way switching	47	No.		
	ii) Two way switching	58	No.		
1.02	10A, moulded plastic ivory white switch plates as MK or approved equivalent as follows:- I) One gang one way ii) two gang two way ii) two gang one way		No. No. No.		
1.03	Lighting fittings complete with lamps of				
	appropriate wattage and colour rendering and fixing materials as follows:-				
	I) Type A	8	No.		
	ii) Type C	4	No.		
	iii) Type D	66	No.		
	iv) Type F	12	No.		
	v) Type H	1	No.		
	vi) Type J	6	No.		
	vii) Type K	5 2	No.		
	ix) Type EXIT		No.		
-	Total carried to Bill No 4 Collect	ion P	age		

Item	Description	Qty	Unit	Rate Kshs	Cost Kshs
	Total Brought forward from the previous page				
	POWER POINTS				
1.04	Raw power socket outlet power points comprising wiring in 3 x 2.5mm ² PVC/SC CU cables drawn in 25mmØ concealed HG PVC conduits/trunking including all conduit accessories but excluding plates	29	No.		
1.05	13A moulded switched socket outlet plates as MK or approved equivalent as follows: I) Twin switched	29	No.		
1.06	Hand drier power points comprising wiring in 3 x 4mm ² PVC/SC/CU cables drawn in 25mmØ HG/PVC conduits complete with all necessary accessories	2	No.		
1.07	20A, DP control switch with neon light and cord outlet for item above as MK or approved equivalent	2	No.		
1.08	Undersink instantaneous water heater power points comprising wiring in 3 x 4mm ² PVC/SC/CU cables drawn in 25mmØ concealed HG PVC conduits	1	No.		
1.09	20A DP control switch marked 'Water Heater' with neon light and cord outlet for item above as MK or approved equivalent	1	No.		
1.10	Cooker Unit power points comprising wiring in 3x6mm2 PVC/SC/CU cables drawn in 32mm diameter HG/PVC conduit complete	1	No.		
1.11	45A Cooker control unit complete with 13A socket outlet and pilot lamps as MK or approved equivalent.	1	No.		
	Total for carried forward to the N	lext p	age		

Item	Description	Qty	Unit	Rate Kshs	Cost Kshs		
	Total Brought forward from the previous page						
1.12	Kitchen extract fan power points comprising wiring in 3 x 2.5mm ² PVC/SC/CU cables drawn in 25mmØ concealed HG PVC conduits	1	No.				
1.13	20A, DP control switch with neon light and cord outlet for item above as MK or approved equivalent	1	No.				
1.14	Bathroom/Toilet extract fan power points comprising wiring in 3 x 2.5mm ² PVC/SC/CU cables drawn in 25mmØ concealed HG PVC conduits	4	No.				
1.15	20A, DP control switch with neon light and cord outlet for item above as MK or approved equivalent	4	No.				
1.16	Air Conditioning Unit power points comprising wiring in 3 x 4mm2 PVC/SC CU cables drawn in 32mmØ concealed HG PVC conduits	6	No.				
1.17	20A DP control switch with neon light and cord outlet for item above as MK or approved equivalent	6	No.				
1.18	Fire alarm control panel power points comprising wiring in 3 x 2.5 mm ² PVC/SC CU cables drawn in 25mmØ concealed HG PVC conduits including all conduit accessories but excluding plates	1	No.				
1.19	20A, switched fused spur DP control switch with neon light and cord outlet for item above as MK or approved equivalent	1	No.				
1.20	FIRE ALARM SYSTEM Fire Alarm points comprising wiring in 1.5mm ² heat resistant cables drawn in 20mmØ concealed HG PVC conduits		No.				
Total for carried forward to the Next page							

Item	Description	Qty	Unit	Rate Kshs	Cost Kshs	
	Total Brought forward from the previous page					
1.21	Addressable Photoelectric Smoke Detector as Eaton or Approved Equivalent	14	No.			
1.22	Addressable Rate of Rise Heat Detector as Eaton or Approved equivalent	1	No.			
1.23	Addressable Manual Fire Alarm 'Break Glass' call points as Eaton or approved equivalent.	2	No.			
1.24	Addressable Electronic Fire Alarm sounder complete with Red Flashing beacon as Eaton or approved equivalent.		No.			
1.25	Single loop Microprocessor based Addressable Fire Alarm Control Panel as Eaton or Approved Equivalent	1	No.			
	DATA/TELEPHONE/TELEVISION & ACCESS CONTROL					
1.26	150 X 50mm - 3 compartment, gauge 16 sheet Deep Powder coated metal trunking complete with bends, outlet plates and other necessary accessories As Manufactured by Power Technics	60	LM			
1.27	Data/Telephone outlet points comprising 25mmØ concealed HG PVC conduits complete with draw wire.	32	No.			
1.28	Television cord outlet points comprising 25mmØ HG PVC conduits complete with T.V co-axial socket outlet as M.K or Approved Equivalent	3	No.			
1.29	Access Control points comprising draw wire in concealed 20mm Ø HG PVC Conduits all emanating from the server room/security office	5	No.			
Total for carried forward to the Next page						

Item	Description	Qty	Unit	Rate Kshs	Cost Kshs
	Total Brought forward from the previous page				
	POWER DISTRIBUTION				
1.30	100A, 8-Way, TPN DB surface/flush mounted as EATON or approved equivalent	1	No.		
1.31	16 mm ² 4-C PVC/SWA/PVC copper cable to DB above c/w appropriate cable lugs	55	Lm		
	I) Cable glands for above cable	4	No.		
1.32	SP Miniature circuit breakers for the distribution boards above				
	I) 10A SP MCB	4	No.		
	I) 20A SP MCB	15	No.		
	I) 32A SP MCB	4	No.		
	ii) 45A SP MCB	1	No.		
1.33	Allow for labelling the circuit breakers under this section including all the incoming and outgoing circuits as per the specifications	1	Item		
	Total for Bill No. 2: C/F to Summar	v Pas	ge G/1	2	

BILL NO. 2: STRUCTURED CABLING WORKS

Item	Description	Qty	Unit	Rate	Kshs.
2.01	36U free standing/wall mounted metal cabinet/ with glass door complete with Cable Managers, fans, power outlet points, grounding kits and castors. The data cabinet to be complete with 1No. APC Power Distribution Units (PDU) to accommodate power for the active devices to engineers approval	1	No.		
2.02	48 port RJ45 cat 6A (or latest) patch panel for UTP termination as Siemons B1:B15 or approved equivalent.	1	No.		
2.03	1M RJ45-RJ45 Cat 6A (or latest) UTP factory terminated patch cord as Siemons or approved equivalent to be used in cabinet.	32	No.		
2.04	2U vertical cable managers/organizers and as Siemon or approved equivalent	2	No.		
2.05	Cat 6A (or latest) UTP 4-pair cable as Siemons or approved equivalent laid between cabinet and work station.	1000	M		
2.06	RJ45 Cat 6A (or latest) UTP (Dual) outlet complete with faceplate and labelling system as Siemons or approved equivalent.	16	No.		
2.07	48 Port Managed Gigabit Ethernet Switch with PoE plus (at least 480W) and 2 SFP Ports as CISCO 9200 catalyst switch (currently available in the market and being supported by Cisco) or approved equivalent	1	No.		
2.08	PoE/PoE+ Wireless Access Point with 2No. 10/100/1000 ethernet ports c/w with ceiling mount accessories as Ubiquity Unify or Approved Equivalent	2	No.		
	Total C/F to next page				

Item	Description	Qty	Unit	Rate	Kshs.					
	Total C/F from previous page									
2.08	Earthing the system at the Cabinet level	1	Item							
2.09	3000VA Rack mountable Uninterruptible power supply unit	1	No.							
2.10	Any other items necessary to complete the structured cabling satisfactorily. (List and give quantities of the items) a) cable ties b) cable manager c) glue d) wood screws	1	Item							
	Total for BILL No. 4 C/F to Summary Pa	ge G/12	Total for BILL No. 4 C/F to Summary Page G/12							

BILL No. 3: IP CCTV SYSTEM INSTALLATIONS							
Item	Description	Qty	Unit	Rate	Kshs.		
	Supply, Install, Test, integration and Commission the following as described in the specifications:						
3.01	Outdoor, IP POE, Vandal resistant Dome camera complete with housing, appropriate mounting brackets and all other accessories to engineers approval as Hanwa or Approved Equivalent	4	No.				
3.02	Category 6A, 12 Port Patch Panel and as Siemon or approved equivalent.	1	No				
3.03	1M RJ45-RJ45 Cat 6A UTP factory terminated patch cord as Siemons or approved equivalent to be used at work	4	No				
3.04	Cat 6A UTP 4-pair cable as Siemons or approved equivalent	250	M				
3.05	16 Channels IP Network video recorder with 16 PoE/PoE+ ports and HDD 2TB as described in the technical specifications of this document	1	No.				
	32" LED HD panel display as described in particular specifications complete with necessary accessories	1	No.				
3.07	Allow Kshs. 100,000 for Engineer supervision of installed system	1	Item				
3.08	Provide telecommunication earth including fuses lighting arrestors and frame earthing to engineers approval	1	Item				
3.09	30A High voltage surge protector as Sollateck or approved equivalent	1	No.				
	Total for Bill No. 2: C/F to Summary Pa	age G/12	2				

Bill No. 4 - ACCESS CONTROL

Item	Description	Qty	Unit	Rate	Amount (Kshs)
	Supply, install, test and commission the following items:				
4.01	Secure I/O Module complete with Integrated Power Supply and batteries as suprema or approved equivalent.	4	No.		
4.02	Software capable of controlling 20 doors as suprema or approved equivalent.	1	Item		
4.03	Electric strike complete with door closer	4	No.		
4.04	IP Based Door Fingerprint biometric & card reader as specified in Particular Specifications as suprema or approved equivalent.	4	No.		
4.05	Door Exit switch	4	No.		
4.06	Override Key switch	4	No.		
4.07	Emergency Break glass	4	No.		
4.08	Desk mounted Finger print Authentication Scanner, 125kHz/13.56 MHz as suprema BioMini Plus 2 or approved equivalent	1	No.		
4.09	Smartcard Reader/Writer as specified in Particular Specifications as suprema DE-620 or approved equivalent.	1	No.		
4.10	MIFARE Cards with the individual employee's name as specified in Particular Specifications.	20	No.		
4.11	Mylair cable for access control system	80	lm		
4.12	Cat 6-E, 4 pair STP terminated in RJ 45 as appropriate and drawn in new conduits and trunking. From the reader to the each floor switch	180	LM		
	Total for Access Control carried to summary page G/12	<u> </u>	<u> </u>		

SUMM	ARY PAGE	
Item	Description	KSHS
1.0	Sub-total Bill No. 1: Electrical installation system B/F from page G/7	
2.0	Sub-total Bill No. 2: Structured Cabling B/F from page G/9	
3.0	Sub-total Bill No. 3: IP CCTV system B/F from page G/10	
3.0	Sub-total Bill No. 4: Access Control system B/F from page G/11	
4.0	Provisional sum of Kshs. 100,000 for training and certification of (3No. Users/equipment operators and 2No. Technical staff from SDPW) as described in the technical specifications of this document	100,000
5.0	Provisional sum of Kshs. 100,000 for Testing and Commissioning of installed system to Engineer's Approval	100,000
	Grand total for Electrical Services Installations works C/F to Grand Summary Page	
TOTA	L AMOUNT IN WORDS	

SCHEDULE OF LIGHT FITTINGS

Item	Description
	LIGHTING FITTINGS
a)	Light Fittings complete with all accessories and lamps as follows: Type A Standard Recessed 600 X 600mm Panel Light, 36W, 115Lm/W, 4000K LED, 50000 hrs Lamp Life, Steel Housing and Aluminum Rim, Polystyrene Diffuser with Integral Control Gear as PHILIPS or approved equivalent.
b)	Type B 12W Cast aluminium bulkhead with moulded glass cover for fluorescent lamps. IP65 protection As Thorn DB Bulkhead or approved equivalent
c)	Type C 200mm dia. Circular Surface Ceiling LED Downlight 11W, 4000K, 115Lm/W, 30000 hrs Lamp Life, Plastic Housing and Polycarbonate Diffuser with Integral Control Gear as PHILIPS or approved equivalent.
d)	Type D 90mm dia. Decorative Circular Surface Ceiling LED Downlight 8W, 4000K, 50000 hrs Lamp Life, Plastic Housing and Polycarbonate Diffuser with Integral Control Gear as PHILIPS or approved equivalent.
c)	Type E Decorative Wall Bracket Luminaire as MICROMARK or approved equivalent.
e)	Type Exit Self-contained single sided EXIT Sign for viewing up to 30m distance, maintained operation, 3W, 3 hours emergency duration with LED strip and ISO Exit legends As THORN or approved equivalent.
d)	Type F Circular LED 11W, 4000K, 115Lm/W, IP65 Rated, 50000 hrs Lamp Life, Surface Ceiling Light with Plastic Housing and Polycarbonate Diffuser as PHILIPS for Washrooms .
f)	Type G LED Mirror Strip Luminaire 8W, 4000K, 95Lm/W, 50000 hrs Lamp Life Complete with Diffuser cw pull cord as PHILIPS or approved equivalent.
g)	Type H 1200mm, 1X16W Slim section, 1P 20 LED batten fitting with as PHILIPS or approved equivalent.
h)	Type I RGB LED Strip light for Buffered Ceiling as PHILIPS or approved equivalent.
i)	Type J Pendant light complete with 8W LED Bulb 4000K 100Lm/W as Phillips or Approved Equivalent
j)	Type K Chandalier complete with 6No. 8W LED bulbs as Phillips or Approved Equivalent



SECTION III - EVALUATION AND QUALIFICATION CRITERIA 1.0 GENERAL PROVISIONS

- 1.1 This section contains the criteria that the Employer shall use to evaluate tender and qualify tenderers. No other factors, methods or criteria shall be used other than specified in this tender document. The Tenderer shall provide all the information requested in the forms included in Section IV, Tendering Forms. The Procuring Entity shall use the Standard Tender Evaluation Document for Goods and Works for evaluating Tenders.
- 1.2 Wherever a Tenderer is required to state a monetary amount, Tenderers should indicate the Kenya Shilling equivalent using the rate of exchange determined as follows:
 - a) For construction turnover or financial data required for each year Exchange rate prevailing on the last day of the respective calendar year (in which the amounts for that year are to be converted) was originally established.
 - b) Value of single contract Exchange rate prevailing on the date of the contract signature.
 - c) Exchange rates shall be taken from the publicly available source identified in the ITT 14.3. Any error in determining the exchange rates in the Tender may be corrected by the Procuring Entity.

1.3 EVALUATION AND CONTRACT AWARD CRITERIA

The Procuring Entity shall use the criteria and methodologies listed in this Section to evaluate tenders and arrive at the Lowest Evaluated Tender. The tender that (i) meets the qualification criteria, (ii) has been determined to be substantially responsive to the Tender Documents, and (iii) is determined to have the Lowest Evaluated Tender price shall be selected for award of contract.

2.0 PRELIMINARY EXAMINATION FOR DETERMINATION OF RESPONSIVENESS Preliminary examination for Determination of Responsiveness

The Procuring Entity will start by examining all tenders to ensure they meet in all respects the eligibility criteria and other mandatory requirements in the ITT, and that the tender is complete in all aspects in meeting the requirements provided for in the preliminary evaluation criteria outlined below. The Standard Tender Evaluation Report Document for Goods and Works for evaluating Tenders provides very clear guide on how to deal with review of these requirements. Tenders that do not pass the Preliminary Examination will be considered non-responsive and will not be considered further.

S/No	MANDATORY REQUIREMENTS(MR)
MR1	Valid Copy of certificate of incorporation/ Registration.
MR2	Valid Current Tax Compliance Certificate from Bidding Company, and if Consortium, from each member of the consortium.
MR3	Submission of valid CR12 form showing the list of directors /shareholding (issued within the last 12 months) or National Identity Card(s) for Sole Proprietorship / Partnership
MR4	Over Five years' experience in works of similar nature.
MR5	Dully filled form of tender
MR6	Dully filled and signed Confidential business questionnaire
MR7	Duly signed and stamped Statement of compliance.

	Submission of original tender document properly BOUND and sequentially serialized and all pages must be initialed or signed. (NB: Use of Spring or Box Files will not be allowed and will result in automatic disqualification.)
MR9	Valid Copy of Current Single Business permit
	The Tender Security (Bid Bond) of 1 % of the contract sum in form of Bank Guarantee from a reputable bank or insurance company approved by Public Procurement Regulatory Authority (PPRA).
	Provide proof of authorization (in form of a Power of attorney signed by commissioner of oaths) as a Tender Signatory if the signatory is not a director or partner of the firm.
	NCA registration certificate and valid NCA 7 and above annual practicing license in Mechanical Services installation works category

Note:

The bid security shall be in accordance with the following notes; -

- (A) The tenderer shall furnish as part of his tenders a tender surety in the amount as stated in the tender document on the Appendix to Instructions to Tenderers".
- (B) The unconditional Tender surety shall be in Kenya shillings and be in form of a certified cheque, bank draft, an irrevocable letter of credit or a guarantee from a reputable Bank/ Insurance approved by PPRA located in the Republic of Kenya. The format of the surety shall be in accordance with the sample form included in the tender documents and the tender surety shall be valid for 150 days from the date of tender opening".
- (C) A substantially responsive tender is one which conforms to all terms and condition and specifications of the tender document without material deviation or reservation and has a valid Bank/Insurance guarantee".

The employer/procuring entity may seek further clarification/confirmation if necessary, to confirm authenticity/compliance of any condition of the tender. Further, in case of a discrepancy between the amounts stated in the appendix to instruction to tenderers and the one stated in the advertisement or invitation letter, the bid security shall be taken as the amount in the advertisement/ letter of invitation.

The bidders' who do not satisfy any of the above requirements shall be considered non-responsive and their tenders will not be evaluated further.

3.0 TENDER EVALUATION (ITT 35)

Price evaluation: in addition to the criteria listed in ITT 35.2 (a) - (d) the following criteria shall apply:

i)	Alternative Completion Times, if permitted under ITT13.2, will be evaluated as follows:
ii)	Alternative Technical Solutions for specified parts of the Works, if permitted under ITT 13.4, will be evaluated as follows
iii)	Other Criteria; if permitted under ITT 35.2(j):

4.0 MULTIPLE CONTRACTS

4.1 Multiple contracts will be permitted in accordance with ITT 35.4. Tenderers are evaluated on basis of Lots and a lowest evaluated tenderer identified for each Lot. The Procuring Entity will select one Option of the two Options listed below for award of Contracts.

OPTION 1

- i) If a tenderer wins only one Lot, the tenderer will be awarded a contract for that Lot, provided the tenderer meets the Eligibility and Qualification Criteria for that Lot.
- ii) If a tenderer wins more than one Lot, the tender will be awarded a contract for all won Lots, provided the tenderer meets the aggregate Eligibility and Qualification Criteria for all the won Lots. The tenderer will be awarded only the combinations for which the tenderer qualifies and the others will be considered for award to second lowest the tenderers.

OPTION 2

The Procuring Entity will consider all possible combinations of won Lots [contract(s)] and determine the combination with the lowest evaluated price. Tenders will then be awarded to the Tenderer or Tenderers in the combination provided the tenderer meets the aggregate Eligibility and Qualification Criteria for all the won Lots.

5.0 ALTERNATIVE TENDERS (ITT 13.1)

Alternative Tenders (ITT 13.1)

An alternative if permitted under ITT 3.1, will be evaluated as follows:

The Procuring Entity shall consider Tenders offered for alternatives as specified in Part 2 - Works requirements. Only the technical alternatives, if any, of the Tenderer with the Best Evaluated Tender conforming to the basic technical requirements shall be considered by the Procuring Entity.

6.0 MARGIN OF PREFERENCE

- 6.1 If the TDS so specifies, the Procuring Entity will grant a margin of preference of fifteen percent (15%) to be loaded on evaluated prices of the foreign tenderers, where the percentage of shareholding of Kenyan citizens is less than fifty- one percent (51%).
- 6.2 Contractors shall be asked to provide, as part of the data for qualification, such information, including details of ownership, as shall be required to determine whether, according to the classification established by the Procuring Entity, a particular contractor or group of contractors qualifies for a margin of preference.
- 6.3 After Tenders have been received and reviewed by the Procuring Entity, responsive Tenders shall be assessed to ascertain their percentage of shareholding of Kenyan citizens. Responsive tenders shall be classified into the following groups:
 - i) Group A: tenders offered by Kenyan Contractors and other Tenderers where Kenyan citizens hold shares of over fifty one percent (51%).
 - ii) *Group B*: tenders offered by foreign Contractors and other Tenderers where Kenyan citizens hold shares of less than fifty one percent (51%).
- 6.4 All evaluated tenders in each group shall, as a first evaluation step, be compared to determine the lowest tender, and the lowest evaluated tender in each group shall be further compared with each other. If, as a result of this comparison, a tender from Group A is the lowest, it shall be selected for the award of contract. If a tender from Group B is the lowest,

an amount equal to the percentage indicated in Item 6.1 of the respective tender price, including unconditional discounts and excluding provisional sums and the cost of day works, if any, shall be added to the evaluated price offered in each tender from Group B. All tenders shall then be compared using new prices with added prices to Group B and the lowest evaluated tender from Group A. If the tender from Group A is still the lowest tender, it shall be selected for award. If not, the lowest evaluated tender from Group B based on the first evaluation price shall be selected.

- 7.0 Post qualification and Contract award (ITT 39), more specifically,
 - a) In case the tender <u>was subject to post-qualification</u>, the contract shall be awarded to the lowest evaluated tenderer, subject to confirmation of pre-qualification data, if so required.
 - b) In case the tender <u>was not subject to post-qualification</u>, the tender that has been determined to be the lowest evaluated tenderer shall be considered for contract award, subject to <u>meeting each of the following conditions</u>.
 - i) The Tenderer shall demonstrate that it has access to, or has available, liquid assets, unencumbered real assets, lines of credit, and other financial means (independent of any contractual advance payment) sufficient to meet the construction cash flow of Kenya Shillings ------

 - iii) At least 3 of contract(s) of a similar nature executed within Kenya, or the East African Community or a broad, that have been satisfactorily and substantially completed as a prime contractor, or joint venture member or sub-contractor each of minimum value Kenya shillings ------ equivalent.
 - iv) Contractor's Representative and Key Personnel, which are specified as below
 - v) Contractors key equipment listed on the table "Contractor's Equipment" below and more specifically listed as [specify requirements for each lot as applicable]

Main Scope of Works ofthis Tender	Quantity(No) (Minimum)	Owned	Hired/ leased
Total			

- i) Other conditions depending on their seriousness.
- a) History of non-performing contracts:

Tenderer and each member of JV in case the Tenderer is a JV, shall demonstrate that non-performance of a contract did not occur because of the default of the Tenderer, or the member of a JV in the last 2 years. The required information shall be furnished in the appropriate form.

b) Pending Litigation

Financial position and prospective long-term profit ability of the Single Tenderer, and in the case the Tenderer is a JV, of each member of the JV, shall remain sound according to criteria established with respect to Financial Capability under Paragraph (i) above if all pending litigation will be resolved against the Tenderer. Tenderer shall provide information on pending litigations in the appropriate form.

c) Litigation History

There shall be no consistent history of court/arbitral award decisions against the Tenderer, in the last 2 years. All parties to the contract shall furnish the information in the appropriate form about any litigation or arbitration resulting from contracts completed or on going under its execution over the years specified. A consistent history of awards against the Tenderer or any member of a JV may result in rejection of the tender.

QUALIFICATION FORM*

Item No.	Qualification Subject	Qualification Requirement	Documents To be Completed/provided byTenderer	For Procuring Entity's Use (Qualification met orNotMet)				
A. PREL	A. PRELIMINARY EVALUATION							
1.	Nationality	Nationality in accordance with ITT 4.5	Duly filled Forms ELI - 1.1 and 1.2					
2.	Tax Obligations for Kenyan Tenderers	Has produced a current tax clearance certificate or tax exemption certificate issued by Kenya Revenue Authority in accordance with ITT 3.14.	Valid Tax Compliance Certificate or Tax Exemption Certificate					
3.	Company Registration	Has produced Valid Copy of certificate of incorporation / Registration from the registrar of companies	Certified copy of Certificate of Incorporation or Registration as the case may be					
4.	Allowed to do business	Has produced a Copy of Current Single Business permit from the county government	Certified copy of Single Business Permit from the County Government					
5.	Directors	Has produced a valid Copy of CR12 from the department of the registrar or National Identity Card(s) for Sole Proprietorship/Partnership.	Certified copy of CR12 or National Identity Card as the case may be					
6.	NCA Registered	Has produced Valid NCA registration certificate and annual practicing licenses as for NCA 7 category and above.	Copy of current NCA registration and practicing certificates					
7.	Conflict of Interest	No conflicts of interest in accordance with ITT 3.3	Duly filled disclosure of interest Form in the Confidential Business Questionnaire					
8.	Public Procurement Regulatory Authority (PPRA) Eligibility	Not having been declared ineligible by the PPRA as described in ITT 3.7	Duly filled and signed self- declaration Form SD1					
9.	State-Owned Enterprise	Meets conditions of ITT 3.8	Attach copies of certified documents stated in Forms ELI - 1.1 and 1.2					

Qualification Subject	Qualification Requirement	To be Completed/provided byTenderer	For Procuring Entity's Use (Qualification met orNotMet)
History of Non- Performing Contracts, Pending Litigation and Litigation History	Meets Post qualification and Contract ward (ITT 39) conditions set out in the Evaluation and Qualification Criteria 7 (iv) (a-c)	Duly filled and signed self- declaration Form CON-2	
Attendance of Pre-Tender Site Visit	Attend Pre-Tender Site Meeting	Certificate of Pre-Tender Site Visit duly signed by the Project Architect	
Tender Security	Tender Security document	Tender Security in the prescribe Amount, Form and Format	
Submitted Tender Document	 ✓ Sequentially serialized ✓ All pages with tenderers entries either typed or 	Prescribed Format	
Note: Only tenderers who fully meet the preliminary evaluation stage requirements shall proceed to technical evaluation. The rest shall stand disqualified.			
B. TECHNICAL EVALUATION			
	History of Non- Performing Contracts, Pending Litigation and Litigation History Attendance of Pre-Tender Site Visit Tender Security Submitted Tender Document I tenderers who fully meet the pre-	History of Non- Performing Contracts, Pending Litigation and Litigation History Attendance of Pre-Tender Site Visit Tender Security Tender Security Tender Security Tender Security Tender Document Submitted Tender Document Submitted Tender Document Attendance of Pre-Tender Site Visit Fill all rates, and amounts, NO Alterations of the Quantities All bidders own Corrections must be Countersigned Sequentially serialized All pages with tenderers entries either typed or hand-written initialized and corrections countersigned Attendance of Pre-Tender Site Meeting Tender Security document Fill all rates, and amounts, NO Alterations of the Quantities All bidders own Corrections must be Countersigned All pages with tenderers entries either typed or hand-written initialized and corrections countersigned	Qualification Subject Qualification Requirement Completed/provided byTenderer History of Non- Performing Contracts, Pending Litigation and Litigation History Meets Post qualification and Contract ward (ITT 39) conditions set out in the Evaluation and Qualification Criteria 7 (iv) (a-c) Duly filled and signed self-declaration Form CON-2 Attendance of Pre-Tender Site Visit Attend Pre-Tender Site Meeting Certificate of Pre-Tender Site Visit duly signed by the Project Architect Tender Security Tender Security document Tender Security in the prescribe Amount, Form and Format V Tape-Bound Tender Document Fill all rates, and amounts, NO Alterations of the Quantities NO Alterations of the Quantities V All bidders own Corrections must Countersigned Sequentially serialized Tender Document in the Prescribed Format V tenderers who fully meet the preliminary evaluation stage requirements shall proceed to technical evaluation. The rest stage of the properties of the proper

1.	Financial Capabilities	(i) The Tenderer shall demonstrate that it has	1. Dully filled Form FIN –
		access to, or has available, liquid assets,	3.1 with proof of
		unencumbered real assets, lines of credit, and other	sources of finances
		financial means (independent of any contractual	which shall be in any of
		advance payment) sufficient to meet the	the following forms:
		construction cash flow requirements estimated as	a. Credit line letter
		Kenya Shillings 1,000,000.00 equivalent for the	from reputable
		subject contract(s) net of the Tenderer's other	bank or financial
		commitments.	institution;
		(ii) The Tenderers shall also demonstrate, to the	b. Overdraft facility
		satisfaction of the Procuring Entity, that it has	from a reputable

Item No.	Qualification Subject	Ouglification Requirement	Documents To be Completed/provided byTenderer	For Procuring Entity's Use (Qualification met orNotMet)
		adequate sources of finance to meet the cash flow requirements on works currently in progress and for future contract commitments. (iii) The tenderer shall provide certified copies of Audited accounts (Signed by Auditors and directors) for the last three (3) years (2021,2022 and 2023) (Certified by an advocate).	or manufuctures	
2.	Average Annual Construction Turnover	Minimum average annual construction turnover of Kenya Shillings 5,000,000.00 equivalent calculated as total certified payments received for contracts in progress and/or completed within the last 5 years, divided by 5 years	Duly filled and signed Form FIN – 3.2	
3.	General Construction Experience	Experience under construction contracts in the role of prime contractor, JV member, subcontractor, or management contractor for at least the last 10 years, starting 1st January 2014	Duly filled and signed Form EXP – 4.1	
4.	Specific Construction & Contract Management Experience	A minimum number of <i>Three</i> similar contracts specified below that have been satisfactorily and substantially completed as a prime contractor, joint	certificates.	

Item No.	Qualification Subject	Qualification Requirement	Completed/provided	For Procuring Entity's Use (Qualification met orNotMet)
		selected from the options mentioned in ITT 35.4] The similarity of the contracts shall be based on the following: (Refurbishments and partitioning works with electrical and mechanical works)		
5.	Directors' qualifications	At least one of the directors to have a degree/diploma in relevant engineering field with a minimum of 10 years relevant experience. NOT APPLICABLE	Academic certificates and curriculum vitaes	
	Contractor's Representative and Key Personnel	Curriculum Vitae (CVs) of the Proposed Key Staff must be presented in the provided format and duly signed by the proposed individual together with their Academic Certificates.	Duly filled and signed Forms PER. 1and PER. 2	
		The site staff shall possess minimum levels set below;		
6.		Site Supervisor	At least a diploma in mechanical engineering or related field with a minimum of 10 years relevant experience.	
			Technicians with a certificate in relevant field with a minimum of 5 years relevant experience; Artisans with a trade test certificate in relevant field	•
			with a minimum of 8 years relevant experience.	
7.	Contractors key tools and equipment		Equipment/Transport: 1 At least 1No. relevant means of transport (Vehicle)	

Item No.	Qualification Subject	Qualification Requirement	Documents To be Completed/provided byTenderer	For Procuring Entity's Use (Qualification met orNotMet)
		demonstrate proof of ownership ii. For Bidders planning to hire, they shall provide an Active Lease Agreement in Place that can be used	2 Relevant equipment for the works being tendered for	
8.	Proposed methodology	Adequacy and quality of the proposed methodology	Technical approach and methodology Provided a detailed Work Methodology	
			Provided a Methodology on safety during the construction period	
	Responsiveness			

Note: Only tenderers who fully meet the technical evaluation stage requirements shall proceed to financial evaluation. The rest shall stand disqualified.

C) FINANCIAL EVALUATION:

Financial Evaluation shall involve checking of the consistency of tender rates and any arithmetic errors in the submitted tender. Any tender which in the opinion of the procuring entity is seriously front-loaded shall be disqualified. Similarly, arithmetic errors if determined a major deviation that affects the substance of the tender shall also lead to disqualification of the tender. Recommendation for award of Contract shall done to the Lowest Evaluated Tender, subject to Post Qualification Evaluation

D) POST QUALIFICATION EVALUATION:

The procuring entity shall conduct due diligence for the purpose of satisfying itself that the information provided in the lowest evaluated tender is accurate.

The lowest evaluated tender shall be rejected if misrepresentation of information or facts is detected during post qualification evaluation.

SECTION V - SPECIFICATIONS

Notes for preparing Specifications

- Specifications must be drafted to present a clear and precise statement of the required standards of materials, and workmanship for tenderers to respond realistically and competitively to the requirements of the Procuring Entity and ensure responsiveness of tenders. The Specifications should require that all materials, plant, and other supplies to be permanently incorporated in the Works be new, unused, of the most recent or current models, and incorporating all recent improvements in design and materials unless provided otherwise in the Contract. Where the Contractor is responsible for the design of any part of the permanent Works, the extent of his obligations must be stated.
- 2 Specifications from previous similar projects are useful and may not be necessary to re-write specifications for every Works Contract.
- 3. There are considerable advantages in standardizing General Specifications for repetitive Works in recognized public sectors, such as high ways, urban housing, irrigation and water supply. The General Specifications should cover all classes of workmanship, materials and equipment commonly involved in constructions, although not necessarily to be used in a particular works contract. Deletions or addenda should then adapt the General Specifications to the particular Works.
- 4. Care must be taken in drafting Specifications to ensure they are not restrictive. In the Specifications of standards for materials, plant and workmanship, existing Kenya Standards should be used as much as possible, otherwise recognized international standards may also be used.
- 5. The Procuring Entity should decide whether technical solutions to specified parts of the Works are to be permitted. Alternatives are appropriate in cases where obvious (and potentially less costly) alternatives are possible to the technical solutions indicated in tender documents for certain elements of the Works, taking into consideration the comparative specialized advantage of potential tenderers.
- 6. The Procuring Entity should provide a description of the selected parts of the Works with appropriate reference to Drawings, Specifications, Bills of Quantities, and Design or Performance criteria, stating that the alternative solutions shall be at least structurally and functionally equivalent to the basic design parameters and Specifications.
- 7. Such alternative solutions shall be accompanied by all information necessary for a complete evaluation by the Procuring Entity, including drawings, design calculations, technical specifications, breakdown of prices, proposed construction methodology, and other relevant details. Technical alternatives permitted in this manner shall be considered by the Procuring Entity each on its own merits and independently of whether the tenderer has priced the item as described in the Procuring Entity's design included with the tender documents.

GENERAL MECHANICAL SPECIFICATONS

GENERAL MECHANICAL SPECIFICATION

2.0 General

This section specifies the general requirement for plant, equipment and materials forming part of the Sub-contract Works and shall apply except where specifically stated elsewhere in the Specification or on the Contract Drawings.

2.1 Quality of Materials

All plant, equipment and materials supplied as part of the Sub-contract Works shall be new and of first-class commercial quality, shall be free from defects and imperfections and where indicated shall be of grades and classifications designated herein.

All products or materials not manufactured by the Sub-contractor shall be products of reputable manufacturers and so far as the provisions of the Specification is concerned shall be as if they had been manufactured by the Sub-contractor.

Materials and apparatus required for the complete installation as called for by the Specification and Contract Drawings shall be supplied by the Sub-contractor unless mention is made otherwise.

Materials and apparatus supplied by others for installation and connection by the Subcontractor shall be carefully examined on receipt. Should any defects be noted, the Subcontractor shall immediately notify the Engineer.

Defective equipment or that damaged in the course of installation or tests shall be replaced as required to the approval of the Engineer.

2.2 Regulations and Standards

The Sub-contract Works shall comply with the current editions of the following:

- a) The Kenya Government Regulations.
- b) The United Kingdom Institution of Electrical Engineers (IEE) Regulations for the Electrical Equipment of Buildings.
- c) The United Kingdom Chartered Institute of Building Services Engineers (CIBSE) Guides.
- d) British Standard and Codes of Practice as published by the British Standards Institution (BSI)
- e) The Local Council By-laws.
- f) The Electricity Supply Authority By-laws.
- g) Local Authority By-laws.
- h) The Kenya Building Code Regulations.
- i) The Kenya Bureau of Standards

2.3 Electrical Requirements

Plant and equipment supplied under this Sub-contract shall be complete with all necessary motor starters, control boards, and other control apparatus. Where control panels incorporating several starters are supplied, they shall be complete with a main isolator.

The supply power up to and including local isolators shall be provided and installed by the Electrical Sub-contractor. All other wiring and connections to equipment shall form part of this Sub-contract and be the responsibility of the Sub-contractor.

The Sub-contractor shall supply three copies of all schematic, cabling and wiring diagrams for the Engineer's approval.

The starting current of all electric motors and equipment shall not exceed the maximum permissible starting currents described in the Kenya Power and Lighting Company (KPLC) Bylaws.

All electrical plant and equipment supplied by the Sub-contractor shall be rated for the supply voltage and frequency obtained in Kenya, that is 415 Volts, 50Hz, 3-Phase or 240Volts, 50Hz, 1-phase.

Any equipment that is not rated for the above voltages and frequencies shall be rejected by the Engineer.

2.4 Transport and Storage

All plant and equipment shall, during transportation be suitably packed, crated and protected to minimize the possibility of damage and to prevent corrosion or other deterioration.

On arrival at site all plant and equipment shall be examined and any damage to parts and protective priming coats made good before storage or installation.

Adequate measures shall be taken by the Sub-contractor to ensure that plant and equipment do not suffer any deterioration during storage.

Prior to installation all piping and equipment shall be thoroughly cleaned.

If, in the opinion of the Engineer any equipment has deteriorated or been damaged to such an extent that it is not suitable for installation, the Sub-contractor shall replace this equipment at his own cost.

2.5 Site Supervision

The Sub-contractor shall ensure that there is an English-speaking supervisor on the site at all times during normal working hours.

2.6 Installation

Installation of all special plant and equipment shall be carried out by the Sub-contractor under adequate supervision from skilled staff provided by the plant and equipment manufacturer or his appointed agent in accordance with the best standards of modern practice and to the relevant regulations and standards described under Clause 2.03 of this Section.

2.7 Testing

2.7.1 General

The Sub-contractor's attention is drawn to Part 'C' Clause 1.38 of the "Preliminaries and General Conditions".

2.7.2 Material Tests

All material for plant and equipment to be installed under this Sub-contract shall be tested, unless otherwise directed, in accordance with the relevant B.S Specification concerned.

For materials where no B.S. Specification exists, tests are to be made in accordance with the best modern commercial methods to the approval of the Engineer, having regard to the particular type of the materials concerned.

The Sub-contractor shall prepare specimens and performance tests and analyses to demonstrate conformance of the various materials with the applicable standards.

If stock material, which has not been specially manufactured for the plant and equipment specified is used, then the Sub-contractor shall submit satisfactory evidence to the Engineer that such materials conform to the requirements stated herein in which case tests of material may be partially or completely waived.

Certified mill test reports of plates, piping and other materials shall be deemed acceptable.

2.7.3 Manufactured Plant and Equipment – Work Tests

The rights of the Engineer relating to the inspection, examination and testing of plant and equipment during manufacture shall be applicable to the Insurance Companies or Inspection Authorities so nominated by the Engineer.

The Sub-contractor shall give two weeks' notice to the Engineer of the manufacturer's intention to carry out such tests and inspections.

The Engineer or his representative shall be entitled to witness such tests and inspections. The cost of such tests and inspections shall be borne by the Sub-contractor.

Six copies of all test and inspection certificates and performance graphs shall be submitted to the Engineer for his approval as soon as possible after the completion of such tests and inspections.

Plant and equipment which is shipped before the relevant test certificate has been approved by the Engineer shall be shipped at the Sub-contractor's own risk and should the test and inspection certificates not be approved; new tests may be ordered by the Engineer at the Sub-contractor's expense.

2.7.4 Pressure Testing

All pipe work installations shall be pressure tested in accordance with the requirements of the various sections of this Specification. The installations may be tested in sections to suit the progress of the works but all tests must be carried out before the work is buried or concealed behind building finishes. All tests must be witnessed by the Engineer or his representative and the Sub-contractor shall give 48 hours' notice to the Engineer of his intention to carry out such tests.

Any pipe work that is buried or concealed before witnessed pressure tests have been carried out shall be exposed at the expense of the Sub-contractor and the specified tests shall then be applied.

The Sub-contractor shall prepare test certificates for signature by the Engineer and shall keep a progressive and up-to-date record of the section of the work that has been tested.

2.7.5 Shop drawings

Before manufacture or Fabrication is commenced the contractor shall submit Two copies of detailed drawings of all water tanks, fire hose reel pump, water booster pump and any other equipment including their components showing all pertinent information including sizes, capacities, construction details, etc., as may be required to determine the suitability of the equipment for the approval of the Engineer. Approval of the detailed drawings shall not relieve the contractor of the full responsibility of errors or the necessity of checking the drawings himself or of furnishing the materials and equipment and performing the work required by the plans and specifications.

2.8 Colour Coding

Unless stated otherwise in the Particular Specification all pipe work shall be color coded in accordance with the latest edition of B.S 1710 and to the approval of the Engineer or Architect.

2.9 Welding

2.9.1 Preparation

Joints to be made by welding shall be accurately cut to size with edges sheared, flame cut or machined to suit the required type of joint. The prepared surface shall be free from all visible

defects such as lamination, surface imperfection due to shearing or flame cutting operation, etc., and shall be free from rust scale, grease and other foreign matter.

2.9.2 Method

All welding shall be carried out by the electric arc processing using covered electrodes in accordance with B.S. 639.

Gas welding may be employed in certain circumstances provided that prior approval is obtained from the Engineer.

2.9.3 Welding Code and Construction

All welded joints shall be carried out in accordance with the following Specifications:

a) Pipe Welding

All pipe welds shall be carried out in accordance with the requirements of B.S.806.

b) General Welding

All welding of mild steel components other than pipework shall comply with the general requirements of B.S. 1856.

2.9.4 Welders Qualifications

Any welder employed on this Sub-contractor shall have passed the trade tests as laid down by the Government of Kenya.

The Engineer may require to see the appropriate to see the appropriate certificate obtained by any welder and should it be proved that the welder does not have the necessary qualifications the Engineer may instruct the Sub- contractor to replace him by a qualified welder.

PARTICULAR SPECIFICATIONS

FOR

PLUMBING AND DRAINAGE INSTALLATIONS

PART I: PARTICULAR SPECIFICATIONS FOR PLUMBING AND DRAINAGE

5.1 GENERAL

This section specifies the general requirements for plant, equipment and materials forming part of the plumbing and drainage installations.

5.2 MATERIALS AND STANDARDS

5.2.1 Pipework and Fittings

Pipework materials are to be used as follows:

a) Galvanized Steel Pipework

Galvanized steel pipe work up to 65mm nominal bore shall be manufactured in accordance with B.S. 1387 Medium Grade, with tapered pipe threads in accordance with B.S. 21. All fittings shall be malleable iron and manufactured in accordance with B.S. 143.

Pipe joints shall be screwed and socketed and sufficient coupling unions shall be allowed so that fittings can be disconnected without cutting the pipe. Running nipples and long screws shall not be permitted unless exceptionally approved by the Engineer.

Galvanized steel pipe work, 80mm nominal bore up to 150mm nominal bore shall be manufactured to comply in all respects with the specification for 65mm pipe, except that screwed and bolted flanges shall replace unions and couplings for the jointing of pipes to valves and other items of plant. All flanges shall comply with the requirements of B.S. 10 to the relevant classifications contained hereinafter under Section 'C' of the Specification.

Galvanizing shall be carried out in accordance with the requirements of B.S. 1387 and B.S. 143 respectively.

b) Polypropylene Pipes –Random (PP-R) Type 3

PP-R type3 pipe work shall be manufactured in accordance with B.S. 7291part 2001. Dimensions and quality of PP-R Pipes shall be in accordance with DIN 8077 and pipelines in plastics materials joints,

component parts, Installation to be in accordance DIN 16928. Joints and fittings to be in accordance to DIN16962. MW/18

Copper Tubing

All copper tubing shall be manufactured in accordance with B.S. 2871 from C.160 'Phosphorous Deoxidized Non-Arsenical Copper' in accordance with B.S. 1172.

Pipe joints shall be made with soldered capillary fittings and connections to equipment shall be with compression fittings manufactured in accordance with B.S. 864.

Short copper connection tubes between galvanized pipe work and sanitary fitments shall not be used because of the risk of galvanic action.

If, as may occur in certain circumstances, it is not possible to make the connection in any way than the use of copper tubing, then a brass straight connector shall be positioned between the galvanized pipe and the copper tube in order to prevent direct contact.

P.V.C. (Hard) Pressure Pipes and Fittings

All P.V.C. pipes and fittings shall be manufactured in accordance with B.S. 3505: 1968.

Jointing

The method of jointing to be employed shall be that of solvent welding, using the pipe and manufacturer's approved cement. Seal ring joint shall be introduced where it is necessary to accommodate thermal expansion.

Testing

Pipelines shall be tested in sections under an internal water pressure normally one and a half times the maximum allowable working pressure of the class of pipe used. Testing shall be carried out as soon as practical after laying and when the pipeline is adequately anchored. Precautions shall be taken to eliminate all air from the test section and to fill the pipe slowly to avoid risk of damage due to surge.

A.B.S. Waste System

Where indicated on the Drawings and Schedules, the Sub-contractor shall supply and fix A.B.S. waste pipes and fittings. $\frac{MW}{19}$

The pipes, traps and fittings shall be in accordance with the relevant British Standards, including B.S. 3943, and fixed generally in accordance with manufacturer's instructions and B.S. 5572: 1978.

Jointing of pipes shall be carried out by means of solvent welding, the manufacturer's instructions and B.S. 5572: 1978.

Jointing of pipes shall be carried out by means of solvent welding. The manufacturer's recommended method of joint preparation and fixing shall be followed.

Standard brackets, as supplied for use with this system, shall be used wherever possible. Where the building structure renders this impracticable the Sub-contractor shall provide purpose made supports, centers of which shall not exceed one meter.

Expansion joints shall be provided as indicated. Supporting brackets and pipe clips shall be fixed on each side of these joints.

f) PVC Soil System

The Sub-contractor shall supply and fix PVC soil pipes and fittings as indicated on the Drawings and Schedules.

Pipes and fittings shall be in accordance with relevant British Standards, including B.S. 4514 and fixed to the manufacturer's instructions and B.S. 5572.

The soil system shall incorporate synthetic rubber gaskets as provided by the manufacturer whose fixing instructions shall be strictly adhere to.

Connections to WC pans shall be effected by the use of a WC connector, gasket and cover, fixed to suit pan outlet.

Suitable supporting brackets and pipe clips shall be provided at maximum of one metre centres.

The Sub-contractor shall be responsible for the joint into the Gully Trap on Drain as indicated on the Drawings.

5.2.2 Valves

a) Draw-off Taps and Stop Valves (Up to 50mm Nominal Bore)

Draw-off taps and valves up to 50mm nominal bore, unless otherwise stated or specified for attachment or connection to sanitary fitment shall be manufactured in accordance with the requirements of B.S.1010.

b) Gate Valves

All gate valves 80mm nominal bore and above, other than those required for fitting to buried water mains shall be of cast iron construction, in accordance with the requirements of B.S. 3464. All gate valves required for fitting to buried water mains shall be of cast iron construction in accordance with the requirements of B.S.1218.

All gate valves up to and including 65mm nominal bore shall be of bronze construction in accordance with the requirements of B.S. 1952.

The pressure classification of all valves shall depend upon the pressure conditions pertaining to the site of works.

Globe Valves

All globe valves up to and including 65mm nominal bore shall be of bronze construction in accordance with the requirements of B.S.3061.

The pressure classification of all globe valves shall depend upon the pressure conditions pertaining to the site of works.

5.2.3 Waste Fitment Traps

a) Standard and Deep Seal P & S Traps

Where standard or deep seal traps are specified they shall be manufactured in suitable non-ferrous materials in accordance with the full requirements of B.S. 1184.

In certain circumstances, cast iron traps may be required for cast iron baths and in these instances bath traps shall be provided which are manufactured in accordance with the full requirements of B.S.1291.

b) Anti-Syphon Traps

Where anti-syphon traps are specified, these shall be similar or equal to the range of traps manufactured by Greenwood and Hughes Limited, Deacon Works Littleshampton, Sussex, England.

The trade name for traps manufactured by this company is 'Grevak'.

5.2.4 Pipe Supports

a) General

This sub-clause deals with pipe supports securing pipes to the structure of buildings for above ground application.

The variety and type of support shall be kept to a minimum and their design shall be such as to facilitate quick and secure fixings to metal, concrete, masonry or wood.

Consideration shall be given, when designing supports, to the maintenance of desired pipe falls and the restraining of pipe movements to a longitudinal axial direction only.

The Sub-contractor shall supply and install all steelwork forming part of the pipe support assemblies and shall be responsible for making good damage to builders work associated with the pipe support installation.

The Sub-contractor shall submit all his proposals for pipe supports to the Engineer for approval before any erection works commence.

b) Steel and Copper Pipes and Tubes

Pipe runs shall be secured by clips connected to pipe angers, wall brackets, or trapeze type supports. 'U' bolts shall not be used as a substitute for pipe clips without the prior approval of the Engineer.

An approximate guide to the maximum permissible supports spacing in metres for steel and copper pipe and tube is given in the following table for horizontal runs.

Size	Copper Tube	Steel Tube
Nominal Bores	to B.S. 659	to B.S. 1387
15mm	1.25m	2.0m
20mm	2.0m	2.5m
2011111	MW/22	213111

25mm	2.0m	2.5m
32mm	2.5m	3.0m
40mm	2.5m	3.0m
50mm	2.5m	3.0m
65mm	3.0m	3.5m
80mm	3.0m	3.5m
100mm	3.0m	4.0m
125mm	3.0m	4.5m
150mm	3.5m	4.5m

The support spacing for vertical runs shall not exceed one and a half times the distances given for horizontal runs.

c) Expansion Joints and Anchors

Where practicable, cold pipework systems shall be arranged with sufficient bends and changes of direction to absorb pipe expansion providing that the pipe stresses are contained within the working limits prescribed in the relevant B.S. specification.

Where piping anchors are supplied, they shall be fixed to the main structure only. Details of all anchor design proposals shall be submitted to the Engineer for approval before erection commences.

The Sub-contractor when arranging his piping shall ensure that no expansion movements are transmitted directly to connections and flanges on pumps or other items of plant.

The Sub-contractor shall supply flexible joints to prevent vibrations and other movements being transmitted from pumps to piping systems or vice versa.

5.2.5 Sanitary Appliances

All sanitary appliances supplied and installed as part of the Sub-contract works shall comply with the general requirements of B.S. Code of Practice 305 and the particular requirements of the latest B.S. Specifications.

5.2.6 Pipe Sleeves

Main runs of pipework are to be fitted with sleeves where they pass through walls and floors. Generally the sleeves shall be of P.V.C. except where they pass through the structure, where they shall be mild steel. The sleeves shall have 6mm - 12mm clearance all around the pipe or for insulated pipework all around the installation. The sleeve will then be packed with slag wool or similar.

5.3 INSTALLATION

5.3.1 General

Installation of all pipework, valves, fittings and equipment shall be carried out under adequate supervision from skilled staff to the relevant codes and standards as specified herein. The Subcontractor shall be responsible to the Main Contractor for ensuring that all builders work associated with his piping installation is carried out in a satisfactory manner to the approval of the Engineer.

5.3.2 Above Ground Installation

a) Water Services

Before any joint is made, the pipes shall be hung in their supports and adjusted to ensure that the joining faces are parallel and any falls which shall be required are achieved without springing the pipe.

Where falls are not shown on the Contract. Drawings or stated elsewhere in the Specification, pipework shall be installed parallel to the lines of the buildings and as close to the walls, ceilings,

columns, etc., as is practicable.

All water systems shall be provided with sufficient drain points and automatic air vents to enable them to function correctly.

Valves and other user equipment shall be installed with adequate access for operation and maintenance. Where valves and other operational equipment are unavoidably installed beyond normal reach or in such position as to be difficult to reach from a small step ladder, extension spindles with floor or wall pedestals shall be provided.

Screwed piping shall be installed with sufficient number of unions to facilitate easy removal of valves and fittings, and to enable alterations of pipework to be carried out without the need to cut the pipe.

Full allowances shall be made for the expansion and contraction of pipework, precautions being taken to ensure that any force produced by the pipe movements are not transmitted to valves, equipment or plant.

All screwed joints to piping and fittings shall be made with P.T.F.E. tape.

The test pressure shall be maintained by the pump for about one hour and if there is any leakage, it shall be measured by the quantity of water pumped into the main in that time. A general leakage of 4.5 litres per 25mm of diameter, per 1.6 kilometres per 24 hours per 30 metres head, may be considered reasonable but any visible individual leak shall be repaired.

b) Sanitary Services

Soil, waste and vent pipe system shall be installed in accordance with the best standard of modern practice as described in B.S. 5572 to the approval of the Engineer.

The Sub-contractor shall be responsible for ensuring that all ground waste fittings are discharged to a gully trap before passing to the sewer via a manhole.

The Sub-contractor shall provide all necessary rodding and inspection facilities within the draining system in positions where easy accessibility is available.

Where a branch requires rodding facilities in a position to which normal access is unobtainable, then that branch shall be extended so as to provide a suitable purpose made rodding eye in the nearest adjacent wall or floor to which easy access is available.

The vent stacks shall terminate above roof level and where stack passes through roof, a weather skirt shall be provided. The Sub-contractor shall be responsible for sealing the roof after installation of the stacks.

The open end of each stack shall be fitted with a plastic coated or galvanised steel wire guard.

Access for rodding and testing shall be provided at the foot of each stack.

Sanitary Appliances

All sanitary appliances associated with the Sub-contract works shall be installed in accordance with the best standard of modern practice as described in C.P. 305 to the approval of the Engineer.

5.4 TESTING AND INSPECTION

5.4.1 Site Tests – Pipework Systems

a) Above Ground Internal Water Services Installation

All water service pipe system installed above ground shall be tested hydraulically for a period of one hour to not less than one and half times to design working pressure.

If preferred, the Sub-contractor may test the pipelines in sections. Any such section found to be satisfactory need not be the subject of a further test when system has been completed, unless specifically requested by the Engineer.

During the test, each branch and joint shall be examined carefully for leaks and any defects revealed shall be made good by the Sub-contractor and the section re-tested.

The Sub-contractor shall take all necessary precautions to prevent damage occurring to special valves and fittings during the tests. Any item damaged shall be repaired or replaced at the Sub-contractor's expenses.

b) Above Ground Soil Waste and Ventilation System

All soil, waste and ventilating pipe system forming part of the above ground installation, shall be given appropriate test procedures as described in B.S. 5572, 1972.

Smoke tests on above ground soil, waste and ventilating pipe system shall not be permitted.

Pressure tests shall be carried out before any work which is to be concealed is finally enclosed.

In all respects, tests shall comply with the requirements of B.S. 5572.

5.4.2 Site Test – Performance

Following satisfactory pressure test on the pipework system operational tests shall be carried out in accordance with the relevant B. S. Code of practice on the systems as a whole to establish that special valves, gauges, control, fittings, equipment and plant are functioning correctly to the satisfaction of the Engineer.

All hot water pipework shall be installed with pre-formed fibre glass lagging to a thickness of 25mm where the pipe runs above a false ceiling or in areas where the ambient temperature is higher than normal with the result that pipe "sweating", due

to condensation will cause nuisance.

All lagged pipes which run in a visible position after erection shall be given a canvas cover and prepared for painting as follows:

Apply a coating of suitable filler until the canvas weave disappears and allow to dry.

Apply two coats of an approved paint and finish in suitable gloss enamel to colors approved by the Engineer.

All lagging for cold and hot water pipes erected in crawlways, ducts and above

false ceiling which after erection are not visible from the corridors of rooms, shall be covered with a reinforced aluminium foil finish banded in colours to be approved by the Engineer.

In all respects, unless otherwise stated, the hot and cold water installation shall be carried out in accordance with the best standard of modern practice and described in C.P.342 and C.P.310 respectively to the approval of the Engineer. $_{MW/28}\,$

The test pressure shall be applied by means of a manually operated test pump or, in the case of long main or mains of large diameter, by a power driven test pump which shall not be left unattended. In either case precautions shall be taken to ensure that the required pressure is not exceeded.

Pressure gauges should be recalibrated before the tests.

The Sub-contractor shall be deemed to have included in his price for all test pumps, and other equipment required under this specification.

The test pressure shall be one and a half times the maximum working pressure except where a pipe is manufactured from a material for which the relevant B.S. specification designates a maximum test pressure.

5.5 STERILISATION OF COLD WATER SYSTEM

All water distribution system shall be thoroughly sterilised and flushed out after the completion of all tests and before being fully commissioned for handover.

The sterilisation procedures shall be carried out by the Sub-contractor in accordance with the requirements of B.S. Code of Practice 301, Clause 409 and to the approval of the Engineer.

PARTICULAR SPECIFICATIONS FOR AIR CONDITIONING SYSTEMS

3.0 SCOPE OF WORKS

The works to be carried out comprises of the supply, delivery, installation, setting to work, testing and commissioning of all materials and equipment called for in this specification and/or shown in the contract drawings.

The tenderer shall include for all appurtenances and appliances not particularly called for in this specification or on the contract drawings but which are necessary for the completion and satisfactory functioning of the system.

No claim for extra payment shall be accepted from the contractor for non-compliance with the above requirements.

If in the opinion of the tenderer there exists difference between the specification and the contract drawings, the tenderer shall clarify the difference with the engineer before tendering.

The Works to be installed under the contract shall comply with the Ministry of Public Works requirements for contract works under "GENERAL MECHANICAL SPECIFICATION".

3.1 CLIMATIC CONDITIONS

The following climatic conditions apply at the sites of the works and all materials and equipment used shall be suitable for these conditions: -

PARAMETERS	(CONDITIONS) NAIROBI CITY
Maximum mean outdoor dry bulb Temperature, t₀	28°C
Minimum Temperature	11.5°C
Relative Humidity	42% - 94%
Altitude	1687m ASL
Longitude	36° 49′ E
Latitude	01° 17′ S
Max. solar radiation occurs during the month of February	

3.2 SYSTEMS DESIGN DATA

The air-conditioning systems are designed to maintain the following internal conditions with ambient conditions of 28°C DB and 55% RH

Internal Temperature $23 \pm 1^{\circ}$ C Relative Humidity $55 \pm 5^{\circ}$

The equipment described here under covers the specific requirements of equipment to be used for this contractor work and shall be used in conjunction with the accompanying contract drawings. It shall be deemed that the tenderer has based his tender on plant and equipment which is equal in performance to that stated within the specification.

3.3 SPLIT AIR CONDITIONING SYSTEM

This shall be installed in the

The system shall be complete with;

3.4 Indoor wall mounted cooling unit (Evaporator)

Each coil unit shall consist of a cooling coil, air circulating fan, fan-guard and a thermostatic expansion valve. A timer unit shall be mounted in the control panel to both the de-frosting intervals and defrosting periods, both of which shall be variable.

The evaporator unit shall be of capacity as specified under the specified conditions, and shall be of the dry expansion type, and preferably of similar make as that of the condensing units. The unit shall be cassette type, high wall mounted or ceiling mounted as will be specified by the Engineer.

The coil shall be manufactured from seamless copper tubing with aluminium fins mechanically bonded to the tubes.

The panel shall be interlocked such, that on energizing the heater, the compressor, condenser and evaporator fan shall be de-energized and only re-energized when the heater is switched off by an evaporator mounted thermostat. A manual overriding switch shall by-pass the timer switch.

The air-circulating fan shall be manufactured from rigid aluminium sheet and finished in white casing. A drip tray with 25mm diameter connections shall be incorporated in the base of the casing.

The Unit shall be complete with the following:

- 1 No. air purifying filter.
- Built in drain pump to automatically drain water.
- Refrigeration pipe work with flared connections
- Fixing brackets/wall mounting kit/ground mounting kit
- Thermostat to control room temperature
- High- and low-pressure units
- Condensate discharge pipe work in Black PVC, 15mm diameter
- Service access valves
- Voltage Surge Protector

The system shall be suitable for 240V, 1 – Phase, 50Hz power supply

The split air-conditioning system shall be designed to maintain room inside temperature of $23\pm1^{\circ}$ C and relative humidity of $55\pm5\%$.

3.5 Outdoor Units.

The outdoor units shall be installed and mounted on the wall using appropriate and approved mounting brackets. They shall be complete with hermetically sealed compressors. Safety devices shall include overload/surge protection among others.

The unit shall be connected to power provided by others. It shall also be connected to refrigerant piping and control wiring. It shall have adequate charge of refrigerator oil and R-32 refrigerant.

The air conditioning units shall be as York or approved equivalent and shall be provided with approved mounting brackets.

The Unit shall be complete with the following:

- Casing constructed of 18-gauge zinc coated mild steel, zinc phosphate bonderized, coated with oven baked polyester paint and weatherized for outdoor installation. It shall have weep holes on base to allow ease of drainage.
- Hermetically sealed compressor mounted to unit base with rubber isolated hold down bolts, uniform in oil & pressures and shall have internal overload protection.
- Refrigeration pipe work with flared connections
- Distributor with refrigeration control
- Fixing brackets/wall mounting kit/ceiling mounting kit
- Heat exchanger capacity controls
- Precise inverter frequency controls
- New oil returning system (refrigerant oil control system)
- High- and low-pressure units
- An innovation of installation with automatic address settings for indoor units with twin multiplex transmission system of no polarity.
- Condensate discharge pipe work
- Service access valves
- Voltage Surge Protector

3.6 Refrigeration Piping

Refrigerant pipe work shall be approved copper tubing and fittings, and shall be properly sized in conformity with the system manufacturer specifications. Pipework shall be joined together by soldering/brazing and shall be complete with all necessary joints, reducers and accessories.

The Ozone friendly refrigerant flow shall be controlled with either a capillary tube or thermostatic expansion valve. Installation shall be carried out by competent and qualified craftsmen. The Engineer may demand proof of qualifications and experience in installation of refrigeration systems.

Pipe work shall be tested for leaks after installation to the Engineers satisfaction. It shall be properly anchored, insulated and no vibration of pipes shall be allowed during the running of the systems. An electronic leak detector shall be used to test for leaks.

MECHANICAL BILLS OF QUANTITIES

SPECIAL NOTES

- 1. The Bills of Quantities form part of the contract documents and are to be read in conjunction with the contract drawings and general specifications of materials and works.
- 2. The prices quoted shall be deemed to include for all obligations under the subcontract including but not limited to supply of materials, labour, delivery to site, storage on site, installation, testing, commissioning and all taxes (including 16% VAT).
- 3. In accordance with Government policy, 3% Withholding Tax and 6% Withholding VAT shall be deducted from all payments made to the Tenderer, and the same shall be forwarded to the Kenya Revenue Authority (KRA).
- 4. All prices omitted from any item, section or part of the Bills of Quantities shall be deemed to have been included to another item, section or part thereof.
- 5. The brief description of the items given in the Bills of Quantities are for the purpose of establishing a standard to which the sub-contractor shall adhere. Otherwise, alternative brands of equal and approved quality will be accepted.
- 6. Should the sub-contractor install any material not specified here in before receiving written approval from the Project Manager, the sub-contractor shall remove the material in question and, at his own cost, install the proper material.
- 7. The grand total of prices in the price summary page must be carried forward to the Form of Tender for the tender to be deemed valid.
- 8. Tenderers must enclose, together with their submitted tenders, detailed manufacturer's Brochures detailing Technical Literature and specifications on all the equipment they intend to offer.

PROPOSED RENOVATIONS OF CABINET SECRETARY'S OFFICES AT 3RD FLOOR WORKS

BUILDING

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
Α	SANITARY APPLIANCES Supply, deliver, install, test and commission the following sanitary appliances complete with all the accessories including all connections to the services, waste, jointing to water supply overflows, supports and all plugging and screwing to walls and floors. Water Closet (WC) Suite Close-coupled WC suite ('S' or 'P'-trap) in approved colour complete with horizontal outlet to BS 3402 with 7.5 litre valveless low level ceramic cistern and fittings including siphon, 15mm diameter side inlet ball valve, 20mm diameter side overflow, plastic flush bend, dual flush system, inlet connection, chrome-plated lever and Soft close seat and cover with metal top fixed (chrome plated) hinges. All to be as" Duravit D- Neo Rimless" (Horizontal outlet) water closet or equal and	1	No.		
В	approved. Toilet roll holder in Chrome and secured to wall as DALI BM70 or approved equivalent Toilet Brush and Holder	1	No.		
С	Chrome plated steel wall mounted toilet brush holder and brush of approved colour as GROHE "Atrio accessories Tier:G5 Prestige" Model - 40 314 toilet brush set or approved equivalent.	1	No.		
D	Robe Hook Robe hook in Satin Aluminium to be mounted by concealed screws to wall wedges. To be as Twyfords Spectrum 2000 accessories or equal and approved. Full length wall mirror	1	No.		
Е	6mm thick polished plate glass silver backed mirror with bevelled edges, size 2000 x 800mm, Plugged and screwed to wall with 4No. chrome plated dome capped screws. The mirror shall rest against a layer of 5mm thick foam. Shower Cubicle	1	No.		
F	High quality Square shower cubicle of size 900 x 900mm complete with 900 x 1850mm pivot door in chrome plated frame with frosted glass, side panels, 40mm diameter grid waste fitting, frame to be screwed to the wall and sealed to shower using silicon sealant and fixing pack. The enclosure to be as Ideal Standard "Tipica-R" or an approved equivalent. Total Carried forward to the next page	1	No.		

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
	Total Brought forward the previous page				
А	Shower tray Shower tray shall be constructed from microlite ceramic and of overall dimensions 900 x 900 x 150mm high and shall have a 40mm dia chrome plated waste. The shower shall be as "Twyfords Calypso" or approved equivalent Paper Towel Dispensing Unit	1	No.		
В	Stainless steel satin finish flat sheets tissue dispensing unit with a 400 sheets capacity. The unit to have a one piece body with a frontal window to indicate when empty and to be lockable. The dispensing unit to be as 'Mediclinics, DT0106CS' Dustbin	1	No.		
С	Pedal operated dust bin in chrome plated steel wit a capacity of approximately 5 litres to Engineer's approval Soap Dispenser	1	No.		
D	Wall mounted soap dispenser with a capacity of about one litre having a press action soap release mechanism complete with fixing screws. Allow for initial soap supply. As Starmix or approved equivalent. Shower Water Heater	1	No.		
Е	High pressure instant water heater complete with a surge protector, external flow control, auto protection from overheating and ability to work under low pressure as 'Alpha' S-200EP Rainshower series or equivalent. The unit to be supplied complete with shower unit comprising of shower head and holder. Soap Dish	1	No.		
F	Chrome plated single soap dish as <i>DALI MT51</i> or approved equivalent. Soap Tray	1	No.		
G	Double corner ceramic soap tray as DALI FM302 or approved equivalent. Towel Rail	1	No.		
Н	Chrome plated towel rail 600mm long with the rail and brackets as one piece. To be as GROHE "Atrio Accessories Tier:G5 Prestige" model 40 309" or equal and approved. Arabic Shower	1	No.		
I	Chrome plate arabic shower fixed next to the water closet complete with plate wall bracket as cobra , scholsser angle valve or equal and approved .	1	No.		
	Total Carried Forward to Next Page				

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
	Total Brought Forward from Previous Page				
А	Tumbler Holder Tumbler holder with glass as DALI ref BMA42 or approved equivalent. Bathroom Cabinets	1	No.		
В	600 x 450 x 500mm Ececutive Bathroom Cabinet complete with Ceramic wash hand basin, 610x1000x6mm thick polished plate glass silver backed mirror with bevelled edges, and Hansgrohe chrome plated self closing pillar tap to Engineer's approval. Flexible Tubing	1	No.		
С	15mm diameter x 300mm long flexible connectors complete with integral chrome plated angle valve as Cobra or equal and approved. Floor Traps	5	No.		
D	100mm chome plated floor traps and gratings Kitchenette Sink	2	No.		
E	Double bowl, double drainer stainless steel kitchen sink of size 1000 x 600mm as manufactured by ASL. The bowl size to be 430 x 420 x 200mm deep complete with chrome plated 40mm waste fittings, plugs, chain stays, overflow, 1No. 15mm diameter chrome plated sink swivel Mixer, heavy duty plastic bottle trap with 75mm deep seal and chain waste fitting. Kitchen Undersink Heater	1	No.		
F	10 litres capacity undersink instantaneous water heater complete with 3.0kw electric heating element, externally adjustable capillary type thermostat, polyurethane form thermal insulation, corrosion-proof moulding outer casing, mountings, water and electrical connections. The heater shall be as Ariston or approved equivalent with power supply 3.0kw, 240/50Hz. Total Carried Forward to Next Page	1	No.		

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
	Total Brought Forward from Previous Page				
	Gas Built In Hob and Kitchen cooker extract hood				
Α	Width: 60 cm Colour:Stainless steel				
	Installation type: Wall-mounted				
	Operating Mode: Exhaust / Recirculation				
	Total power of the motors: 250 W Type of control setting and signalling devices				
	LED, Low-lift pushbuttons				
	Max. air extraction: 620 m³/h	1	No.		
	Boost position air extraction: 700 m³/h	1	INO.		
	Sound power at max. speed (2010/30/EC) 63 dB				
	Sound power boost (2010/30/EC)				
	68 dB				
	Max. air recirculation: 415 m ³ /h. To be as BOSCH or				
	equal and approved. Gas Built In Hob as to be as				
В	Ariston PPH 75G D/IX 5 or approved equivalent				
Б	Allow for extension of the plumbing and drainage pipe work to accommodate the position of the new fitting	1	No.		
Sub-Total Sanitary Fittings Installation Works for Cabinet Secretary's Office Carried Forward to Collection Page					

SANIT	TARY APPLIANCES -VISITORS' WASHROOM				
Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
A	Supply, deliver, install, test and commission the following sanitary appliances complete with all the accessories including all connections to the services, waste, jointing to water supply overflows, supports and all plugging and screwing to walls and floors. Water Closet (WC) Suite Close-coupled WC suite ('S' or 'P'-trap) in approved colour complete with horizontal outlet to BS 3402 with 7.5 litre valveless low level ceramic cistern and fittings including siphon, 15mm diameter side inlet ball valve,				
	20mm diameter side overflow, plastic flush bend, dual flush system, inlet connection, chrome-plated lever and Soft close seat and cover with metal top fixed (chrome plated) hinges. All to be as" Duravit D- Code" (Horizontal outlet) water closet or equal and approved, with Arabic shower and associated accessories	5	No.		
В	Toilet roll holder in Chrome and secured to wall as DALI BM70 or approved equivalent Toilet Brush and Holder	5	No.		
С	Chrome plated steel wall mounted toilet brush holder and brush of approved colour as GROHE "Atrio accessories Tier:G5 Prestige" Model- 40 314 toilet brush set or approved equivalent.	5	No.		
D	Robe Hook Robe hook in Satin Aluminium to be mounted by concealed screws to wall wedges. To be as Twyfords Spectrum 2000 accessories or equal and approved. Paper Towel Dispensing Unit	5	No.		
E	Stainless steel satin finish flat sheets tissue dispensing unit with a 400 sheets capacity. The unit to have a one piece body with a frontal window to indicate when empty and to be lockable. The dispensing unit to be as 'Mediclinics, DT0106CS' Dustbin	4	No.		
F	Pedal operated dust bin in chrome plated steel wit a capacity of approximately 5 litres to Engineer's approval Soap Dispenser	4	No.		
G	Wall mounted soap dispenser with a capacity of about one litre having a press action soap release mechanism complete with fixing screws. Allow for initial soap supply. As Starmix or approved equivalent.	4	No.		
	Total Carried forward to the next page	ge			

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)	
	Total Brought forward the previous page					
A	Wash hand basin (WHB) Semi pedestal wash basin as Duravit D-Code germshield antibactirial in white ref #231055 with centre tap hole size 545 by 435mm complete with semi pedestal ref #085717 and all accessories and with a single lever chrome basin tap Urinal	4	No.			
В	Urinal set (1bowls) Urinal bowl, with spreader as Twyford "Cliffton" Cat. No.Vc 7002WH complete with top inlet spreader and outlet grating (No.WF 9370XX) and 40mm bottle trap-plastic type (malpine type)Urinal division as Twyford "Cliffton" No. VC8051 WH complete with wall hangers.	2	No.			
С	32mm urinal bowl flush valve for the above urinal bowls complete with, back entry with integral vacuum breaker, non-hold-open features and non-return valve, inlet control stop and wall plate comprising flush valve, bent chrome plated flush pipe and rubber pipe connector. The flush valve to be push button type. The fittings shall be as 'Docol' or equal and approved. Flexible Tubing	2	No.			
D	15mm diameter x 300mm long flexible connectors complete with integral chrome plated angle valve as Cobra or equal and approved. Mirror	12	No.			
E	6mm thick polished plate glass silver backed mirror with beveled edges, size 610 x 450mm, Plugged and screwed to wall with 4No. chrome plated dome capped screws. The mirror shall rest against a layer of 5mm thick foam. Arabic Shower	4	No.			
F	Chrome plate arabic shower fixed next to the water closet complete with plate wall bracket as cobra, scholsser angle valve or equal and approved. Floor Traps	4	No.			
G H	100mm chome plated floor traps and gratings Allow for the plumbing and drainage pipe workand	4	No.			
	associated fittings to accommodate the position of the new fittings.	1	No.			
	Sub-Total Sanitary Fittings Installation Works for Visitors' Washroom Carried Forward to Collection Page					

SANITARY APPLIANCES COLLECTION PAGE					
Item	Description	Amount (Ksh)			
1	Sub-Total Sanitary Fittings Installation Works for Cabinet Secretary's and PS Offices Brought Forward to Collection Page				
2	Sub-Total Sanitary Fittings Installation Works for Visitors' Washroom Brought Forward to Collection Page				
3	Allow for testing and commissioning of the above works to the satisfaction of the project engineer				
	Total for Sanitary Fittings Installation Works Carried Forward to Mechanical Works Summary Page				

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
Α	CABINET SECRETARY'S OFFICE AIR CONDITIONING INSTLLATION WORKS. Split Air Conditioner: Indoor Unit Supply, deliver, install, test and commisioning of a ceiling cassete,(single split) type ceiling mounted air-conditioning indoor unit with the following parameters: - Cooling capacity 18,000 BTU/hr -Air Flow Rate: 9.5m³/min - A wireless remote control - Operating on R134a refrigerant or any other non ozone depleting refrigerant Thermostat to control room temperature - Electrostatic air filter - Ceiling mounting kit - Sound pressure level of 45db(A) - Fan speed control	No.	2		
В	The indoor unit tobe as LG or equal and approved Outdoor Unit Wall mounted outdoor unit capable of supplying one indoor unit at the same time as described in item 'A' above. It shall be mounted on the external wall and be provided with purpose made protective steel angle iron frame complete with anti vibration mountings. The entire system shall be able to start automatically after power failure with a 3 minute delay. The complete unit to be as LG or equal and approved model.	No.	2		
С	Insulated refrigerant pipework.	Lm	40		
D	25mm dia. PVC condensate discharge pipe work.	Lm	60		
E	Power protection unit as Solatek or equal and approved.	No.	2		
F	Allow for sealing and making good of all openings and any other builders work associated with the installation.	Item	1		
G	Allow for all electrical works including wiring and switches from the local isolator	Item	1		
	Sub-total for Cabinet Secretary's Office Air conditioning carried forward to Collection Page	J Insta	llation	Works	

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
Α	CONFERENCE ROOM Split Air Conditioner: Indoor Unit Supply, deliver, install, test and commisioning of a ceiling cassete,(single split) type ceiling mounted air-conditioning indoor unit with the following parameters: Cooling capacity 18,000 BTU/hr -Air Flow Rate: 9.5m³/min - A wireless remote control - Operating on R134a refrigerant or any other non ozone depleting refrigerant Thermostat to control room temperature - Electrostatic air filter - Ceiling mounting kit - Sound pressure level of 45db(A) - Fan speed control The indoor unit tobe as LG or equal and approved model	No.	2		
В	Outdoor Unit Wall mounted outdoor unit capable of supplying one indoor unit at the same time as described in item 'A' above. It shall be mounted on the external wall and be provided with purpose made protective steel angle iron frame complete with anti vibration mountings. The entire system shall be able to start automatically after power failure with a 3 minute delay. The complete unit to be as LG or equal and approved model.	No.	2		
С	Insulated refrigerant pipework.	Lm	40		
D	25mm dia. PVC condensate discharge pipe work.	Lm	60		
Е	Power protection unit as Solatek or equal and approved.	No.	2		
F	Allow Kshs. 150,000 for training and continous proffesional programme for State Department for Public Works Mechanical Engineering Staff	Item	1		
G	Allow for sealing and making good of all openings and any other builders work associated with the installation.	Item	1		
Н	Allow for all electrical works including wiring and switches from the local isolator	Item	1		
	Sub-total for Conference Room Air conditioning Installators forward to Collection Page	ation \	Works	carried	

Item	Description	Qty	Unit	Rate (Kshs)	Amount (Kshs)
A	PRIVATE LOUNGE Split Air Conditioner: Indoor Unit Supply, deliver, install, test and commisioning of a ceiling cassete,(single split) type ceiling mounted air-conditioning indoor unit with the following parameters: Cooling capacity 18,000 BTU/hr -Air Flow Rate: 9.5m³/min - A wireless remote control - Operating on R134a refrigerant or any other non ozone depleting refrigerant Thermostat to control room temperature - Electrostatic air filter - Ceiling mounting kit - Sound pressure level of 45db(A) - Fan speed control The indoor unit tobe as LG or equal and approved model	No.	1		
В	Outdoor Unit Wall mounted outdoor unit capable of supplying one indoor unit at the same time as described in item 'A' above. It shall be mounted on the external wall and be provided with purpose made protective steel angle iron frame complete with anti vibration mountings. The entire system shall be able to start automatically after power failure with a 3 minute delay. The complete unit to be as LG or equal and	No.	1		
_	approved model. Insulated refrigerant pipework.	Lm	20		
C	25mm dia. PVC condensate discharge pipe work.	Lm	50		
E	Power protection unit as Solatek or equal and approved.	No.	2		
F	Allow for sealing and making good of all openings and any other builders work associated with the installation.	Item	1		
G	Allow for all electrical works including wiring and switches from the local isolator	Item	1		
Н	Fittings Approval Allow Kshs. 50,000 for approval factory/showroom visits with project engineer for the selection and approval of all fittings sample. Sub-total for Private Lounge Air conditioning Installation	Item	1	rriod	
	forward to Collection Page	OII VVO	ins ca	i i ieu	

	AIR CONDITIONING INSTALLATION WORKS COLLECTION PAGE	
Item	Description	Amount (Ksh)
1	Sub -total for the Cabinet Secretary's Office Air conditioning Installation Works brought forward to Collection Page	
2	Sub-total for Conference Room Air conditioning Installation Works brought forward to Collection Page	
3	Sub-total for Private Lounge Air conditioning Installation Works brought forward to Collection Page	
4	Allow for testing and commisioning of the above works to the satisfaction of the project engineer	
	Total for Air Conditioning Installation Works Carried Forward to Mechanical Works Summary Page	

MECHANICAL WORKS SUMMARY PAGE		
Item	Description	Amount (Ksh)
1	Total for Sanitary Fittings Installation Works	
2	Total for Air Conditioning Installation Works	
3	Allow for Dismantling & placing in safe custody as directed by the client of all existing equipment, pipework and sanitary fittings which are to be replaced with new ones	
	Total for Mechanical Installation Works Carried Forward to Grand Summary Page	

SCHEDULE OF UNIT RATES

- 1. The tenderer shall insert unit rates against the items in the following schedules and may add such other items as he considers appropriate.
- 2. The unit rates shall include for supply, transport, insurance, delivery to site, storage as necessary, assembling, cleaning, installing, connecting, profit and maintenance in defects liability and any other obligation under this contract.
- 3. The unit rates will be used to assess the value of additions or omissions arising from authorized variations to the contract works.
- 4. Where trade names or manufacturer's catalogue numbers are mentioned in the specification, the reference is intended as a guide to the type of article or quality of material required. Alternative brands of equal and approved quality will be accepted

			RATE
ITEM	DESCRIPTION	UNIT	(Kshs)
1.	Hand drier	No.	
2.	Toilet Roll Holder	No.	
3.	High Wall (Single split AC Unit 18,000BTU/Hr)	No.	
4.	High Wall (Single split AC Unit 24,000BTU/Hr)	No.	
5.	Cassette Type (Single split AC Unit 24,000BTU/Hr)	No.	

TECHNICAL SCHEDULE

- 1. The tenderer shall submit technical schedules for all materials and equipment upon which he has based his tender sum.
- 2. The tenderer shall also submit separate comprehensive descriptive and performance details for all plant apparatus and fittings described in the technical schedules. Manufacturer's literature shall be accepted. Failure to comply with this may have his tender disqualified.
- 3. Completion of the technical schedule shall not relieve the Contractor from complying with the requirements of the specifications except as may be approved by the Engineer.

NB. The tenderer must complete in full the technical schedule. Apart from the information required in the technical schedule, the tenderer MUST SUBMIT LEGIBLE comprehensive manufacturer's technical brochures and performance details for all items listed in this schedule and CLEARLY HIGHLIGHT THE SPECIFIC REQUIRED ITEM ONLY.

		MANUFACTURER	COUNTRY	REMARKS
			OF ORIGIN	(Catalogue No. etc.)
1.	Water Closet (WC) Pan			
2.	WC flush-valve			
3.	Urinal Bowl			
4.	Urinal flush-valve			
5.	Urinal Division			
6.	Wash hand basin			
7.	Basin Tap			
8.	Soap Dispenser			
9.	Paper towel Dispenser			
10.	Stainless steel pedal operated			
	cylindrical bin			
11.	Double Bowl Double Drainer sink			
12.	Under sink heater			
13.	High wall (single split AC unit			
	18,000 BTU/hr)			

Catalogue MUST be attached for all the items in the schedule of material above



PROPOSED REORGANISATION OF 3RD FLOOR, WORKS BUILDING.

ITEM	DESCRIPTION	RATE	AMOUNT (KShs)
	BILL NO.6 - PROVISIONAL SUMS		
	PROVISIONAL SUMS		
	The following provisional items are to be measured on completion of the works and priced in accordance with rates contained in these Bills of Quantities or pro-rata thereto or deducted in whole if not required.		
	Provisional sum for:		
A	Allow a provisional sum of Kenya Shillings Two Million (Ksh. 2,000,000.00) only for contingency sum to be omitted or expended in whole or in part at the discretion of the Project Manager.		2,000,000.00
В	Allow a provisional sum of Kenya Shillings Five Hundred Thousand Only (Ksh. 500,000.00) for Branding Works to be omitted or expended in whole or in part at the discretion of the Project Manager.		500,000.00
	Total Provisional Sums carried to Grand Summary		2,500,000.00



PROPOSED REORGANISATION OF 3RD FLOOR, WORKS BUILDING.

	GRAND SUM	<u>IMARY</u>			
ltem	Description	Page No.	For Tenderer Use Only	For Official Use Only	
			KSHS.	KSHS.	
		PD (0			
Α	PARTICULAR PRELIMINARIES	PP/9			
В	GENERAL PRELIMINARIES	GP/10			
C	builder's works	BW/21			
D	ELECTRICAL WORKS	G/12			
Е	mechanical works	M/50			
F	PROVISIONAL SUMS (Contingencies and Branding Works)	PS/1			
		160 15)			
	GRAND TOTAL CARRIED TO FORM OF TENDER (VAT INCLU	JSIVE)			
	AMOUNT IN WORDS : KENYA SHILLINGS				
	TENDERER'S NAME				
	ADDRESS				
	DATE				
	TENDERER'S SIGNATURE				
	WITNESS'S NAME				
	ADDRESS	•••••			
	DATE				
	WITNESS SIGNATURE				